

## Southern Mindoro Annual Procurement Plan for FY 2024

Code (PAP)	Procurement Project	PMO/End-User	Is this an Early Procurement Activity? (Yes/No)	Mode of Procurement	Schedule for Each Procurement Activity				Source of Funds	Estimated Budget (Php)			Remarks (brief description of Project)
					Advertisement/Posting of IB/REI	Submission/Opening of Bids	Notice of Award	Contract Signing		Total	MOOE	CO	
310305102181000	24EI0068- Widening of Permanent Bridges: Budburan Br. (B00233MR) Along Calapan South Road, Mansalay, Oriental Mindoro	Construction Section	NO	Competitive Bidding	06-Dec-23	27-Dec-23	22-Jan-24	26-Jan-24	GoP	49,000,000.00		49,000,000.00	Widening of 385.88 sq.m. PSCG Br., from 2 lanes to 4 lanes, 2 span 30.10 l.m. Br. Const. of 6.0 l.m. Approach Slab at Approach "A" & "B". PCCP Widening/Carriageway = 0.876 lane km. 3.35m wide, 0.28m thk. Conc. of shoulder = 0.876 lane km. varies width of 0.80 & 2.00m, 0.23m thick. Construction of 191.80 l.m. Retaining Wall with 32 sets Concrete Guardrails. Construction of 148.20 l.m. bank protection works.
320102106941000	24EI0072- Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Banus River Control, Barangay Malayong – Barangay Manguyang Section, Gloria, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	49,000,000.00		49,000,000.00	Construction of Gabion Revetment w/ Sheet Piles at existing gabion revetment of Banus River, Barangay Malayong – Barangay Manguyang Section, Gabion Length = 326.00 L.M., Installation of 5-Layer Gabion 1.00 m x 1.00 m x 2.00 m with Closure at the end of the project. Installation of Sheet Piles 6.00 m. length with 328.02m length of pile cap. Additional one-layer gabion, Length = 44.00 L.M., to existing 5 layer gabion revetment at specified location. See Plan and Details
320102106944000	24EI0076- Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Wasig River Control (Downstream), Barangay Wasig, Mansalay, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	49,000,000.00		49,000,000.00	Construction of Wasig River Control (Downstream), Barangay Wasig, Gabion Length = 300.00 L.M., Installation of 6-Layer Gabion 1.00 m x 1.00 m 2.00 m with Closure at the beginning and end of the project. Construction of Pile Cap 0.60 m x 0.60 m. and Installation of Steel Sheet Piles, Length = 300.30m. Construction of Slope Protection for protection of abutment at the end of section 1. See Plan and Details.
300215104706000	24EI0077- Construction of Lumangbayan PCDG Bridge, Brgy. Lumangbayan, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	49,000,000.00		49,000,000.00	Const. of 238.50sq.m. PSCG Br., 2-Lanes, 1 span, 25.00 L.M. Br. Const. of 6.0 L.M. Approach Slab @ Approaches "A" & "B". Concreting of Approaches (PCCP) = 0.636 Lane Km., 3.05m. wide, 0.23m. thk. Conc. of shoulder = 0.636 Lane Km., width of 1.75m., 0.15 m. thk. Construction of 590.00 L.M. Retaining wall with 80 sets Concrete Guardrails. Construction of 171.47 L.M. Bank protection works. Installation of 37.00 sets of Solar LED Roadway Light.
300221106043000	24EI0080- Construction of Road at Barangay Labasan, Bongabong, Oriental Mindoro, Phase I	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	4,950,000.00		4,950,000.00	Length = 0.476 Lane km (238.0 L.M), Carriageway Width = 5.00 m., Shoulder Width = 1.00 m., See Plans and Details.
300221106044000	24EI0081- Construction of Road at Barangay Labasan, Bongabong, Oriental Mindoro, Phase II	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	4,950,000.00		4,950,000.00	Length = 0.637 Lane km (318.50 L.M), Carriageway Width = 5.00 m., Shoulder Width = 1.00 m., Construction of Retaining Wall 38.75 L.M. @ Right Side. Installation of 1 Line RCPC – 0.61 m dia x 8.00m. Provide S-Type Headwall @ bothsides; See Plans and Details.
300221106047000	24EI0083- Construction of Road at Sitio Highlander, Barangay Banutan, Gloria, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	4,950,000.00		4,950,000.00	Road Length = 0.6844 Lane km, Pavement Width = 5.00 m., Pavement Thickness = 0.23 m., Shoulder Width @ both sides = 1.00 m., Pavement Thickness = 0.23m., See Plans and Details.

300221106045000	24EI0084- Construction of Road at Sitio Riverside, Barangay San Isidro, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	4,950,000.00	4,950,000.00	Total Road Length = 225.0 L.M. (0.450 Lane km.), Pavement Width = 2.50m/lane, Pavement Thickness = 0.23 m. thk.. Construction of Retaining Wall Total Length = 188.00 L.M., Installation of 1-0.90m dia. and 1 -0.60 m dia. RCPC provide S-Type Headwall. Installation of 8 pieces Solar LED Streetlight.
300221106042000	24EI0086- Construction of Road at Sitio Uyao, Bagumbayan, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	4,950,000.00	4,950,000.00	Road Length = 0.8640 Lane km, Pavement Width = 4.00 m., Pavement Thickness = 0.23 m., Gravel Shoulder Width = 0.50 m., Removal and replacement of existing damaged roadway. See Plans and Details.
300226113428000	24EI0096- Construction of Multi – Purpose Building at Brgy. Villa Celestial, Mansalay, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Jan-24	13-Feb-24	22-Feb-24	29-Feb-24	GoP	4,950,000.00	4,950,000.00	Construction of 1 unit Multi-Purpose Building (Covered Court) 18.00m x 30.00m. This includes concreting of column footing, column, footing tie beam, slab, beam and gutter. Fabrication and installation truss, purlins and roofing works. Installation of downspout, catch basin and additional embankment.
320102106943000	24EI0074- Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Madugo I River Control, Barangay Malaya Section, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	30-Jan-24	20-Feb-24	27-Feb-24	05-Mar-24	GoP	49,000,000.00	49,000,000.00	Construction of Concrete Revetment at existing concrete revetment of Madugo I River at both banks, Concrete Revetment Length at Left Bank = 777.00 L.M., Concrete Revetment Length at Right Bank = 745.00 L.M., Total Length of Concrete Revetment 1,522.00 L.M. Installation of 1 line of RCPC 1-1.20mØ x 5.00m with S-type headwall @ left bank at specified location. Installation of 2 lines of RCPC 1-1.20mØ x 10.00m with S-type headwall @ both banks at specified location. Construction of access stairs at left and right banks at specified location. See plan and details.
300221106053000	24EI0089- Construction of Road, Sitio Masagana, Barangay Poblacion, Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	30-Jan-24	20-Feb-24	27-Feb-24	05-Mar-24	GoP	4,950,000.00	4,950,000.00	Length = 0.4522 Lane KM (226.10 L.M.), Carriageway Width, 5.00m; Shoulder Width = 1.00m. Construction of Retaining wall 171.60 L.M.; Installation of 2 Lines – RCPC – 0.61m dia x 8.0m. Provide S-Type Headwall @ Bothside. See Plan and Details.
300221106017000	24EI0108- Construction of Road Brgy. Bangbang, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	30-Jan-24	20-Feb-24	08-May-24	16-May-24	GoP	4,950,000.00	4,950,000.00	Road Length = 0.3540 lane KM, Pavement Width = 5.00m., Pavement Thickness = 0.23m., Shoulder Width @ Both Sides = 1.00 m. Construction of Retaining Wall Bothside Length = 175.75 L.M. Installation of 1 Line RCPC 1-0.610m dia x 8.0m. Provide S Type Headwall Bothside. See Plan and Details.
300226113426000	24EI0091- Construction (Completion) of Multi-Purpose Building at Barangay San Rafael, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	30-Jan-24	20-Feb-24	27-Feb-24	05-Mar-24	GoP	2,970,000.00	2,970,000.00	Construction (Completion) of Multi-Purpose Building (Covered Court). This includes earthworks, reinforced concrete works, construction of bleachers, benches, and male/female toilets, installation of end wall cover, installation of basketball ring, roofing works, and painting works. This also includes electrical works such as installation of lighting fixtures and 2 complete sets of scoreboard.
320102106942000	24EI0071- Construction/Rehabilitation of Flood Mitigation Facilities within Major Basins and Principal Rivers, Construction of Bansud River Control, Barangay Malaya Section, Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	01-Feb-24	22-Feb-24	29-Feb-24	07-Mar-24	GoP	49,000,000.00	49,000,000.00	Construction of Gabion Revetment w/ Sheet Piles at existing gabion revetment of Bansud River, Gabion Length = 289.00 L.M., Installation of 7-Layer Gabion 1.00m x 1.00m x 2.00m with Closure at the beginning and end of the project. Installation of Sheet Piles 6.00m. length with 289.52m length of pile cap. See plan and details.

320102106432000	24EI0073- Construction/Rehabilitation of Flood Mitigation Facilities within Major Basins and Principal Rivers, Construction of Bongabong River Control, Brgy. Morente Section, Bongabong, Oriental Mindoro	Construction Section	NO	Competitive Bidding	01-Feb-24	22-Feb-24	29-Feb-24	07-Mar-24	GoP	96,500,000.00		96,500,000.00	Gabion Length = 560.00 L.M., Installation of 6-Layer Gabion 1.00 mx 1.00 m x 2.00 m with Closure at the beginning of the project. Construction of Pile Cap 0.60 m x 0.60 m. and installation of Steel Sheet Piles, Length = 560.56m. See plan and details.
300221106048000	24EI0085- Construction of Road at Sitio Tagao, Barangay Manihala, Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	01-Feb-24	22-Feb-24	29-Feb-24	07-Mar-24	GoP	4,950,000.00		4,950,000.00	Length = 0.3808 Lane KM (190.40 L.M.), Carriageway Width, 5.00m; Shoulder Width = 1.00m. Construction of open line canal 80.80 L.M.; Construction of Slope Protection 80.80 L.M. See Plan & Details.
300226113443000	24EI0095- Construction of Multi-Purpose Building at Barangay San Roque, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	01-Feb-24	22-Feb-24	29-Feb-24	07-Mar-24	GoP	4,950,000.00		4,950,000.00	Construction of 1 unit Multi-Purpose Building (8.50m x 27.00m) complete, including site preparation (cut and fill)
300226113430000	24EI0097- Construction of Multi-Purpose Building at Conrazon Elementary School, Barangay Conrazon, Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	01-Feb-24	22-Feb-24	29-Feb-24	07-Mar-24	GoP	4,950,000.00		4,950,000.00	Construction of 1 unit Multi-Purpose Building (8.50m x 27.00m) complete, including site preparation (additional 0.60m embankment and partial cutting of trees)
300226113424000	24EI0098- Construction of Multi-Purpose Building at Sitio Balagbag, Barangay Maligaya, Gloria, Oriental Mindoro	Construction Section	NO	Competitive Bidding	01-Feb-24	22-Feb-24	29-Feb-24	07-Mar-24	GoP	14,850,000.00		14,850,000.00	Construction of Multi-Purpose Building (One Storey, 15mx40m). This includes demolition of existing structure and removal of trees This also includes earthworks, reinforced concrete works, installation of metal structures, masonry works, installation of pre – painted rib – type roofing sheet walls and roofing works. Additionally, this also includes finishing works including steel, and wood painting, installation of automatic roll up doors, wood panel doors and installation of windows.
300219102882000	24EI0079- Sustainable Infrastructure Projects Alleviating Gaps (Sipag) - Flood Mitigation Structures Protecting Public Infrastructures/Facilities - Construction of Cavillan River Waterway Enhancement Structure (Nasukob Section), along Sitio Cavillan, Barangay Nasukob, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	30-Jan-24	27-Feb-24	20-Mar-24	01-Apr-24	GoP	29,400,000.00		29,400,000.00	Gabion Length = 183.00 L.M., Installation of 6-Layer Gabion 1.00 m x 1.00 m x 2.00 m with Closure at the beginning and end of the project. Construction of Pile Cap 0.60 m x 0.60 m. and installation of Steel Sheet Piles, Length = 183.26m. See plan and details.
300221106051000	24EI0087- Construction of Road Brgy. San Mariano, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	07-Feb-24	27-Feb-24	20-Mar-24	01-Apr-24	GoP	14,850,000.00		14,850,000.00	Construction of Road, Brgy. San Mariano, Roxas, Road Length (First Section)= 0.7450 Lane KM, Second Section = 0.2606 lane km, 3rd Section = 0.8386 lane km., Total Length = 1.84416 lane km. Pavement Width = 6.10 m., Shoulder Width @ Both Sides = 1.50 m., Pavement Thickness= 0.23 m., Installation of 1 Line RCPC 1 - 0.610 m dia x 10.0 m. Provide S Type Headwall Bothside. See Plan and Details.
300226113422000	24EI0094- Construction (Completion) of Multi-Purpose Building at Sitio Centro, Barangay Marayos, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	07-Feb-24	27-Feb-24	20-Mar-24	01-Apr-24	GoP	2,970,000.00		2,970,000.00	Construction (Completion) of Multi-Purpose Building (Covered Court). This includes earthworks, reinforced concrete works, construction of additional bay (1), fabrication of steel bleachers, installation of end wall cover (front side), installation of basketball ring, rubberized floor paint (basketball court), roofing works, and painting works. This also includes installation of two (2) complete sets of electronic scoreboard

310111100713000	24EI0111- Construction/Upgrading/Rehabilitation of Drainage Along National Roads – Secondary Road – Bongabong – Sagana – Roxas – San Aquilino Rd – K0112+022.00 – K0112+222.00 – K0128+005.00 – K0128+396.00, Bongabong – Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	14-Feb-24	05-Mar-24	25-Jun-24	05-Jul-24	GoP	17,640,000.00	17,640,000.00	Construction/Upgrading/Rehabilitation of Drainage along National Roads – Secondary Road – Bongabong – Sagana – Roxas – San Aquilino Rd – K0112+022.00 – K0112+222.00 (200m B/S); K0128+005.00– K0128+215.00 (210.0m B/S); K0128+215– K0128+278.10 (63.10m L/S); K0128+278.10– K0128+327.30 (49.20m B/S); K0128+327.30– K0128+396.00 (68.70m L/S); Length =1,050.20 L.M., Shoulder Width = 1.50m, 0.15m thk. L=400.0m. Installation of Solar Street Light 5 pcs. See Plan and details.
320102106431000	24EI0075- Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Cawacat River (Downstream), Brgy. Campaasan Section, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	14-Feb-24	05-Mar-24	19-Mar-24	26-Mar-24	GoP	96,500,000.00	96,500,000.00	Construction of Gabion Revetment w/ Sheet Piles at Cawacat River adjacent to the abutment protection of Approach B of Cawacat Bridge (Downstream), Gabion Length=559.00 L.M., Installation of 7-Layer Gabion 1.00 m x 1.00 m x 2.00 m with Closure at the beginning and end of the project. Installation of Sheet Piles 6.00 m length with 559.02m length of pile cap. Installation of 1 line of RCPC 1-0.90M Ø x 8.00M at the abutment protection of 2nd approach of Cawacat Bridge. Provide S-Type Headwalls at Both Ends of RCPC. See plan and details.
300221106046000	24EI0082- Construction of Road at Barangay Manaul, Mansalay, Oriental Mindoro	Construction Section	NO	Competitive Bidding	14-Feb-24	05-Mar-24	19-Mar-24	26-Mar-24	GoP	4,950,000.00	4,950,000.00	Road Length = 0.6056 Lane km, Pavement Width = 5.00 m., Pavement Thickness = 0.23 m., Shoulder Width @ both sides = 1.00 m., Pavement Thickness = 0.23m., Construction of Slope Protection @ Left Side = 12.17 L.M., Right side = 20.0 L.M., See Plans and Details.
300226113429000	24EI0090- Construction (Completion) of Multi-Purpose Building at Barangay Bagong Bayan I, Bongabong Oriental Mindoro	Construction Section	NO	Competitive Bidding	14-Feb-24	05-Mar-24	19-Mar-24	26-Mar-24	GoP	2,970,000.00	2,970,000.00	Completion of Two Storey Multi-Purpose Building. This Includes additional concrete works, plastering, masonry, wood and steel painting, painting of doors, tile works, installation of additional window, door, decorative stone, ceiling works, installation of sewer and cold water line, plumbing fixtures, septic tank, catch basin and electrical works.
300226113423000	24EI0093- Construction (Completion) of Multi- Purpose Building at Sitio Avocado, Barangay Anoling, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	21-Feb-24	12-Mar-24	21-Mar-24	01-Apr-24	GoP	2,970,000.00	2,970,000.00	Completion of Covered Court (Bleachers, Storage Area, and Wall Flashing) This includes earthworks, civil works, masonry painting, steel painting, roofing works, installation and fabrication of steel matting enclosure.
300226113419000	24EI0104- Construction of Multi-Purpose Building, Brgy. Zone 2, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	21-Feb-24	12-Mar-24	21-Mar-24	01-Apr-24	GoP	9,900,000.00	9,900,000.00	Construction of Multi-Purpose Building (Pinamalayan Market). This includes demolition of existing structures, earthworks, soil poisoning, reinforced concrete works such as construction of ground floor columns & second floor perimeter/ intermediate beams, concreting of slab on fill, hall ways, and parking space, construction of ramps and lastly, ground floor masonry works.
300226113425000	24EI0092- Construction (Completion) of Multi-Purpose Building at Barangay Sta. Maria, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	26-Mar-24	08-Apr-24	GoP	2,970,000.00	2,970,000.00	This includes earthworks, demolition of existing obstruction structure, structural reinforced concrete works, plastering works, railings, tile works, painting works, roofing works, plumbing, electrical works and other mechanical works.
300226113416000	24EI0101- Construction of Multi-Purpose Building (Classroom), Cacawan High School, Brgy. Cacawan, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	06-Mar-24	26-Mar-24	12-Apr-24	24-Apr-24	GoP	9,900,000.00	9,900,000.00	Construction of Multi-Purpose Building (Five Classroom with CR -45.00m x 8.50m) complete. This includes site preparation (cutting of trees and embankment)

300226113421000	24EI0106- Construction of Multi-Purpose Building (Municipal Gymnasium), Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	06-Mar-24	26-Mar-24	12-Apr-24	24-Apr-24	GoP	9,900,000.00		9,900,000.00	Construction of Gymnasium Phase I. This includes earthworks, lean concrete, structural reinforced column footing, column, & footing tie beam.
300226113276000	24EI0107- Construction of Multi-Purpose Building, Community College, Brgy. Poblacion, Mansalay, Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	04-Apr-24	08-May-24	16-May-24	GoP	19,800,000.00		19,800,000.00	Completion of Two Storey School building (5 Classrooms and 1 Faculty Room). This includes earthworks, concrete works, masonry works
300226113417000	24EI0102- Construction of Multi-Purpose Building, Poblacion, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	18-Apr-24	03-May-24	13-May-24	GoP	4,950,000.00		4,950,000.00	Construction of 1 unit 2-Storey Multi-Purpose Building (2 10.00m x 11.50m). This includes structural reinforced concrete works, masonry works, plastering works, railings, decorative stones, tile works, wood and steel painting works, ceiling works (partial), roofing works, plumbing and electrical works. Excluding masonry painting works.
300226113414000	24EI0099- Construction of Multi-Purpose Building (Balay Kalinga), Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	07-May-24	28-May-24	31-May-24	13-Jun-24	GoP	29,700,000.00		29,700,000.00	This includes Earthworks (structure excavation, embankment), Reinforced concrete (structural concrete, reinforcing steel, formworks and falseworks), Finishing and other Civil Works (termite control work, storm drainage and sewerage system, plumbing, carpentry and joinery works, hardware, aluminum frame glass door, aluminum glass windows, wooden doors and windows, corrugated roofing, pre-painted metal sheets, ceramic and granite tiles, vinyl floor tiles, cement plaster finish, painting, varnish, masonry works, metal structures), Electrical (conduits, boxes, and fittings, wires and wiring devices, panelboard with main & branch breakers, lighting fixtures)
300226113415000	24EI0100- Construction of Multi-Purpose Building (Balay Aruga), Municipality of Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	07-May-24	28-May-24	31-May-24	13-Jun-24	GoP	19,800,000.00		19,800,000.00	This includes earthworks such as removal of trees, excavation, embankment and gravel fill, reinforced concrete works, installation sliding doors, installation of sliding, fixed and awning windows and installation of wooden doors. This also includes masonry works, tile works and moulding, installation of metal structures, plastering and painting works, ceiling works, installation of reflective insulation, sewer line and plumbing works, roofing works, electrical works and finally mechanical works.
300226113418000	24EI0103- Construction (Completion) of Multi-Purpose Facility, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	07-May-24	28-May-24	31-May-24	13-Jun-24	GoP	9,900,000.00		9,900,000.00	Construction (Completion) of Multi-Purpose Facility (Construction of Senior Citizen's Hall, Indoor Playground, Stall, and Recreational Area). This includes demolition of existing structures, reinforced concrete works, installation of flush doors, installation of awning windows. This also includes masonry works, tile works, installation of metal structures, plastering and painting works, ceiling works, installation of steel railings, installation of sewer line and plumbing works, roofing works, installation of reflective insulation, finishing works, and finally electrical works

300226113420000	24E10105- Rehabilitation of Multi-Purpose Facility, Pinamayanan, Oriental Mindoro (Phase 2)	Construction Section	NO	Competitive Bidding	07-May-24	28-May-24	31-May-24	14-Jun-24	GoP	14,850,000.00	14,850,000.00	14,850,000.00	<p>Rehabilitation of Multi-Purpose Facility, Phase 2 (Pinamayanan Multi-Purpose Hall). This includes demolition of existing structures, reinforced concrete works, installation of double swing doors, installation of fixed and awning windows. This also includes installation of maple flooring, installation of polycarbonate sheets, masonry works, installation of decorative stone, installation of HVLS Fan, tile works, installation of metal structures, plastering and painting works, ceiling works, installation of WPC mouldings, sewer line and plumbing works, roofing works and finally electrical works.</p>
300225102064000	24E10046- Construction of Drainage Canal, Barangay Majiao, Bulacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	20-Oct-23	09-Nov-24	22-Jan-24	26-Jan-24	GoP	4,950,000.00	4,950,000.00	4,950,000.00	<p>Construction of Drainage Canal, Length = 490.00 l.m., Concrete Shoulder Length(for B/S) = 136.0 m/166.40 m., Concrete Shoulder Width = 1.00m/1.50m., RCCP 0.23 mm thk at Road Gap and Reblocking for RCCP installation, Length = 0.0522 lane km, Width = 2.50 m/ lane km., installation of 1-910 RCCPC x 8.00 pcs, provide S-Type Headwall.</p>
310203210484000	24E10109- Concreting of Dayhagan to Ogbot FMR, Brgy. Dayhagan, Bongabong, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	26-Mar-24	05-Apr-24	GoP	29,850,000.00	29,850,000.00	29,850,000.00	<p>Concreting of Dayhagan to Ogbot FMR, Brgy. Dayhagan, Bongabong, Oriental Mindoro, Length = 2.800 Lane KM (1,400.00 L.M.), Carriageway Width, 5.00; Shoulder Width = 1.00m., Construction of Retaining wall, 2,206.56 L.M., Construction of Open Lined Canal, 355.00 L.M. @ Right Side, installation of 1 lined 0.61 dia RCCPC x 10.00m; installation of 6 lined 0.61 RCCPC x 8.00m. See Plan and Details</p>
310203210475000	24E10110- Concreting of Brgy. Pag-asa to Brgy. Conrazon, Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	26-Mar-24	05-Apr-24	GoP	14,925,000.00	14,925,000.00	14,925,000.00	<p>Concreting of Road, Length= 899.00 L.M., (1,798 Lane 0.23 m., Gravel Shoulder Width= 1.00 m., Construction of Retaining Wall, Length- 279.00 L.M. See Plan &amp; Details.</p>
310203210493000	24E10113- Concreting of Brgy. Nabuslot, Pinamayanan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	26-Mar-24	05-Apr-24	GoP	9,950,000.00	9,950,000.00	9,950,000.00	<p>Length = 0.928 Lane KM (464.00 L.M.) Carriageway Width, 5.00; Shoulder Width = varies, Construction of Retaining wall, 928.00 L.M.</p>
310203210500000	24E10114- Concreting of Sitio Amihan, Brgy. San Aquilino FMR, Brgy. San Aquilino, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	26-Mar-24	05-Apr-24	GoP	9,950,000.00	9,950,000.00	9,950,000.00	<p>Concreting of Road, Length= 1,008 Lane Km (504 L.M.), Carriageway Width= 5.00 m., Shoulder Width= varies, Construction of Retaining Wall, 515.05 L.M., installation of 6 lined 0.61 dia. RCCPC x 8.00. See Plan &amp; Details.</p>
310203210494000	24E10115- Concreting of Brgy. Nasucob FMR, Brgy. Nasucob, Bulacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	26-Mar-24	05-Apr-24	GoP	9,950,000.00	9,950,000.00	9,950,000.00	<p>Road Length = 0.536 Lane KM, Pavement Width = 5.00 m., Pavement Thickness=0.23 m., Concrete Shoulder Width @ Both Sides= 1.00 m., Construction of Slope Protection @ Bothside = 48.0 L.M., Construction of Retaining Wall @ Bothside = 268.0 LM, installation of 1 Line RCCPC 1-0.610 m dia x 8.0 m. Provide S Type Headwall Bothside.. See Plan and Details.</p>
310203210495000	24E10116- Concreting of Brgy. San Isidro FMR, Brgy. San Isidro, Bulacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	23-Feb-24	14-Mar-24	05-Apr-24	12-Apr-24	GoP	9,950,000.00	9,950,000.00	9,950,000.00	<p>Concreting of Road, Length= 1,036 Lane Km, Pavement Width= 5.00 m., Pavement Thickness = 0.23m, Shoulder width @ both sides = 1.00m. See Plan &amp; Details.</p>

	24EI0112- Repair/Rehabilitation of Line Canal along CSR K0082+500 – K0082+570, Gloria, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	21-Feb-24	12-Mar-24	15-Mar-24	18-Mar-24	GoP	727,740.09	727,740.09		Replacement of existing damaged line canal = 70 l.m.
	24EI0124- Construction of Rainwater Collector System in Public Facilities, Bongabong – Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	20-Mar-24	11-Apr-24	24-Apr-24	07-May-24	GoP	2,895,000.00	2,895,000.00		Construction of 2m x 2m x2m Concrete Tank
200000100019000	24EI0125- Repair/Maintenance DPWH Building Southern Mindoro DEO Main Building (Materials Testing Laboratory, Commission on Audit, Conference Room and Information Technology Room), Southern Mindoro District Engineering Office, Dangay, Roxas, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	27-Mar-24	16-Apr-24	02-May-24	14-May-24	GoP	3,000,000.00	3,000,000.00		1.) Repair/Maintenance of DPWH Building Main Building (Materials Testing Laboratory, Commission on Audit, Conference Room and Information Technology Room) (replacement of floor tiles, ceiling, roofing, electrical and plumbing works and repainting)
200000100019000	24EI0126- Repair/Maintenance DENR Building Southern Mindoro DEO Main Building, San Mariano, Roxas, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	27-Mar-24	16-Apr-24	02-May-24	14-May-24	GoP	2,500,000.00	2,500,000.00		Repair/Maintenance of DENR Building Main Building, Southern Mindoro DEO Main Building (replacement of tiles, painting of masonry works and of ceiling, replacement of doors and windows)
200000100019000	24EI0127- Repair/Maintenance of DILG Building Bureau of Jail Management & Penology Poblacion, Bansud, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	27-Mar-24	16-Apr-24	02-May-24	14-May-24	GoP	1,750,000.00	1,750,000.00		1.) Repair/Maintenance of DILG Building Bureau of Jail Management & Penology Poblacion, Bansud, Oriental Mindoro.
200000100020000	24EI0128- Repair/Maintenance of San Rafael Revetment, Brgy. San Rafael, Roxas, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	27-Mar-24	16-Apr-24	02-May-24	14-May-24	GoP	5,000,000.00	5,000,000.00		Reconstruction of 5-Layer Gabion Revetment to existing gabion at Bongabong River, San Rafael Section, Gabion Length = 92.00 L.M., Installation of 5-Layer Gabion 1.00 m x 1.00 m x 2.00 m. Installation of 4-Layer Gabion Spurdike with mattress at both sides, Spur Dike Length = 10.00 L.M. See plan and details.
	24EI0129- Repair/Rehabilitation of National Road with Slips and Soil Collapse at CSR K0175+100 – K0175+140 (Tambangan Section), Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	05-Jun-24	25-Jun-24	28-Jun-24	05-Jul-24	GoP	2,077,666.70	2,077,666.70		Construction of Slope Protection Structure along CSR. Construction of Cribwall, Total length, L = 40.00m. Installation of Sheet Piles, 40.00m, H = 4.00m. Construction of Concrete Guard Rails. See Plan and Details.
	24EI0130- Repair/Rehabilitation of Lined Canal along CSR K0179+900 – K0180+000, Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	05-Jun-24	25-Jun-24	28-Jun-24	05-Jul-24	GoP	1,016,669.65	1,016,669.65		Replacement of existing damaged line canal = 100.00 l.m
300105201273000	24EI0131- Construction (Completion) of Evacuation Center, Phase II, Barangay Cacawan, Pinamalayan, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	02-Jul-24	23-Jul-24	31-Jul-24	12-Aug-24	GoP	9,389,450.00	9,389,450.00		Completion of 1 unit building (50.00m x 28.90m) at Cacawan, Pinamalayan, Oriental Mindoro. Completion of finishing works for the Gymnasium, Training Room, Comfort Rooms, Stages and Offices. This includes basketball ring and other finishing works, including masonry and painting works, spandrel and rubber flooring.
	24EI0134- Repair/Maintenance of Roads with Slips, Slope Collapse and Landslide - Secondary Roads, CSR (K0123+150 - K0123+172), Bongabong, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	03-Oct-24	22-Oct-24	22-Nov-24	27-Nov-24	GoP	1,500,000.00	1,500,000.00		Repair/Maintenance of Roads with Slips, Slope Collapse and Landslide. Total Length, L = 22.00 m. Installation of Sheet Piles, 22.00 m, H = 6.00 m. Installation of 4 Layer Gabion 1.00 m x 1.00 m x 2.00 m. See Plan and Details.

	24EI0139- Repair/Maintenance of Damaged Concrete Pavement along CSR K0154+104- K0154+111.5, K0173+900 - K0174+820(int.), MOOECR K0200+850 -K0203+386(int.), Mansalay-Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	02-Dec-24	23-Dec-24	04-Feb-25	14-Feb-25	GoP	3,000,000.00	3,000,000.00		Reblocking of Road 638.18sq.m. (0.28mm thick) at intermittent sections. See Plan and Details.
	24EI0140- Repair/Maintenance of Damaged Concrete Pavement with Slope Protection along MOOECR K0199+600-K0199+636, Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	02-Dec-24	23-Dec-24	04-Feb-25	14-Feb-25	GoP	5,700,000.00	5,700,000.00		Reblocking, 120.6sq.M. (0.28m thk), Paving of Shoulder, 54 sq.m (0.15m thk), S/P-Stone Masonry - 66.77 cu.m. With 6-meter Sheet Piles. See Plan and Details.
	24EI0141- Repair/Maintenance of Lined Canal along CSR K0100+400 - K0100+540, Bongabong, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	02-Dec-24	23-Dec-24	04-Feb-25	14-Feb-25	GoP	2,200,000.00	2,200,000.00		Replacement of existing damaged line canal = 140.00 ln.m
	24EI0142- Repair/Maintenance of Damaged Slope Protection along Calapan South Road, K0121+200 - K0121+270, Brgy. Hagan, Bongabong, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	02-Dec-24	23-Dec-24	04-Feb-25	14-Feb-25	GoP	9,425,325.00	9,425,325.00		Replacement of existing damaged line canal = 140.00 ln.m
	24EI0144- Repair/Maintenance of Damaged Lined Canal along CSR K0177+800 - K0177+900, Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	20-Dec-24	09-Jan-25	04-Feb-25	14-Feb-25	GoP	3,000,000.00	3,000,000.00		Repair/Maintenance of Damaged Lined Canal along CSR K0177+800 - K0177+900 Bulalacao, Length = 100.00 LM. See Plan and Details
	24EI0145- Repair/Maintenance of Damaged Slope Protection along CSR K0161+000-K0161+160, Mansalay, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	20-Dec-24	09-Jan-25	04-Feb-25	14-Feb-25	GoP	5,000,000.00	5,000,000.00		S/P-Structural Concrete -83.82 cu.m. See Plan and Details. With 6-meter Sheet Piles
	24EI0146- Repair/Maintenance of Damaged Slope Protection along CSR K0173+100-K0173+150, Bulalacao, Oriental Mindoro	Maintenance Section	NO	Competitive Bidding	20-Dec-24	09-Jan-25	04-Feb-25	14-Feb-25	GoP	2,000,000.00	2,000,000.00		Stone Masonry - 50 m length. See Plan and Details
300101200001000	24EI0117- Construction of 1-Storey 2-Classroom School Building in Milagrosa National High School, Barangay Milagrosa, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	04-Apr-24	19-Apr-24	03-May-24	GoP	5,970,000.00		5,970,000.00	Complete construction of One Storey 2-Classroom School Building at 9.50m x 18.000m with 2-CR 1.85m x 2.025 including site adaption
300101200001000	24EI0118- Construction of 1-Storey 2-Classroom School Building in Balatasan National High School, Barangay Balatasan, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	04-Apr-24	19-Apr-24	03-May-24	GoP	5,970,000.00		5,970,000.00	Complete Construction of One Storey 2-Classroom School Building 9.50m x 18.00m with 2-CR 1.85m x 2.025m including Site Adaption.
300101200001000	24EI0119- Construction of 1-Storey 2-Classroom School Building in Apnagan Elementary School, Barangay Villa Pagasa, Bansud, Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	04-Apr-24	19-Apr-24	03-May-24	GoP	5,970,000.00		5,970,000.00	Complete Construction of One Storey 2-Classroom School Building 9.50m x 18.00m with 2-CR 1.85m x 2.025m including Site Adaption.
300101200001000	24EI0120- Construction of 1-Storey 4-Classroom School Building in San Vicente High School, Bulalacao, Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	04-Apr-24	19-Apr-24	03-May-24	GoP	12,583,765.00		12,583,765.00	Complete Construction of One Storey 4-Classroom School Building 9.50m x 36.00m CR including Site Preparation.

300101200001000	24EI0121- Construction of 1STY4CL, San Vicente High School, Bulalacao (San Pedro), Oriental Mindoro	Construction Section	NO	Competitive Bidding	15-Mar-24	04-Apr-24	19-Apr-24	03-May-24	GoP	12,935,000.00		12,935,000.00	Complete construction of Two Storey 4-Classroom School Building 9.50m x 36.00m (with stairwell 5m width, steel casement window at rear portion with grilles for the front jalousie windows, fire protection system, overhead tank and cistern). This also includes demolition works and site adaptation works (Hard rock excavation, embankment and cutting of tree.
	24EI0123- Repair of 8 Classrooms, San Mariano ES, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	20-Mar-24	11-Apr-24	08-Aug-24	16-Aug-24	GoP	4,825,000.00		4,825,000.00	Repair and Rehabilitation of School Buildings ( 8 Classrooms: Building 1(1CL, BOD Type), Building 2 (2CL, BLSB), Building 5 (2CL, BOD Type), and Building 6(3CL, Marcos Type)). Building 1 includes removal and replacement of roof along with truss, ceiling, painting of ceiling & electrical works. Building 2 includes removal and replacement of roof along with truss, ceiling, painting of ceiling & electrical works. Building 5 includes removal and replacement of roof along with truss, ceiling, painting of ceiling & electrical works. Lastly, Building 6 includes removal and replacement of roof along with truss, ceiling, painting of ceiling & electrical works.
300101200001000	24EI0122- Construction of 1-Storey 3-Classroom School Building in B.T. Lazaro Memorial School, Barangay San Isidro, Roxas, Oriental Mindoro	Construction Section	NO	Competitive Bidding	24-Apr-24	14-May-24	03-Jan-25	06-Jan-25	GoP	8,955,000.00		8,955,000.00	Complete construction of One Storey 3-Classroom School Building 9.50mx27.00m with site preparation (embankment and cutting of trees)
	24EI0135- Construction/Maintenance of Flood Mitigation Structures and Drainage Systems, Construction of River Control, Sabang River, Sabang, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	29-Oct-24	19-Nov-24	19-Dec-24	23-Dec-24	GoP	48,250,000.00		48,250,000.00	Construction of 6-layer Gabion Revetment w/ Sheet Piles at Sabang River, Gabion Length = 228.00 L.M., Installation of 4-Layer Gabion 1.00mx1.00mx2.00m with Closure at the end of the project. Installation of Sheet Piles 6.00m length with 228.00m length of pile cap. See plan and details.
	24EI0136- Construction of Pula River Control Structure, Barangay Santa Maria Section, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	07-Nov-24	26-Nov-24	27-Dec-24	17-Jan-25	GoP	19,300,000.00		19,300,000.00	Construction of Gabion Revetment w/ Steel Sheet Piles at Pula River Control Structure, Barangay Santa Maria Section, Gabion Length = 84.00 L.M., Installation of 7-Layer Gabion 1.00 m x 1.00 m x 2.00 m with Closure at the end of the project. Installation of Steel Sheet Piles 7.50 m. length with 84.00m length of pile cap. See plan and details.
	24EI0137- Construction /Maintenance of Flood Mitigation Structures and Drainage Systems, Construction of Wasig River Control Structure, Brgy. Villa Celestial, Mansalay, Oriental Mindoro	Construction Section	NO	Competitive Bidding	22-Nov-24	12-Dec-24	17-Dec-24	18-Dec-24	GoP	38,600,000.00		38,600,000.00	Construction of Gabion Revetment w/ Steel Sheet Piles at Wasig River Control Structure, Brgy. Villa Celestial, Gabion Length= 154.00 L.M., Installation of 7-Layer Gabion 1.00m x 1.00m x 2.00m with Closure at the end of 1st section and beginning of 2nd section. Installation of additional 2 layer gabion to existing 5 layer gabion revetment, Length= 166.00 L.M. with closure at the end. Installation of Steel Sheet Piles 6.00m length with 154.00m length of pile cap. See plan and details.
	24EI0138- Construction /Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers Construction of Pula River Control Structure, Barangay Santa Maria Section, Pinamalayan, Oriental Mindoro	Construction Section	NO	Competitive Bidding	29-Nov-24	18-Dec-24	26-Dec-24	02-Jan-25	GoP	19,300,000.00		19,300,000.00	Construction of Gabion Revetment w/ Steel Sheet Piles at Pula River Control Structure, Barangay Santa Maria Section, Gabion Length = 84.00 L.M., Installation of 7-layer Gabion 1.00m x 1.00 m x 2.00m with Closure at the end of the project. Installation of Steel Sheet Piles 6.00m length with 84.00m length of pile cap. See plan and details

	24EI0143- Construction of Tawas River Control, Bongabong, Oriental Mindoro	Construction Section	NO	Competitive Bidding	06-Dec-24	26-Dec-24	04-Feb-25	14-Feb-25	GoP	96,500,000.00		96,500,000.00	Construction of Gabion Revetment w/ Sheet Piles of Tawas River Control, Gabion Length = 578.00 L.M., Installation of 6-Layer Gabion 1.00x1.00mx2.00 with Closure at the beginning and end of the project. Installation of Steel Sheet Piles 6.00m. Length with 578.27m length of pile cap. Installation of 3 lines of RCPC 1-0.90m Ø x 8.00m at specified location. Provide S-Type Headwalls at Both Ends of RCPC. See plan and details.
--	--	----------------------	----	---------------------	-----------	-----------	-----------	-----------	-----	---------------	--	---------------	--

Prepared by:

ALELI DILLY U. MANALAYSAY  
BAC Secretariat

Recommended for Approval by:

EMMANUEL A. MANALAYSAY  
BAC Chairperson

APPROVED:

ANNIELYN E. PADULLO  
Head of the Procuring Entity