

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Estimated Budget Cost			Remarks	
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE		CO
21EID001	Road Widening - Secondary Roads - Bongabong-Sagaia Roxas-San Aguilino Rd - KO115 + 635 - KO116 + 193, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	10-Feb-21	GMA 2021	20,854,358.61		20,854,358.61	Road Widening - Secondary Roads, B53SR (KO115+635 - KO116+193), Road Length = 1,1580 Lane KM, Pavement Width = 3.65m/3.35m both-sides, Pavement Thickness = 0.28m thk. Construction of Covered Lined Canal @ Bothside Length = 550.5 L.M.
21EID002	Road Widening - Secondary Roads - Calapan South Rd - KO104 + 224 - KO104 + 468, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	10-Feb-21	GMA 2021	7,173,600.00		7,173,600.00	Road Widening Total Road Length = 241.00 Lm. (0.488 lane km.), Pavement width = 6.70m, Pavement thickness = 0.28m thk. Construction of Retaining Wall (Stone Masonry), Total Length = 180.0 Lm. Open Lined Canal, Total Length = 200.0 Lm.
21EID003	Off - Carriageway/ Improvement - Secondary Roads - Calapan South Rd - KO102 + 550 - KO102 + 934, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	21-Jun-21	03-Jul-21	GMA 2021	6,764,940.00		6,764,940.00	Road Widening Total Road Length = 241.00 Lm. (0.482 lane km.), Pavement width = 6.10m, Pavement thickness = 0.28m thk. Construction of Retaining Wall (Stone Masonry), Total Length = 410.0 Lm. Extension of 1 line of RCPC 1220m diameter x 3.0m (2 pcs. @ U/S and 1 pc. @ R/S. Provide 5 - Type Headwell.
21EID004	Off - Carriageway/ Improvement - Secondary Roads - Calapan South Rd - KO115 + 000 - KO115 + 301, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	09-Feb-21	GMA 2021	5,012,700.00		5,012,700.00	Off-carriageway Improvement of Secondary Roads, along CSR, KO115+000-KO115+301, Length = 301.00 L.M., Pavement Width = varies (3.35m max), Pavement Thickness = 0.28m thk., Shoulder Width = varies (50m max), Construction of Retaining Wall & Lined Canal @ Right Side = 21.90 L.M., See plans and details.
21EID005	Off - Carriageway/ Improvement - Secondary Roads Along Mindoro Oriental/Occidental East Coastal Rd - KO195 + 000 - KO195 + 545, Bulaclaco, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	24-Jun-21	09-Jul-21	GMA 2021	5,880,000.00		5,880,000.00	Road Length = 1,617.10 sq.m. (258.60 ha.m.), Pavement width = 3.05m, Pavement thickness = 0.28m thk. Construction of Slope Protection), Total Length = 256.10 Lm. Additional 0.90m dia. RCPC - 4 pcs. Provide Headwalls at both-sides. See plans and details.
21EID006	Widening of Permanent Bridges - Dalaphan Br. (B00052MR) Along Calapan South Road, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	18,169,200.00		18,169,200.00	Widening of 151.21 sq.m. RCOPG Br., from 2 lanes to 4 lanes, 1 span 15.54 Lm. Br. Construction of 6.0 Lm. Approach Slab at App. "A" & "B", Upgrading of at App. "A" = 0.0860 lane km, Widening of 0.0950 lane km, 3.35m wide, 0.28m thk. @ App. "A", Widening = 0.03812 lane km, 3.35m wide @ Approach "B", 0.28m thk. Concreting of shoulder = 0.13312 lane km., 2.00m wide, 0.23m thick. Const. of 87.74 Lm. Retaining Wall, Construction of App. Railing = 40 pcs., Lined Canal = 41.61 Lm., Bank Protection = 39.55 Lm., 0.23m thk. Const. of 87.74 Lm. retaining wall, Const. of App. Railing = 40 pcs., Lined Canal = 41.61 Lm., Bank Protection = 39.55 Lm.
21EID007	Construction (Improvement) of Multi-Purpose Building at Barangay Dayhagan, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	11-Feb-21	GMA 2021	990,000.00		990,000.00	Completion of Covered Court (18.00m x 30.00m.) including plain and reinforced concrete works, painting, plumbing and electrical works.
21EID008	Construction of Multi-Purpose Building (Covered Court) Alacadena, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	10-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-purpose building (Covered Court) 18.00m x 30.00m. This includes concreting of column footing, slab column, footing the beam, beam & corbel, gutter and sillings. Fabrication of installation of baseplate, steel trusses, purlins, sagrods and turns buckle and accessories. This also includes roofing works and installation of downspouts demolition of existing concrete slab/obstruction.
21EID009	Construction of Multi-Purpose Building at Barangay Cakewin, Pnamayan, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	11-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-purpose Building (Covered Court) 18.00m x 30.00m. This includes concreting of column footing, slab column, footing the beam, beam & corbel, gutter and sillings. Fabrication of installation of baseplate, steel trusses, purlins, sagrods and turns buckle and accessories. This also includes roofing works and installation of downspouts.
21EID010	Construction of Multi-Purpose Building at Barangay Pamisan Malaki, Pnamayan, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	16-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court) 16.00mx30.00m. This includes concreting of column footing, slab column, footing the beam, beam & corbel, gutter and sillings. Fabrication and installation of baseplate, steel trusses, purlins, sagrods and turns buckle and accessories. This also includes roofing works and installation of downspouts, plastering painting works and demolition works.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - CMW Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21EID011	Construction of Multi-Purpose Building at Barangay Zone 2, Pnamalayen, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	10-Feb-21	GMA 2021	4,950,000.00		4,950,000.00	Construction of 1-unit Building (Brgy. Hall, 8.00m x 10.00m - Phase II). This includes: construction of foundation up to roof slab, including construction of stairs, masonry works, plastering works, doors and windows, rough - ins of plumbing and electrical works. Excluding railings of ramps, on stairs and roof deck, plumbing fixtures, tiling works, painting works.
21EID012	Preventive Maintenance - Secondary Roads - Mindoro Oriental/Occidental East Coastal Rd - K0189 + 000 - K0189 + 482, Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	9,111,935.49		9,111,935.49	Asphalt Overlay 80 mm thick along Mindoro Oriental Occidental East Coastal Road (Net Length 507.01m - (0.6140 Lane km).
21EID013	Preventive Maintenance - Secondary Roads - Mindoro Oriental/Occidental East Coastal Rd - K0201 + 573 - K0201 + 833, Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	5,154,800.00		5,154,800.00	Asphalt Overlay - MOOECR - K0201+573 - K0201+833 Total Road Length = 260 Lm. (0.520 lane Km) including Transitions B/S, Asphalt Thickness = 80.00mm thk, Asphalt Width = 6.10 - 6.70m.
21EID014	Road Widening - Secondary Roads - Bongabong-Sagaya-Roxas-Sn Aquilino Rd - K0118 + 000 - K0118 + 842, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	11-Feb-21	GMA 2021	23,189,590.54		23,189,590.54	Road Length = 1.640 lane km, Pavement width = 3.65m/3.35m, bothside, Pavement thickness = 0.28m thk. Construction of Covered Lined Canal Right Side Length = 530.00 Lm, Left Side Length = 436.00 Lm. Extend 1 line RCPC - 0.50m dia x 3.0m @ Left side, Extend 1 line RCPC - 0.50m dia x 1.0m @ Right side, Provide S - Type Headwall at bothsides.
21EID015	Road Widening - Secondary Roads - Mindoro Oriental/Occidental East Coastal Rd - K0188 + 010 - K0188 + 769, Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	11-Feb-21	GMA 2021	13,817,020.00		13,817,020.00	Road Widening of Secondary Roads, along MOOECR, K0188 + 010 - K0188 + 769.00, Length = 759.00 Lm., Pavement width = varies (3.35m max.), Pavement thickness = 0.28m thk., Shoulder Width = (1.00m), Construction of Retaining Wall @ Left Side, Length = 149.00 Lm., Installation of 1 Line RCPC 1 - 0.90m dia x 8.0m Provide S-Type Headwall @ Bothside. See Plan & Details.
21EID016	Off - Cartageway Improvement - Secondary Roads, MOOECR (K0199 + 000 - K0199 + 598), Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	24-Jan-21	09-Jul-21	GMA 2021	6,349,420.00		6,349,420.00	Widening of 151.21 sq.m. RCDG Br., from 2 lanes to 4 lanes, 1 span 15.54 Lm. Br. Construction of 6.0 Lm. Approach Slab at App. "A" & "B". Upgrading of at App. "X" = 0.0860 lane km. Widening of 0.0950 Lm. 3.35m wide, 0.28m thk. @ App. "A", Widening = 0.03812 lane km. 3.35m wide @ Approach "B", 0.28m thk. Concrete of shoulder = 0.13312 lane km., 2.00m wide, 0.23m thick. Const. of 87.74 Lm. Retaining Wall. Construction of App. Railing = 40 pcs., Lined Canal = 41.61 Lm., Bank Protection = 39.55 Lm., 0.23m thk. Const. of 87.74 Lm. retaining wall, Const. of App. Railing = 40 pcs., Lined Canal = 41.61 Lm., Bank Protection = 39.55 Lm.
21EID017	Construction of Sungai River Control (Upstream), Manila-Vila Pag-as Section, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	16-Feb-21	GMA 2021	29,399,298.34		29,399,298.34	Construction of 0.340 km. (340 Lm.), 7 layers gabions revetment with mattresses.
21EID019	Construction of Multi-Purpose Building at Barangay Malay, Pnamalayen, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	18-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-purpose (Covered Court) 16.00m x 30.00m. This includes: concreting of column footing, slab column, footing the beam, beam & corbel, gutter and sidings. Fabrication and installation of baseplate, steel trusses, purlins, sagrods and turn buckle and accessories. This also includes roofing works and installation of downspouts. Plastering and demolition works.
21EID020	Construction of Multi-Purpose Building at Barangay Panabtan Munt, Pnamalayen, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-purpose Building 9.50m x 22.50m. Construction of Multi - Purpose Building Complete.
21EID022	Preventive Maintenance - Secondary Roads - Calapan South Rd - K0127 + 094 - K0127 + 218, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	5,333,160.00		5,333,160.00	Asphalt Overlay 80mm thick along Calapan South Road - K0127 + 094 - K0127 + 218, Net Length = 124.00 Lm. (0.4960 lane km.)
21EID023	Rehabilitation/Reconstruction of Roads with Slopes, Slope Collapse Landslide - Secondary Roads - Calapan South Rd - K0114+527.80 - K0114+563.00, K0114+600 - K0114+695.60, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	16-Feb-21	GMA 2021	14,993,950.39		14,993,950.39	Rehabilitation of Slope Protection: Area of Crbwall (First Section) at Left Side = 281.60 sq.m. and Construction of Slope Protection: Area of Crbwall (Second Section) at Left Side = 764.80 sq.m., including Installation of Sheet Piles, L = 130.80 m, H = 6.00 m. Road Widening @ Left Side L = 0.1308 lane km, W = 3.35 m., Thickness = 0.28 m., with Concrete Shoulder, W = 1.00 m, 0.15 m. thk., Road Widening @ Right Side L = 0.0956 lane km., W = 3.35 m., Thickness 0.28 m., with Concrete Shoulder W = 2.00m., 0.15 m. thk. Installation of Concrete Guard Rails @ Left Side Number = 37 pcs. See Plan and Details.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - CMI Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21E0024	Road Widening - Secondary Roads - Bongbong-Saguna-Roxas-San Aguilino Rd - KO111 + 333 - KO112 + 074, Bongbong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	10-Feb-21	GMA 2021	21,608,779.18		21,608,779.18	Road Length = 1.4820 lane km, Pavement width = 3.65m, bothside, Pavement thickness = 0.28m thk. Construction of Covered Lined Canal Right Side Length = 741.00 Lm., Left Side Length = 224.50 Lm. Extend 1 line RCPC - 0.50m dia x 4.0m @ Left Side, Extend 1 line RCPC - 0.50m dia x 4.0m @ Right Side, Provide S - Type Headwall at both sides.
21E0025	Road Widening - Secondary Roads - Bongbong-Saguna - Roxas - San Aguilino Rd - KO128 + 808 - KO129 + 059, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	29-Jan-21	09-Jul-21	GMA 2021	8,819,545.96		8,819,545.96	Road Length Left Side = 0.2424 lane km., Road Length Right Side = 0.2424 lane km., Pavement width = 3.05m, bothside, Pavement thickness = 0.28m thk. Construction of Covered Lined Canal Right Side Length = 239.40 Lm., Left Side = 242.40 Lm.
21E0026	Road Widening - Secondary Roads - Calapan South Rd - KO106 + 002.40 - KO106 + 880, Bongbong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	24-Jun-21	12-Jul-21	GMA 2021	19,600,000.00		19,600,000.00	Road Widening Total Road Length = 877.60 Lm. (1,755 lane km.), Pavement width = 3.35m. Pavement thickness = 0.28m thk. Construction of Retaining Wall (Stone Masonry), Total Length = 531.20 Lm. Extension of 1 line RCPC - 0.50m dia x 8.0m (4 pcs. @ L/S and 4 pcs. @ R/S), Provide S - Type Headwall.
21E0027	Construction of Bongbong River Control, Barangay San Jose Section, Bongbong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	16-Feb-21	GMA 2021	24,499,484.73		24,499,484.73	Construction of 0.350 km. (350 m.m.), 6 bays gabions revetment w/ matress.
21E0028	Construction of Pula River Control, Barangay Sabang Section, Mamaslaya, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	10-Feb-21	GMA 2021	48,999,800.98		48,999,800.98	Construction of 0.030 km. (630 Lm.), 6 bays gabions revetment with matress.
21E0029	Construction/Improvement of Multi-Purpose Building at Barangay Don Pedro, Mamaslaya, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	990,000.00		990,000.00	Completion of Covered Court (15 x 30m), including construction of one bay, construction of 11 m bleachers, plastering and painting of existing bleachers, installation of end wall covering at one(1) & installation of downspout and catch basin
21E0030	Construction of Multi-Purpose Building at Barangay Maraski, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	18-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-purpose building (Covered Court) 15.00m x 30.00m. This includes concreting of column footing, slab column, footing the beam, lean & corbel, gutter and sittings. Fabrication and installation of baseplate, steel trusses, purlins, sagrods and turnbuckle and accessories. This also includes roofing works and installation of downspout, plastering and demolition works. And installation of wires, devices, panelboard, conduits, lighting fixture and gouted riprap.
21E0031	Construction of Multi-Purpose Building at Barangay San Isidro, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	15-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit Multi - Purpose Building (Covered Court) 16.00m x 26.40m. This includes concreting of column footing, slab column, footing the beam, lean and corbel, gutter and sittings. Fabrication and installation of baseplate, steel trusses, purlins, sagrods and turnbuckle and accessories. This also includes roofing works and installation of downspout, catch basin, plastering, demolition works and installation of wires, devices, panelboard, conduits, lighting fixture and set of floor clock.
21E0032	Construction of Multi-Purpose Building at Barangay San Vicente, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	15-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit Multi - Purpose Building (Covered Court) 18.00m x 30.00m. This includes concreting of column footing, slab column, footing the beam, lean & corbel, gutter and sittings. Fabrication and installation of baseplate, steel trusses, purlins, sagrods and turnbuckle and accessories. This includes roofing works and installation of downspouts and demolition of existing structure.
21E0033	Construction of Multi-Purpose Building (New Bulacao Public Market), Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	16-Feb-21	GMA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brry. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walk, roughing - ins of plumbing and electrical works. Excluding nailing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0034	Construction/Improvement/Rehabilitation of Drainage along National Roads Secondary Road - Calapan South Road - KO068 + 643 - KO069 + 060, Fumamlaya, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GMA 2021	14,224,364.39		14,224,364.39	Construction / Improvement of Covered Drainage along National Roads - KO068 + 643 - KO069 + 060 @ Left Side Length = 435.0 L.M., KO068+0643 -KO069+047 @ Right Side Length = 422 L.M., Inner Width = 1.20m., Outer Width = 1.50m. Paving of Shoulder Left Side, KO068+643- KO069+360 = Length = 435.0 L.M., KO068+0643-KO069+047 @ Right Side = 422.0 L.M., Thickness = 0.15 m thk. Width = 1.50m.
21E0035	Road Widening - Secondary Roads - Bongbong-Saguna-Roxas-San Aguilino Rd - KO125 + 915 - KO126 + 540, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	11-Jan-21	23-Jun-21	GMA 2021	15,876,000.00		15,876,000.00	Road Widening, Total Road Length = 617.00 Lm. (1,143 lane km.), Pavement Width = 3.35m, 3.30m, 3.65/line, Pavement Thickness = 0.28m thk. Construction of Covered Lined Canal @ R/S L = 617.00 Lm. Construction of Slope Protection (Grouted Riprap), Total Length = 31.50 Lm. Extension of 3 line of RCPC 610mm dia. See Plans and Details.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - CMI Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Estimated Budget Cost			Remarks	
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE		CO
21E0036	Off – Carriageway/ Improvement - Secondary Roads - Calapan South Rd - KO109 + 053 - KO109 + 480, Bongabong, Oriental Mindoro.	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	24-Jun-21	09-Jul-21	GAA 2021	7,203,000.00		7,203,000.00	Total Road Length = 427.00 L.M. (2,604.70 sq.m.), Pavement Width = 3.05m bottoisides, Pavement Thickness = 0.28m thk.
21E0037	Off - Carriageway/ Improvement - Secondary Roads - Calapan South Rd - KO121 + 334 - KO121 + 668, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	15-Feb-21	GAA 2021	4,582,480.00		4,582,480.00	Total Length = 334.00 L.M. (668.00 lane km), Pavement Width = varies (3.05m max.), Pavement Thickness = 0.28m thk., Shoulder Width = varies (0.50m max), Construction of Slope Protection @ Left Side Length = 52.80 L.M. See plans & Details.
21E0038	Widening of Permanent Bridges: Agsalin Br. (B00230M)R) along Calapan South Road, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	16-Feb-21	GAA 2021	26,460,000.00		26,460,000.00	Widening of 257.58sq.m. PSCG Br., from 2-lanes to 4-lanes, 1 span, 27.00 L.M. Br: Const. of 6.0 L.M. Approach Slab @ Approach "A" & "B" Widening of Carriageway = 0.262 lane Km., 3.35m., wide, 0.28m thk. Conc. of Shoulder = 0.276 lane Km., varies width of 0.80' & 2.00 m., 0.23 m. thk., Construction of 266.00 L.M. Retaining wall with 62 sets Concrete Guardsrails. Construction of 164.20 L.M. Bank protection Works.
21E0039	Construction of Bongabong River Control, Barangay Luna Section, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	09-Feb-21	GAA 2021	48,999,180.80		48,999,180.80	Construction of 0.352 km. (352 In.m.), 7 layers gabions revetment w/ sheet piles.
21E0040	Construction of Sumagui River Control (Downstream), Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	09-Feb-21	GAA 2021	48,999,048.91		48,999,048.91	Construction of 0.580 km. (350 In.m.), 7 layers gabions revetment w/ mattees.
21E0041	Construction/ Improvement of Access Roads leading to Airports (Kalsada Tungo sa Paliparan) Pnamalayan Airport Road, Pnamalayan, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	11-Feb-21	GAA 2021	19,599,978.50		19,599,978.50	Road Length = 1.277 lane km.), Pavement width = 6.70m., Pavement thickness – 0.28m thk. Paving of Shoulder bottoisides = 0.8386 lane km. @ Second Section. Construction of Open Lined Canal @ Right Side Length = 420.55 Lm., Slope Protection @ Left Side = 420.55 Lm. Extend 1 line RCPC 2 – 1.20m dia. x 1.0m @ bottoiside. Installation of 2 line RCPC 1 - 0.60m dia. x 11.0m. Provide S – Type Headwall Bottoiside.
21E0042	Construction (Improvement) of Multi-Purpose Building at Barangay Campaasan, Bulacasan, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	09-Feb-21	GAA 2021	1,980,000.00		1,980,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0043	Construction of Multi-Purpose Building at Barangay Papandunghin, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	11-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0044	Construction of Multi-Purpose Building at Barangay Sigang, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	26-Feb-21	12-Mar-21	GAA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0045	Construction of Multi-Purpose Building at Barangay Weygan, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	15-Feb-21	GAA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0046	Construction of Pula River Control, Brgy. Sto. Nino Section, Pnamalayan, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	11-Feb-21	GAA 2021	27,119,103.74		27,119,103.74	Construction of 0.240 km. (240 In.m.), concrete revetment w/ sheet piles.
21E0047	Construction/Improvement Access Roads Leading to Declared Tourism Destinations Brgy. Malibay to Brgy. Buong Lupa Leading to Waling Langat Falls, Package II, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	16-Feb-21	GAA 2021	14,699,570.06		14,699,570.06	Construction/Improvement Access Roads Leading to Declared Tourism Destinations Brgy. Buong Lupa Leading to Waling Langat Falls, Road, First Section Road Length = 1.3611 Lane Km, Second Section Road Length = 0.0580 lane km. Pavement Width = 6.10m Pavement Thickness = 0.23m thk. Shoulder Width = 1.0m. Bottoiside. Construction Slope Protection @ Bottoiside Length = 435.0 L.M. Construction of Retaining Wall Length = 69.10 m. Installation of 1 line RCPC – 1.0.60m. x dia x 9.0m.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Estimated Budget Cost			Remarks	
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE		CO
21E0048	Construction/Improvement of Access Roads leading to Declared Tourism Destinations - Internal Access Road to Sibol Palamang, Maribudo leading to Maribudo Waterfalls II, Package II, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	14,700,000.00		14,700,000.00	Construction/Improvement of Access Road to Sibol Palamang, Road Length=419.00 LM, (0.838 Lane Km), Pavement Width = 6.10m, Pavement Thickness = 0.23m, Conc. Shoulder Width = 1.0 m, Construction of Retaining Wall (Stone Masonry) Total Length = 39.0 LM, Construction of Lined Canal @ Bothside Length = 419.0 LM
21E0049	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (TRDP) - NRJ leading to Agasalin Fish Sanctuary, Package II, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	09-Feb-21	GAA 2021	14,698,255.64		14,698,255.64	Construction/Improvement of Access Roads Leading to Declared Tourism Destinations (TRDP) – NRJ leading to Agasalin Fish Sanctuary, Road Length = 2,006.8 Lane Km, Pavement Width = 6.10m bothside, Pavement Thickness = 0.23 mthk, Gravel Shoulder 1.50m, Construction of Slope Protection @ Left Side Length = 74.60 LM @ Right Side Length = 34.60 LM Installation of 1 line RCPC- 1 – 0.90 m. dia x 10.0m, 1 line RCPC- 2 - 0.60m dia x 10.0m, 1 line RCPC- 1 - 0.60m dia x 10.0m. Extended 1 line RCPC- 1 – 0.60m dia, X 4.0 m @ Bothsides, Provide S – Type Headwall Bothsides, Removal of Existing PCCP 14m x 2.5m, 207m x 5.0m (1st section) and 630.80m x 5.0m (second section).
21E0050	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (TRDP) – NRJ leading to Phantom Cave and Bamboo Plantation, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	09-Feb-21	GAA 2021	19,431,440.00		19,431,440.00	Construction/Improvement of Access Roads Leading to Declared Tourism Destinations (TRDP) – NRJ leading to Phantom Cave and Bamboo Plantation, Road Length = 1397.60 Lane Km, (2,795 Lane Km) Pavement Width = 6.10m, Pavement Thickness = 0.23 m. thk. Construction of Slope Protection L= 157.30 LM Installation of 1-line of RCPC 610m diameter x 10.00m provide S-Type headwall
21E0051	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (TRDP) - NRJ leading to Spreading Spring Waters and Mangyan Villages of Hanunuo Tribe, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	9,800,000.00.		9,800,000.00.	Construction of concrete road, Total Road Length = 614 LM, (1.228 lane km.), Pavement width = 6.10m, Pavement thickness = 0.23m thk. Construction of Slope Protection L = 157.30 LM, Installation of 3 lines of RCPC 610mm dia x 10.00m. Provide S – Type Headwall.
21E0052	Construction of Multi-Purpose Building at Barangay Cabugao, Bulakeao, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	26-Feb-21	12-Mar-21	GAA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – in of plumbing and electrical works. Excluding ralling of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0056	Construction of Multi-Purpose Building, Brgy. Mapang, Bengabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	11-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – in of plumbing and electrical works. Excluding ralling of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21E0057	Construction of Popot Creek River Control, Barangay Pag-asu, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	16-Feb-21	GAA 2021	6,928,871.20		6,928,871.20	Construction of 0.300 km. (300 In.m.), concrete revetment.
21E0058	Construction/Improvement Access Roads leading to Declared Tourism Destinations San Roque-San Juan-Tafelma Road, Brgy. San Juan, Bulakeao, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	11-Feb-21	GAA 2021	19,599,849.86		19,599,849.86	Road Length = 1,955.2 Lane Km, Pavement Width = 6.10 m, Pavement thickness = .230 m thk., Shoulder Width = 1.50 m Both side, Construction Slope Protection @ Left Side Length = 541.75 LM, Right Side Length = 78.0 LM, Installation of 5 lines RCPC-1-0.60 m. dia, X 10.0 m. dia, X 10.0 m. line 1 RCPC- 1 - .90 m dia x 10 m, 1 line RCPC- 1-1.20 m dia, x 10.0 m. Provide S – Type headwall on bothsides.
21E0059	Concreting/Improvement of Road from Barangay Malinao To Barangay Roma, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	18-Feb-21	GAA 2021	44,550,000.00		44,550,000.00	Concreting/ Improvement of Road from Barangay Malinao To Barangay Roma, Total Road Length = 3,575.0 LM, (6.170 Lane Km), Pavement Width = 5.00 m, Pavement Thickness = 0.23m. thk. Construction of Slope Protection (Grouted Riprap), Length = 1,138.00 LM, Construction of Retaining Wall (Stone Masonry), Length = 76.00 LM, Installation of RCPC 610mm and 910mm diameter x 8.00m, Provide S – Type Headwall bothsides. See plans and details.
21E0060	Construction (Completion) of Multi-Purpose Building in Bansud Municipal Compound, Barangay Polioction, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	15-Feb-21	GAA 2021	4,950,000.00		4,950,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – in of plumbing and electrical works. Excluding ralling of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21EID061	Construction (Improvement) of Multi-Purpose Building at Barangay Cabahay, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	11-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting, works, doors and windows.
21EID062	Construction (Improvement) of Multi-Purpose Building at Barangay Ilog, Bongbong, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	17-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting, works, doors and windows.
21EID063	Construction (Improvement) of Multi-Purpose Building at Barangay Proper Bansud, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	11-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting, works, doors and windows.
21EID064	Construction of Multi-Purpose Building at Barangay Buong Lupa, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	11-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting, works, doors and windows.
21EID065	Construction of Road at Barangay B. Del Mundo, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	10-Feb-21	GAA 2021	1,979,938.95		1,979,938.95	Construction of Road at Barangay B. Del Mundo, Mansalay, Oriental Mindoro, Road Length = 0.4210Lane KM (210.50 L.M.), Pavement Width = 5.00m, Pavement Thickness = 0.23m, Shoulder Width = 0.50m.
21EID066	Construction of Road at Barangay Kaligasan, Bongbong, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	10-Feb-21	GAA 2021	989,822.15		989,822.15	Construction of Road at Barangay Kaligasan, Bongbong, Oriental Mindoro, Road Length = 0.1880 Lane KM (94.0 L.M.), First Section, Second Section Road Length = 0.0068 Lane KM (3.40 L.M.) Pavement Width = 5.00m, Pavement Thickness = 0.230m, Shoulder Width = 0.50m, Installation of 1 Line RCP1 – 0.060m dia x 8.0m, Provide S Type Headwall Boredpiles. Construction of Slope Protection @ Second Section Left Side = 3.40 L.M.
21EID067	Construction of Road at Barangay Salcedo, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	1,979,758.36		1,979,758.36	Construction of Road at Barangay B. Salcedo, Bansud, Oriental Mindoro Road Length = 0.4166 Lane Km (208.3 L.M.), Pavement Width = 5.00m, Pavement Thickness = 0.23m, Shoulder Width = 0.50m.
21EID069	Widening of Permanent Bridges - Tuguean Br. (B000-091R) along Calapan South Rd., Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	10-Feb-21	GAA 2021	15,533,000.00		15,533,000.00	Widening of 151.21 sqm RCDG BR., from 2-lanes to 4-lanes, 1 span, 15.85 L.M. Br., Construction of 6.0 L.M. Approach Slab at App. A & B. Upgrading of Cartigeway at App. B. = 0.1013 Lane KM, Widening = 0.101200 lane km, 3.65m wide, 0.28m thk. @ App. A, Widening = 0.10103 lane km, 3.35 – 4.35 m wide @ App. B, 0.28m thk. Conc. of Shoulder = 0.1133 lane km, 1.2-2.00m wide, 0.23m thk. Cont. of 111.62 L.M. Retaining wall, Cont. of App. Railing = 32 pcs, Bank protection = 2.95 L.M.
21EID070	Concreting of San Roque - San Juan-Tataram Road Leading to Sugulay Island and Various Beaches, Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	2,969,559.17		2,969,659.17	Road Length =0.4920 Lane KM (246.00 In m.), Pavement Width = 5.00 m, Pavement thickness = 0.230 in thk., Shoulder Width = 0.50 m, Installation of 2 Lines RCP1-1.0-60 m. dia x 8. Ftwide S Type Headwall Boredpiles, Construction Slope of Protection Length= 51.75 L.M.
21EID071	Construction (Improvement) of Multi-Purpose Building at Barangay Panayayan, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	10-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting, works, doors and windows.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date					Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE	CO	
21EIO072	Construction/Improvement of Multi-Purpose Building at Brgy. Pobladon, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21EIO075	Construction of Multi-Purpose Building at Barangay Paligaya, Gbon, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	11-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21EIO078	Construction of Slope Protection Structure (Rerapping) at Barangay Malo, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	1,979,746.87.		1,979,746.87.	Construction of Slope Protection Structure (Rerapping) at Barangay Malo, Bansud, Oriental Mindoro, Slope Protection Length = 80.00 LM.
21EIO079	Construction of Road at Barangay Polisah, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	26-Jan-21	09-Feb-21	GAA 2021	989,982.00		989,982.00	Construction of Road at Barangay Polisah, Bongabong, Oriental Mindoro, Road Length = 0.2830 Lane KM (141.50 LM), Pavement Width = 5.00m, Pavement Thickness = 0.15m, Shoulder Width = 0.50m, Installation of Line RCPC 1.0-60mm x 8.00m. Provide S-type Headwall @ Both Sides, See Plan and Details.
21EIO080	Construction of Road at Sitio Adlaya, Barangay Mansalay, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	15-Feb-21	GAA 2021	989,173.09		989,173.09	Road Length = 0.606 lane km. (60.00 LM), Pavement width = 5.00m, Pavement Thickness = 0.23m, Shoulder Width = 0.50m to 1.50m ave. Construction of 70.0 LM., slope protection. See Plans and Details.
21EIO081	Construction of Road with Drainage Canal at Sitio Palayan, Barangay Pacasan, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	12-Nov-20	09-Dec-20	30-Mar-21	15-Apr-21	GAA 2021	2,969,975.46		2,969,975.46	Road Length = 0.4630 Lane KM (231.50 LM), Pavement Width = 5.00m, Pavement Thickness = 0.23m, Shoulder Width = 0.50m Construction of Open Urd Canal @ Right Side, Length, L= 231.50m, Open U/C Inner Width = 0.40m, Outer Width = 0.70m, Inner Height = varies.
21EIO083	Construction (Improvement) of Multi-Purpose Building at Barangay Pobladon, Bulacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	16-Feb-21	GAA 2021	1,980,000.00		1,980,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21EIO084	Construction (Improvement) of Multi-Purpose Building at Barangay Victoria, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	05-Nov-20	02-Dec-20	26-Jan-21	15-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21EIO085	Construction (Improvement) of Multi-Purpose Building at Sitio Bal-Ong, Barangay San Jose, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	15-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brgy. Hail, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21EIO086	Construction of Road at Barangay Malibos, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of Road, Total Road Length = 83.30 LM. (0.167 lane km.), Pavement width = 5.00m, Pavement thickness = 0.23m, Conc. Shoulder width = 0.50m.
21EIO087	Construction of Road at Barangay Ogbot, Bongabong, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	10-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of Road, Total Road Length = 83.30 LM. (0.167 lane km.), Pavement width = 5.00m, Pavement thickness = 0.23m, Conc. Shoulder width = 0.50m.
21EIO088	Construction of Road at Sitio Bungaluan, Barangay Bato, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	1,979,869.24		1,979,869.24	Construction of Road, Total Road Length = 83.30 LM. (0.167 lane km.), Pavement width = 5.00m, Pavement thickness = 0.23m, Conc. Shoulder width = 0.50m.
21EIO089	Construction of Road at Sitio Naalin to Sitio Butana, Barangay Bonhon, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	990,000.00.		990,000.00.	Construction of Road, Total Road Length = 83.30 LM. (0.167 lane km.), Pavement width = 5.00m, Pavement thickness = 0.23m, Conc. Shoulder width = 0.50m.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - CIVIL WORKS

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21ED0092	Widening of Permanent Bridge: Labasan Br. (B00033MR) along Calapan South Road, Bongbong, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	16-Feb-21	GAA 2021	18,502,400.00		18,502,400.00	Widening of 180.32 sq.m RCDG Br. From 2-Lanes to 4-Lanes, 1 span, 18.88 LM Br. Construction of 6.0 LM Approach Slab at App. "A & B", widening = 0.187 Lane Km., 3.65m wide, 0.28m thk @ App "X" Widening = 0.0357 Lane Km., 3.35 wide @ App "B" 0.28m thk. Conc. Of Shoulder = 0.2050 Lane Km., 2.00m wide, Const. Of 185.08 LM Retaining Wall and Const of App Railing = 53 pcs.
21ED0093	Construction of Multi-Purpose Building at Barangay San Francisco, Bulacacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	26-Feb-21	12-Mar-21	GAA 2021	3,960,900.00		3,960,000.00	Construction of 1 unit 2 storey building (Brig. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED0095	Construction of Multi-Purpose Building at Barangay Masubob, Bulacacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	26-Feb-21	12-Mar-21	GAA 2021	3,960,900.00		3,960,000.00	Construction of 1 unit 2 storey building (Brig. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED0096	Construction of Multi-Purpose Building, Barangay Kanat, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	20-Nov-20	10-Dec-20	26-Jan-21	10-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brig. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED0098	Concrete of Road from Silo Fatima to Silo Duong, Barangay Kanat, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	2,969,201.32		2,969,201.32	Concrete of Road, Total Road Length = 83.30 Lm. (0.167 line km.), Pavement width = 5.00m, Pavement thickness = 0.23m. Conc. Shoulder width = 0.50m.
21ED100	Concrete of Road, Silo Malanig, Barangay Sacedo, Bannud, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	2,969,719.90		2,969,719.90	Concrete of Road, Total Road Length = 83.30 Lm. (0.167 line km.), Pavement width = 5.00m, Pavement thickness = 0.23m. Conc. Shoulder width = 0.50m.
21ED101	Concrete of San Roque - San Juan - Tarama Road leading to Sigulay Island and Various Beaches, Phase II, Bulacacao, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	4,949,711.03		4,949,711.03	Concrete of Road, Total Road Length = 83.30 Lm. (0.167 line km.), Pavement width = 5.00m, Pavement thickness = 0.23m. Conc. Shoulder width = 0.50m.
21ED102	Widening of Permanent Bridges - Quinsagan Br. (B00033MR) along Calapan South Rd., Pnamalayau, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	15-Feb-21	GAA 2021	30,046,800.00		30,046,800.00	Widening of 292.50 sq.m, RCDG Br., 2-Lane to 4-Lane, 1 Span, 30.66 LM. Br., Construction of 6.0 LM Approach Slab at App. "A&B", Widening=0.0329 Lane Km., 3.65m wide, 0.28m thk. @App "X", Widening = 0.0227 Lane Km., 3.65 wide @App "B" 0.28m Thk. Cons. Of Shoulder = 0.1147 Lane Km, 2.00m wide, Const. of 69.58 LM Retaining wall, Const. of App. Railing = 20 pcs & Blank Protection = 194.66 LM.
21ED104	Construction (Improvement) of Multi-Purpose Building at Barangay Dangay, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	01-Dec-20	22-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	990,000.00		990,000.00	Construction of 1 unit 2 storey building (Brig. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED105	Construction of Multi-Purpose Building (Disaster Response Management Facility) at Barangay Philiprayn, Gloria, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	18-Feb-21	GAA 2021	4,950,000.00		4,950,000.00	Construction of 1 unit 2 storey building (Brig. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED106	Rehabilitation of Multi-Purpose Building at Barangay Sumagui, Bansud, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	29-Jan-21	17-Feb-21	GAA 2021	1,980,000.00		1,980,000.00	Construction of 1 unit 2 storey building (Brig. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing - ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Estimated Budget Cost			Remarks	
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE		CO
21ED107	Construction of Multi-Purpose Building (Lunelood Center), Barangay Santa Teresita, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED108	Construction of Multi-Purpose Building, Brgy. San Isidro, Roxas, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	18-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED109	Concreting/Improvement of Road from Barangay Mahinang to Barangay Roma, Phase II, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	08-Dec-20	29-Dec-20	27-Jan-21	15-Feb-21	GAA 2021	2,970,000.00		2,970,000.00	Concreting of Road, Total Road Length = 83.30 Lm. (0.167 lane km.), Pavement width = 5.00m, Pavement thickness = 0.23m. Conc. Shoulder width = 0.50m.
21ED110	Construction of Concrete Road and Construction (Completion) of Bailey Bridge, Barangay Weygan, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	28-Dec-20	19-Jan-21	29-Jan-21	18-Feb-21	GAA 2021	10,935,000.00		10,935,000.00	Completion of 2-span (12 Pansib) Bailey bridge with steel deck. Concreting of = 1.6302 Lane Km., 3.05m. wide, 0.23m thk. with slope protection & concrete guardrail =104.00 sets. Construction of 2-barrel 3.00m x 3.00m x 8.00 box culvert with wingwall & apron. Installation of 6-lines 0.90m dia. X 8.00m RCPC with Headwall bothside. Construction of Abutment/Bank Protection = 59.60L.M.
21ED111	Construction of Road, Sibot Camacawa, Barangay Ranzo, Phamarsayan, Oriental Mindoro	Construction Section	Yes	Public Bidding	15-Dec-20	07-Jan-21	26-Feb-21	12-Mar-21	GAA 2021	2,969,812.97		2,969,812.97	Road Length = 720.00 lane km. (720.00 Lm.), Pavement Width = 2.50m, Pavement Thickness = 0.15m thk. Shoulder Width = 0.50m. Installation of 3 lines RCPC 1 – 0.60m dia. x 4.00m. Provide S – Type Headwall @ Bothsides. See Plans and Details.
21ED112	Construction of Road, Sibot Hagines-Matara, Barangay Masag, Mansalay, Oriental Mindoro	Construction Section	Yes	Public Bidding	26-Nov-20	16-Dec-20	27-Jan-21	10-Feb-21	GAA 2021	9,900,000.00		9,900,000.00	Construction of Road, Sibot Hagines – Matara, Total Road Length = 868.00 L.M.(1.736 Lane Km), Pavement Width = 5.00m, Pavement Thickness = 0.23m. Installation of 2 – line of RCPC 610mm diameter x 7.00m & 1 – line of RCPC 1220mm diameter x 7.00m. Provide S- type headwall
21ED118	Construction of Multi-Purpose Building at Barangay Bagong Slat, Bulalacao, Oriental Mindoro.	Construction Section	No	Public Bidding	27-Jan-21	16-Feb-21	24-Feb-21	11-Mar-21	GAA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED119	Construction Multi-Purpose Building at Barangay Masin, Bulalacao, Oriental Mindoro.	Construction Section	No	Public Bidding	27-Jan-21	16-Feb-21	24-Feb-21	11-Mar-21	GAA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED120	Construction of Multi-Purpose Building at Barangay Milagroa, Bulalacao, Oriental Mindoro	Construction Section	No	Public Bidding	27-Jan-21	16-Feb-21	24-Feb-21	11-Mar-21	GAA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.
21ED121	Concreting of Brgy. Anila Road, Bongabong, Oriental Mindoro.	Construction Section	No	Public Bidding	27-Jan-21	16-Feb-21	24-Feb-21	12-Mar-21	GAA 2021	10,395,000.00		10,395,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8,00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – ins of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting works, doors and windows.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21E0122	Construction of Multi-Purpose Building, Brgy. San Isidro, Bulacao, Oriental Mindoro	Construction Section	No	Public Bidding	27-Jan-21	16-Feb-21	24-Feb-21	12-Mar-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit 2 storey building (Brgy. Hall, Phase 1) 2 - 8.00mx10.00m. This includes construction of foundation up to second floor slab, including construction of stairs, exterior walls, roughing – in of plumbing and electrical works. Excluding railing of ramps and stairs, inside partition except comfort room, plumbing fixtures, tiling works, plaster and painting, works, doors and windows.
21E0123	Construction of Multi-Purpose Building at Barangay Sibang, Pannalayan, Oriental Mindoro	Construction Section	No	Public Bidding	27-Jan-21	16-Feb-21	27-Jan-21	10-Feb-21	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court) 15.00m x 30.00m. This includes concreting of column footing, column, footing the beam, lean & corbel, gutter and sidings and repair of slab concrete. Fabrication and installation of baseplate, steel trusses, pulleys, sagrods and turns buckle and accessories. This also includes roofing works and installation of downspouts, catch basins, plastering demolition works, and installation of wires, devices, panelboard, conduits, lighting fixture, shot dock and grouted riprap.
21E0124	Concreting of Sta. Maria – Manguyang Road, Gloria, Oriental Mindoro	Construction Section	No	Public Bidding	12-Feb-21	04-Mar-21	17-Mar-21	26-Mar-21	GMA 2021	19,600,000.00		19,600,000.00	Total Road Length = 1,825.00 Lm. (3.65 lane km.), Pavement Width = 5.00m, Pavement Thickness = 0.23m thk. Installation of RCPC 610mm dia.x 8.00m. Provide S – Type headwall bothsides.
21E0125	Construction and Concreting of Road, Silbo Panlanao, Brgy. Sagana, leading to Training Camp SAF-PMP, Bongabong, Oriental Mindoro	Construction Section	No	Public Bidding	12-Feb-21	04-Mar-21	17-Mar-21	26-Mar-21	GMA 2021	9,900,000.00		9,900,000.00	Total Road Length = 1,825.00 Lm. (3.65 lane km.), Pavement Width = 5.00m, Pavement Thickness = 0.23m thk. Installation of RCPC 610mm dia.x 8.00m. Provide S – Type headwall bothsides.
21E0126	Concreting of Brgy. Spigang Road, Bongabong, Oriental Mindoro	Construction Section	No	Public Bidding	12-Feb-21	04-Mar-21	17-Mar-21	26-Mar-21	GMA 2021	19,600,000.00		19,600,000.00	Total Road Length = 1,825.00 Lm. (3.65 lane km.), Pavement Width = 5.00m, Pavement Thickness = 0.23m thk. Installation of RCPC 610mm dia.x 8.00m. Provide S – Type headwall bothsides.
21E0127	Construction of Bansud River Control, Poblacion Section, Bansud, Oriental Mindoro.	Construction Section	No	Public Bidding	01-Mar-21	23-Mar-21	07-Apr-21	16-Apr-21	GMA 2021	19,599,804.46		19,599,804.46	Construction of 0.176 km. (176 Lm.), 7 bays Gabions Retainment w/ Mattresses.
21E0128	Construction of Baroc River Control, Roma Section, Mansalay, Oriental Mindoro.	Construction Section	No	Public Bidding	22-Feb-21	16-Mar-21	31-Mar-21	14-Apr-21	GMA 2021	19,599,121.99		19,599,121.99	Construction of Gabions, 0.240 K.M. (240 L.M.), 6 bays Gabions Retainment w/ Mattress.
21E0133	Construction of Multi – Purpose Building (Barangay Hall) at Brgy. Marfrancisco, Pannalayan, Oriental Mindoro	Construction Section	No	Public Bidding	06/10/2021	06/29/2021	July 14, 2021	July 27, 2021	GMA 2021	3,920,000.00		3,920,000.00	Construction of 1 - unit - 2 – Storey building (Barangay Hall). This includes civil works, plastering works, doors, and windows, ceiling works at second floor, railings on veranda and entry (on ramp & stairs are excluded), steel painting, roofing works, plumbing works, and electrical works. Excluding masonry and wood painting, tiling works and plumbing fixtures.
21E0135	Construction of Multi – Purpose Building (Barangay Hall) at Gloria, Oriental Mindoro	Construction Section	No	Public Bidding	04/29/2021	05/18/2021	June 2, 2021	June 15, 2021	GMA 2021	8,820,000.00		8,820,000.00	Construction of 3-unit building (Barangay Hall). The projects are located at Brgy. Pitirayan, G. Antonio and Buoni Lupo. This includes demolition of existing structures, civil works, finishing works, painting works, tiling works, ceiling works, railings, roofing works and electrical works.
21E0136	Construction of Multi – Purpose Building (Barangay Hall) at Roxas, Oriental Mindoro	Construction Section	No	Public Bidding	05/05/2021	05/25/2021	June 9, 2021	June 23, 2021	GMA 2021	5,880,000.00		5,880,000.00	1.) Complete Construction at Victoria, Roxas, Oriental Mindoro (stairs 1m width, sliding windows at front, left and right side of the building and firewell at rear side of the building, balcony and PWD ramp at the front, perimeter walls 150mm CHB and Interior walls 300mm CHB with plastering both exterior and interior, with complete paintings, floor and wall tiles at toilets, ceilings, complete electrical works and plumbing works.) See details and plans; 2.) Construction of 2-storey Building with Roof Deck at San Aguilino, Roxas, Oriental Mindoro (stairs 1.20m width, awning and fixed windows, porch and PWD ramp at the front, with floor tiles for toilets and ceiling at the roof top of stairs, plastering for exterior walls, without paintings for masonry and wood, without waterproofing at roof deck, incomplete electrical works and with plumbing works except for catch basins.) See details and plans.
21E0138	Construction of Multi-Purpose Building (Covered Court) at Bongabong, Oriental Mindoro	Construction Section	No	Public Bidding	05/25/2021	06/15/2021	June 30, 2021	July 13, 2021	GMA 2021	35,280,000.00		35,280,000.00	Construction and Completion of 12 units Multi – Purpose Building (Covered Court) at Barangay Anilo, Bulak, Camrundo, Kaliprasan, Libertad, Luna, Magapang, Morente, Polashah, San Jose and San Juan. This includes concreting of column footing, column, footing the beam, beam, and corbel. Fabrication and installation of steel trusses, struts, pulleys and accessories and roofing works. This also includes installation of drainages and electrical works.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Estimated Budget Cost			Remarks	
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE		CO
21ED139	Construction of Multi – Purpose Building (Covered Court) at Pnamalayan, Oriental Mindoro	Construction Section	No	Public Bidding	06/10/2021	06/29/2021	July 14, 2021	July 27, 2021	GAA 2021	17,640,000.00		17,640,000.00	Construction and completion of 6-units Multi-Purpose Building (Covered Court) at Barangay Baniad, Bul, Ganihwa Piliangpog, Quinabjan and Sta.Isabel. This includes concreting of column footing, column, footing the beam, lean and corbel. Fabrication and installation of steel trusses, struts, purins & accessories and roofing works. This also includes installation of drainages and electrical works.
21ED140	Construction of Multi – Purpose Building (Covered Court) at Roxas, Oriental Mindoro	Construction Section	No	Public Bidding	04/29/2021	05/18/2021	June 2, 2021	June 15, 2021	GAA 2021	17,640,000.00		17,640,000.00	Construction completion of 6-units multi-Purpose Building (Covered Court) at Barangay Uyao, Bagumbayan, Mabuhay, San Jose, San Rafael and Libertad. This includes concreting of Column footing, slab, column, footing the beam, beam and corbel. Fabrication and installation of steel trusses, struts, purins & accessories and roofing works. This also includes installation of drainages and electrical works.
21ED141	Construction of Multi-Purpose Building (Evacuation Center) at Brgy. Palayan and Brgy. Pamisan Hunt, Pnamalayan, Oriental Mindoro	Construction Section	No	Public Bidding	05/25/2021	06/15/2021	June 30, 2021	July 13, 2021	GAA 2021	7,840,000.00		7,840,000.00	Construction of 2 unit 2-storey Multi-purpose Building (evacuation Center). The project is located at Brgy. Palayan and Brgy. Pamisan Hunt, Pnamalayan. This includes civil works, plastering works, doors and windows, ceiling works except of open space at ground floor, railings on veranda, entry ramp & stairs, steel painting, roofing works, plumbing works and electrical works. Excluding masonry and wood painting, tiling works and plumbing fixtures.
21ED146	Construction/Rehabilitation of Multi-Purpose Building (Evacuation Center), Barangay Poblacion and Barangay Cabahna, Mansalay, Oriental Mindoro	Construction Section	No	Public Bidding	04/22/2021	05/18/2021	June 2, 2021	June 15, 2021	GAA 2021	5,980,000.00		5,980,000.00	Construction of 2 units Storey Evacuation Center Bldg. (Scope of Works: Bldg. 1: Construction of T & B, Kitchen, Floor Tiles, Doors & Windows, Masonry & Steel Painting, Plumbing, Septic Tank, Downspout and Masonry Painting (Ground Floor Only). Bldg. 2: Civil Works, Plumbing and Electrical Works.
21ED147	Construction/Rehabilitation of Multi-Purpose Building 2nd Phase, Nabuod, Pnamalayan, Oriental Mindoro	Construction Section	No	Public Bidding	04/22/2021	05/18/2021	June 2, 2021	June 15, 2021	GAA 2021	3,920,000.00		3,920,000.00	Construction/Rehabilitation of 1 unit 3-storey Multi-Purpose Building (Barangay Hall), 6m x 10.30 m. This includes completion of structural works, masonry works, finishing works ceiling, tileworks, painting, roofing works, installation of doors, windows, and fire exit, comfort rooms, septic tank, plumbing and electrical works.
21ED148	Construction/Improvement of Multi – Purpose Building (Covered Court) at Brgy. Budburan, Mansalay, Oriental Mindoro	Construction Section	No	Public Bidding	04/22/2021	05/18/2021	June 2, 2021	June 15, 2021	GAA 2021	3,920,000.00		3,920,000.00	Completion of Covered Court (18.0 x 30.0 m) including plain and reinforced concrete works, bleachers, stage masonry painting, plumbing and electrical works
21ED149	Construction of Drainage Structure - Incinay and Brgy. Zone 3, Pnamalayan, Oriental Mindoro	Construction Section	No	Public Bidding	04/29/2021	05/18/2021	June 2, 2021	June 15, 2021	GAA 2021	7,840,000.00		7,840,000.00	Construction of Covered Drainage Canal Total Length =900 L.M., Brgy. Zone 3 Length =450.00 Lm., Outer Width =1.00, Outer Height =1.00 m., Construction of Concrete Shoulder Length =450.0 Lm. Thickness =0.15m thk. Brgy. Incinay Length =450.0 Lm., Outer Width =1.00, Outer Height =1.00 m.
21ED150	Flood Control Structures/Facilities, Construction of Barangay Aplaya Sewell, Bongabong, Oriental Mindoro	Construction Section	No	Public Bidding	22-Feb-21	16-Mar-21	31-Mar-21	14-Apr-21	GAA 2021	29,399,220.03		29,399,220.03	Construction of Sewall, Concrete Revetment Length = 560.00 L.M.
21ED151	Construction of Pnamul II River Control, Mansalay, Oriental Mindoro	Construction Section	No	Public Bidding	01-Mar-21	23-Mar-21	07-Apr-21	16-Apr-21	GAA 2021	19,798,667.11		19,798,667.11	Construction of 1.10 km. (1100 Lm.) concrete revetment
21ED152	Concreting of Road, Brgy. San Isidro – Luna – Haguit – Mapping – Formon, Bongabong, Oriental Mindoro	Construction Section	No	Public Bidding	01-Mar-21	23-Mar-21	07-Apr-21	16-Apr-21	GAA 2021	9,800,000.00		9,800,000.00	Total Road Length = 653.60 Lm. (1.307 lane km.); Pavement width = 5.00m; Pavement thickness = 0.23m; Construction of Double Barrel Boxculvert 6.90m8.00m3.60m. Construction of Slope Protection Length = 162.10. Installation of RCPC 1220mm dia.8.00m. Provide S – Type Headwall boulders.
21ED153	Concreting of Road, Brgy. San Mariano – Brgy. San Vicente, Roxas, Oriental Mindoro	Construction Section	No	Public Bidding	05-Mar-21	25-Mar-21	08-Apr-21	21-Apr-21	GAA 2021	19,599,821.73		19,599,821.73	Total Road Length = 1,437.50 L.M. (2.8750 Lane Km), Pavement Width = 5.00 m, Pavement Thickness = 0.23 m, Shoulder Width = 1.00m, Extension of 1 line RCPC – 0.90m dia.x 2.00m, 1 line RCPC 1 – 0.90m dia.x 1.00m, 1 line RCPC 1 – 0.60m dia.x 1.00m and Removal and Replacement of 1 – 0.90m dia.x 6.00m by 1 – 1.20m dia.x 8.00m. Provide S – Type Headwall @ Boulders. Length of Retaining Wall = 518.60m. Length of Slope Protection = 291.00. See Plans and Details.
21ED154	Concreting of Road, So. Ilaya, Brgy. San Miguel – Brgy. Uyao – Brgy. Libertad, Roxas, Oriental Mindoro	Construction Section	No	Public Bidding	22-Mar-21	13-Apr-21	28-Apr-21	07-May-21	GAA 2021	19,600,000.00		19,600,000.00	Total Road Length = 1,652.00 L.M. (3.304 Lane Km), Pavement Width = 5.00 m, Pavement Thickness = 0.23 m, Installation of 5 line of RCPC 610mm dia. x 7.00m, Installation of 1 line of RCPC 610mm dia. x 8.00m and Installation of double barrel of RCPC 910mm dia. x 8.00m. Provide S – Type Headwall.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - CM Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21ED0155	Concreting of Barangay Del Mundo Road Mainstay, Oriental Mindoro.	Construction Section	No	Public Bidding	22-Feb-21	16-Mar-21	31-Mar-21	14-Apr-21	GAA 2021	19,600,000.00		19,600,000.00	Road Length = 1,905.70 L.M. (3.811 Lane KM), Pavement Width = 5.00 m, Pavement Thickness = 0.23 m. Shoulder Width = Varies.
21ED0156	Concreting of Brgy. Morente Road, Bongbong, Oriental Mindoro	Construction Section	No	Public Bidding	24-Mar-21	15-Apr-21	29-Apr-21	07-May-21	GAA 2021	19,600,000.00		19,600,000.00	Concreting of Brgy. Morente Road, Road Length = 1,522.00 L.M. (3.044 Lane KM), Pavement Width = 5.00m, Pavement Thickness = 0.23m, Shoulder Width = 1.0m. Construction of Retaining Wall (Stone Masonry) Total Length = 600.00 L.M. Installation of 2-Line RCPC 1-0.50M dia. X 8.00M, 1-Line RCPC 1-0.60M dia. X 8.00M, Provide S-Type Headwall @ Both Side. See Plan and Details.
21ED0157	Construction of Bansud River Control, Conracon section, Bansud, Oriental Mindoro.	Construction Section	No	Public Bidding	22-Feb-21	23-Mar-21	07-Apr-21	16-Apr-21	GAA 2021	19,599,570.67		19,599,570.67	Construction of Gabions, 0.314 K.M. (314 L.M.), 5 bays Gabions Retainment w/ Mattress.
21ED0158	Concreting of Bulacao Diversion Road Phase II, Campesean Section, Bulacao, Oriental Mindoro	Construction Section	No	Public Bidding	25-May-21	15-Jun-21	June 30, 2021	July 13, 2021	GAA 2021	29,400,000.00		29,400,000.00	Road Length = 1,938.00 L.M. (3.8760 Lane KM), Pavement Width = 5.00 m, Pavement Thickness = 0.23 m. Shoulder Width = 1.00m, Length of Slope Protection, L = 70.00 Lm. Installation of RCPC 3 - 610mm dia. X 8.00m and 1 - 1220mm dia. X 8.00m. Provide S - Type Headwall @ Both Sides.
21ED0159	Concreting of Caltagay - Panhuan Munt Road, Panhayan, Oriental Mindoro	Construction Section	No	Public Bidding	05-Mar-21	25-Mar-21	08-Apr-21	21-Apr-21	GAA 2021	19,600,000.00		19,600,000.00	Construction of Concrete Road, Total Road Length = 1,279.40 L.M. (2.559 Lane KM), Pavement Width = 6.10m, Pavement Thickness = 0.23m. thk., Construction of Slope Protection, L = 195.50 Lm. Construction of Retaining Wall, L = 225.00 L.M. Installation of 3 - Lines of RCPC 610mm dia. X 10.00m. Provide S-Type Headwall.
21ED0160	Concreting of M. Adriano - Malabay Road, Gloria, Oriental Mindoro	Construction Section	No	Public Bidding	30-Mar-21	20-Apr-21	May 5, 2021	May 19, 2021		19,600,000.00		19,600,000.00	Total Road Length = 1,938.00 L.M. (3.876 Lane KM), Pavement Width = 5.00 m, Pavement Thickness = 0.23 m. thk. Installation of RCPC 3 - 610mm diameter x 7.00m, Provide S-Type Headwall Bothside.
21ED0161	Concreting of Narte-Pinok-Alma Villa Road, Gloria, Oriental Mindoro	Construction Section	No	Public Bidding	22-Feb-21	16-Mar-21	31-Mar-21	14-Apr-21	GAA 2021	19,600,000.00		19,600,000.00	Concreting of Road at Brgy. Aladesma (L=250.00m, W=5.00m), Brgy. Bato (L=240.00m, W=5.00m), Brgy. Conracon (L=180.00m, W=5.00m), Brgy. Malo (L=210.00m, W=5.00m), Brgy. Panhayan (L=160.00m, W=5.00m), Brgy. Pag-asal (L=240.00m, W=5.00m), Brgy. Proper Bansud (L=250.00m, W=5.00m), Brgy. Proper Tiguan (L=280.00m, W=5.00m), Brgy. Rosacera (L=385. W=5.00m), Brgy. Salcedo (L=300.00m, W=5.00m), Brgy. Sumagui (L=385.00m, W=5.00m), Brgy. Villa Pag-asal (L=280.00m, W=5.00m). Installation of 3 - Lined RCPC 1 - 0.60M dia. X 8.00M, 1-Lined RCPC 1-0.50M dia. X 8.00M, 3-Lined RCPC 1-1.20M dia. X 8.00M, Provide S-Type Headwall @ Both Side. See Plan and Details.
21ED0162	Concreting of Road at Bansud, Oriental Mindoro	Construction Section	No	Public Bidding	24-Mar-21	15-Apr-21	29-Apr-21	07-May-21	GAA 2021	35,640,000.00		35,640,000.00	Concreting of Road at Brgy. Adlaya (L=300.00m, W=5.00m), Brgy. Balangan (L=280.00m, W=5.00m), Brgy. Camandique (L=345.00m, W=5.00m), Brgy. Formon (L=260.00m, W=5.00m), Brgy. Hagani (L=290.00m, W=5.00m), Brgy. Haguik (L=280.00m, W=5.00m), Brgy. Malibong (L=380.00m, W=5.00m), Brgy. Mela de Oro (L=220.00m, W=5.00m), Brgy. Ogbo (L=330.00m, W=5.00m), Brgy. Sagana (L=340.00m, W=5.00m), Brgy. San Isidro (L=330.00m, W=5.00m), Brgy. Sta. Cruz (L=385.00m, W=5.00m), Brgy. San Isidro (L=330.00m, W=5.00m), Brgy. Sta. Cruz (L=385.00m, W=5.00m), Installation of 2-Lined RCPC 1-0.60M dia. X 8.00M, 6 lined RCPC 3 - 0.50m dia. X 8.00m, 1-Lined RCPC 2-1.20M dia. X 8.00M, Provide S-Type Headwall @ Both Side. See Plan and Details.
21ED0163	Concreting of Road at Bongbong, Oriental Mindoro	Construction Section	No	Public Bidding	30-Mar-21	20-Apr-21	May 5, 2021	May 19, 2021	GAA 2021	44,190,000.00		44,100,000.00	

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21EIO164	Concreting of Road at Bulalacao, Oriental Mindoro	Construction Section	No	Public Bidding	04/29/2021	05/18/2021	June 2, 2021	June 15, 2021	GMA 2021	41,160,000.00		41,160,000.00	Construction of Concrete Road. Total Road Length = 5,754.50 Lm. (11.509 line km.). Bryg: Bagong Sikat Length = 135.20 Lm, W=5.00m, Bryg: Benil Length = 101.00 Lm, W=5.00m, Bryg: Camtunang Length = 258.00m, W=5.00m, Bryg: Naujo Length = 178.10m, W=5.00m, Bryg: Nasucob Length = 243.50 Lm, W=5.00m, Bryg: San Francisco Length = 262.30 Lm, W=6.10m, Bryg: San Juan Length = 251.00 Lm, W=5.00m, Bryg: Balabasan Length = 232.00 Lm, W=5.00m, Bryg: Cabaog Length = 251.50 Lm, W=5.00m, Bryg: Campasan Length = 204.20 Lm, W=6.10m, Bryg: Mingroal Length = 251.30 Lm, W=5.00m, Bryg: Pobocan Length = 230.00m, W=5.00m, Bryg: San Isidro Length = 234.50 Lm, W=5.00m, Bryg: San Roque Length = 256.00 Lm, W=5.00m, Construction of Slope Protection (Grouted Riprap, Construction of Retaining Wall (Stone Masonry), Construction of Lined Canal (Stone Masonry) and Installation of RCPC 610mm, 910mm and 1220mm. Provide S-Type Headwall @ Both Side. See Plan and Details.
21EIO165	Concreting of Road at Mansalay, Oriental Mindoro	Construction Section	No	Public Bidding	24-Mar-21	04/15/2021	28-Apr-21	07-May-21	GMA 2021	38,610,000.00		38,610,000.00	Concreting of Road at Bryg: Dal Mundo (L=300.00m, W=5.00m), Bryg: Balugo (L=280.00m, W=5.00m), Bryg: Bonbon (L=200.00m, W=5.00m), Bryg: Don Pedro (L=240.00m, W=5.00m), Bryg: Manaul (L=240.00m, W=5.00m), Bryg: Panaytayen (L=160.00m, W=5.00m), Bryg: Roma (L=290.00m, W=5.00m), Bryg: Sta. Maria (L=280.00m, W=5.00m), Bryg: Sta. Teresita (L=280.00m, W=5.00m), Bryg: Villa Celestial (L=230.00m, W=5.00m), Bryg: Winyan (L=285.00m, W=5.00m), Bryg: Wala (L=240.00m, W=5.00m), Installation of 3-Lined RCPC 1 - 0.060m, dia. X 8.00m, 3-Lined RCPC 3-0.90m dia. X 8.00m, 3-Lined RCPC 1-1.20m dia X 8.00m, Provide S-Type Headwall @ Both sides. See Plan and Details
21EIO166	Concreting of Road at Roxas, Oriental Mindoro	Construction Section	No	Public Bidding	04/29/2021	05/18/2021	June 2, 2021	June 15, 2021	GMA 2021	35,280,000.00		35,280,000.00	Concreting of Road at Roxas, Oriental Mindoro, Road Length=3,095.60 L.M. (6.0192-Lane Km), (Bryg: Canil (L=215.00m, W=5.00m), Bryg: Dangay (L=262.00m, W=5.00m), Bryg: Happy Valley (L=216.00m, W=5.00m), Bryg: Librong (L=282.00m, W=5.00), Bryg: Little Tanager (L=294.00m, W=5.00m), Bryg: Maraka (L=166.00m, W=5.00m), Bryg: Ochoy (L=184.00m, W=5.00m), Bryg: Paduan (L=255.00m, W=5.00m), Bryg: San Isidro (L=270.00m, W=5.00m), Bryg: San Plarino (L=294.60m, W=5.00m), Bryg: San Miguel (L=245.00m, W=5.00m), Bryg: San Vicente (L=292.00m, W=5.00m), Installation of 2-Lined RCPC 1-0.60m, dia. X 8.00m, Installation of 1 - lined RCPC 1-0.60m, dia. X 7.00m, Installation of 3-Lined RCPC 1- 0.90m, dia. X 8.00m, Installation of 1-Lined RCPC 1-0.90m, dia. X 7.00m, Installation of 1-Lined RCPC 1-1.20m, dia. X7.00m, Construction of Retaining Wall & Slope Protection = 1,752.00m. Provide S-Type Headwall @ Both Side. See Plan and Details.
21EIO167	Concreting of Road, Silbo Laway, Bryg: Sakeco - Silbo Baya - Bryg: Tigusan, Bardsud, Oriental Mindoro	Construction Section	No	Public Bidding	22-Mar-21	04/13/2021	28-Apr-21	07-May-21	GMA 2021	19,600,000.00		19,600,000.00	Concreting of Silbo Laway, First Section Length = 2.60 lane km. Pavement Width = 5.00 m, Pavement Thickness = 0.23 m, Concreting of Silbo Baya Road, Second Section Length = 0.974 lane km, Pavement Width = 5.00 m, Pavement Thickness = 0.23 m, Shoulder width = 0.50m, Installation of 7 lines RCPC 1 - 610mm dia. x 7.00m, Provide S - Type headwall bootides. Installation of 1 line of RCPC 2 - 1.20m dia. x 7.00m, Provide S - T-type headwall, Apron and wingwall bootides. See plans and details.
21EIO168	Concreting of Road, Bryg: Quepanglo - Bryg: San Juan Proper, Bulalacao, Oriental Mindoro	Construction Section	No	Public Bidding	22-Mar-21	04/13/2021	28-Apr-21	07-May-21	GMA 2021	19,600,000.00		19,600,000.00	Total Road Length = 1,300.00 Lm, (2.60 lane km.), Pavement Width = 5.00 m, Pavement Thickness = 0.23 m, Construction of Triple Barrel Box Culvert, 10.20mx8.00mx3.60m, Construction of Slope Protection, Length = 342.20 Lm, Installation of RCPC 610mm & 910mm dia. x 8.00m, Provide S - Type headwall bootides.
21EIO169	Construction of Multi-Purpose Building in Barangay Nasucob, Bulalacao, Oriental Mindoro	Construction Section	No	Public Bidding	01-Mar-21	03/23/2021	30-Mar-21	15-Apr-21	GMA 2021	960,000.00		960,000.00	Construction of 2-storey Multi-purpose Building, Phase 1. This includes structural works of ground floor, foundation, footing the beam, column, beam, slab on fill and second floor slab partial 6" CHB and roughing - Ins.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - CMW Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Source of Funds	Estimated Budget Cost			Remarks
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval		Total	MOOE	CO	
21ED0170	Concreting of Road at Gloria, Oriental Mindoro	Construction Section	No	Public Bidding	03/30/2021	04/20/2021	May 5, 2021	May 19, 2021	GMA 2021	69,480,000.00		69,480,000.00	Construction of Concrete Road of Total Length = 5.268 L.M. (10.536 Lane Km), Bryg, Agos Length = 216.00 Lm, Width = 4.00, Bryg, Agaslin Length = 206.00 Lm, Width = 5.00, Bryg, Alma Villa Length = 212.00 Lm, Width = 5.00, Bryg, Andres Bonifacio Length = 224.00 Lm, Width = 4.00, Bryg, Balete Length = 200.00 Lm, Width = 6.10, Bryg, Batus Length = 218.00 Lm, Width = 5.00, Bryg, Banuran Length = 220.00 Lm, Width = 5.00, Bryg, Buakalian Length = 237.00 Lm, Width = 4.00, Bryg, Gaitunuran Length = 245.00 Lm, Width = 4.00, Bryg, Kemat Length = 215.00 Lm, Width = 5.00, Bryg, Lucio Laurel Length = 200.00 Lm, Width = 6.10, Bryg, Adarico Length = 212.00 Lm, Width = 5.00, Bryg, Malang Length = 220.00 Lm, Width = 5.00, Bryg, Malayong Length = 236.00 Lm, Width = 4.00, Bryg, Malipaya Length = 220.00 Lm, Width = 5.00, Bryg, Malipaya Length = 220.00 Lm, Width = 5.00, Bryg, Manayung Length = 220.00 Lm, Width = 5.00, Bryg, Marapoc Length = 222.00 Lm, Width = 5.00, Bryg, Marra Length = 215.00 Lm, Width = 5.00, Bryg, Papandungan Length = 212.00 Lm, Width = 5.30, Bryg, San Antonio Length = 215.00 Lm, Width = 5.00, Bryg, Sta. Maria Length = 220.00 Lm, Width = 5.00, Bryg, Sta. Theresa Length = 218.00 Lm, Width = 4.00 - 5.00, Bryg, Tambong Length = 198.00 Lm, Width = 6.10, Construction of Slope protection L = 536.00 Lm, Installation of RCPC 910mm and 1220mm, provide S-type Headwall
21ED0171	Concreting of Road at Pinaulayan, Oriental Mindoro	Construction Section	No	Public Bidding	04/29/2021	05/18/2021	June 2, 2021	June 15, 2021	GMA 2021	72,375,000.00		72,375,000.00	Concreting of Road at Pinaulayan, Oriental Mindoro, Road Length=5737.90 L.M. (11.4738 Lane Km), Bryg, Anoling (L=255.70m, W=5.00m), Bryg, Bacungan (L=195.50m, W=5.00m), Bryg, Bangbang (L=265.40m, W=5.00m), at Bryg, Cacawan (L=258.40m, W=5.00m), Bryg, Calinag (L=252.50m, W=5.00m), Bryg, Del Razon (L=215.10m, W=5.00m), Bryg, Lumangbayen (L=203.50m, W=5.00m), Bryg, Maraya (L=180.50m, W=5.00m), Bryg, Maringod (L=247.50m, W=5.00m), Bryg, Marayor (L=213.50m, W=5.00m), Bryg, Paglalag (L=319.20m, W=5.00m), Bryg, Pambisan (L=257.20m, W=5.00m), Bryg, Pangulayan (L=265.30m, W=5.00m), Bryg, Papandayan (L=188.80m, W=6.7m, Side W=0.23-0.65m), Bryg, Pili (L=273.90m, W=2.5-5m), Bryg, Ranza (L=229.50m, W=5.00m), Bryg, Rosario (L=251.10m, W=5.00m), Bryg, Sabang (L=220.10m, W=5.00m), Bryg, Sta. Maria (L=171.10m, W=5.00m), Bryg, Sta. Nifio (L=218.50m, W=5.00m), Bryg, Wawa (L=276.80m, W=5.00m), Bryg, Zone 1 (L=212.70m, W=6.00m), Bryg, Zone 2 (L=146.90m, W=6.70m), Bryg, Zone 4 (L=167.90m, W=3.3-3.35m), Retaining Wall = 1,422.10m, Installation of 12-Lined RCPC 1-0.60m, dia. X 8.00, 3-Lined RCPC 1-0.6m, dia. X 6.00m, 1-Lined RCPC 1-0.6m, dia. X 10.00m, 1-Lined RCPC 1-0.9m, dia. X 8.00m, Provide S-Type Headwall @ both Side, See Plan and Details.
21ED0172	Construction of Flood Control Structure, Manobo River, Bagong Sikat Section, Bulakeco, Oriental Mindoro	Construction Section	No	Public Bidding	01-Mar-21	03/23/2021	07-Apr-21	16-Apr-21	GMA 2021	9,799,477.02		9,799,477.02	Construction of 0.120 km. (120 Lm.), 6 layers Gabions Retention w/ Mattresses.
21ED0177	Construction of Multi - Purpose Building at Barangay Akadesna, Bansud, Oriental Mindoro	Construction Section	No	Public Bidding	05-Mar-21	03/25/2021	03/30/2021	04/15/2021	GMA 2021	3,960,000.00		3,960,000.00	Construction of 1 unit building (8,00m ² .50m). Construction of multi - purpose building complete.
21ED0178	Repair/Maintenance of CERK Building, Main Building, San Mariano, Roxas, Oriental Mindoro	Maintenance Section	No	Public Bidding	04/22/2021	05/18/2021	05/27/2021	06/08/2021	SR2021-03-006890	2,500,000.00		2,500,000.00	Repair/Maintenance of Main Building with proposed replacement of roofing, ceiling and electrical works.
21ED0179	Repair/Maintenance of DILG Building, PNP Main Building (Pantry and Quarters), Poblacion, Bongabong, Oriental Mindoro	Maintenance Section	No	Public Bidding	04/22/2021	05/18/2021	05/27/2021	06/10/2021	SR2021-03-006890	1,500,000.00		1,500,000.00	Repair/Maintenance of Main Building with proposed replacement of roofing, ceiling and electrical works.
21ED0180	Repair/Maintenance of DILG Building, Bureau of Fire Protection Office & Quarters, Poblacion, Bansud, Oriental Mindoro	Maintenance Section	No	Public Bidding	04/29/2021	05/18/2021	05/27/2021	06/08/2021	SR2021-03-006890	2,000,000.00		2,000,000.00	Repair/Maintenance of Office Building and Quarters with proposed second floor intended for quarters and roof deck.

ANNUAL PROCUREMENT PLAN FOR CY 2021 - Civil Works

CONTRACT ID	Project Name	PMO End User	Is This an Early Procurement Activity? (Yes/No)	Mode of Procurement	Date				Estimated Budget Cost			Remarks	
					Advertisement	Submission / Opening of Bids	Notice of Award	Contract Approval	Source of Funds	Total	MOOE		CO
21ED181	Repair/Maintenance of DLG Building, Bureau of Fire Protection Building, Mansalay, Oriental Mindoro	Maintenance Section	No	Public Bidding	04/29/2021	05/18/2021	05/27/2021	06/08/2021	SR2021-03-006890	1,500,000.00	1,500,000.00		Repair/Maintenance of Main Building with proposed ceiling and finishing works.
21ED182	Repair/Maintenance of Barac Dike, Brgy. Sta. Brigida, Mansalay, Oriental Mindoro (F2000212)	Maintenance Section	No	Public Bidding	05/05/2021	05/25/2021	June 22, 2021	June 9, 2021	SR2021-03-006747	2,000,000.00	2,000,000.00		Repair/Maintenance of Barac Dike, Brgy. Sta. Brigida, Mansalay, Oriental Mindoro. Gabion length = 26.00 m.m., Installation of 5 – layer gabion, 1.00 m x 1.00m x 2.00 m., Installation of mattresses 0.30m x 2.00 m x 6.00 m.,
21ED183	Repair/Maintenance of Abutment Protection of Tambangan Bridge Abutment A, Bulacao, Oriental Mindoro	Maintenance Section	No	Public Bidding	05/05/2021	05/25/2021	05/31/2021	06/14/2021	SR2021-03-004281	1,105,177.00	1,105,177.00		Repair/Maintenance of Abutment Protection of Tambangan Bridge Abutment A, Bulacao, Oriental Mindoro. Gabion Length = 20.00 L.M., Installation of 1-Layer Gabion 1.00mx1.00mx2.00m. Gabion Length = 15.00 L.M. Installation of 4-Layer Gabion 1.00m x 1.00m x 2.00m.,
21ED184	Repair/Maintenance of Balte Revetment, Brgy. Adriatico, Gloria, Oriental Mindoro (F4001512)	Maintenance Section	No	Public Bidding	05/05/2021	05/25/2021	05/31/2021	06/14/2021	SR2021-03-006747	3,000,000.00	3,000,000.00		Repair/Maintenance of Balte Revetment, Brgy. Adriatico, Gloria, Oriental Mindoro. Gabion length = 34.30 m.m., Installation of 6 – layer gabion, 1.00 m x 1.00m x 2.00 m., Installation of mattresses 0.30m x 2.00 m x 6.00 m
21ED185	Repair/Maintenance of DLG Building PNP Building - Special Action Force (SAF Main Building), Sitio Panlanao, Brgy. Sagana, Bongabong, Oriental Mindoro	Maintenance Section	No	Public Bidding	05/05/2021	05/25/2021	05/31/2021	06/09/2021	SR2021-03-006890	2,859,691.34	2,859,691.34		Repair/Maintenance of Main Building with proposed replacement of structural, wall partitions, roofing, ceiling, floor tiles and finishing, painting and electrical works.
21ED187	Concreting of Morente – Batangan FHR, Brgy. Morente and Batangan, Bongabong, Oriental Mindoro	Construction Section	No	Public Bidding	05/25/2021	06/15/2021	06/23/2021	07/08/2021	DA 2021	11,940,000.00		11,940,000.00	Concreting of Morente - Batangan FHR, Total Road Length=634.80 L.M. (1.2696 Lane Km), Pavement Width = 5.00m., Pavement Thickness= 0.23m. Construction of Lined Canal, Total Length = 605.80 L.M., Construction of Retaining Wall (Stone Masonry) Total Length = 40.00 L.M., Installation of 2 Lined RCPC 1 - 60m diameter x 8.00m, Installation of 1 Lined RCPC 1 – 0.90m diameter x 8.00m, Provide S-Type Headwall @ both sides. See Plan and Details.
21ED188	Concreting of Sitio Balaican, Brgy Marayao FHR, Brgy. Marayao Panambayan, Oriental Mindoro	Construction Section	No	Public Bidding	05/25/2021	06/15/2021	06/23/2021	07/06/2021	DA 2021	11,940,000.00		11,940,000.00	Concreting of Sitio Balaican, Brgy Marayao FHR, Total Road Length = 893.00 L.M. (1.786 Lane Km), Pavement Width =5.00 m., Pavement Thickness = 0.23 m. thk. Construction of Slope Protection at U/S, Length = 164.00 Lm, Installation of RCPC 3 - 910mm diameter x 8.00m and 1- 610mm diameter x 8.00m, provide S-Type headwall bottside
21ED189	Concreting of Happy Valley FHR, Brgy. Happy Valley, Roxas, Oriental Mindoro	Construction Section	No	Public Bidding	05/25/2021	06/15/2021	06/23/2021	07/06/2021	DA 2021	12,437,500.00		12,437,500.00	Concreting of Happy Valley FHR, Road Length = 832.8 L.M. (1.6656 Lane Km), Pavement Width = 5.00 m., Pavement Thickness = 0.23 m., Shoulder Width = 1.0 m, Construction of Lined Canal, Total Length = 315.0 L.M. Bothside, Construction of Slope Protection Total Length = 120.0 L.M, Installation of 1 Line RCPC 1- 0.60M, dia. x 8.00M, Provide S-Type Headwall @ Both Side. See Plan and Details

Prepared by:

MAYBELLE B. SISCAR, E-III
OIC, Procurement Staff

Checked by:

DETINO V. GUEVARA, JR., E-III
Chief, Planning and Design Section

Approved by:

ANIELYN E. PADULLO
District Engineer