

Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
DAVAO DE ORO 2ND DISTRICT ENGINEERING OFFICE
Compostela, Davao de Oro, Region XI

UPDATED ANNUAL PROCUREMENT PLAN FOR CIVIL WORKS FY 2024

Code (PAP)	Procurement Project	PMO/ End-User	Is this an Early Procurement Activity? (Yes/No)	Mode of Procurement	Schedule for Each Procurement Activity				Source of Funds	Estimated Budget (PhP)			Remarks (brief description of Project)
					Advertisement/ Posting of IB/REI	Submission/O pening of Bids	Notice of Award	Contract Signing		Total	MOOE	CO	
300226115675000	1.) 24LI0002 - Construction of Multi-Purpose Building, Barangay Siocon, Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	10/13/23-10/19/23	12/6/2023	1/31/2024	02/08/24	GoP	5000000	-	5000000	Construction of Complete Health Center (8m x 10.7m) including Site Development, Plumbing Works, Ceiling Works, Painting Works, Carpentry and Joinery Works, Aluminum Signage (Letters and LOGO), Electrical Works and Airconditioning (Package/Split Type)
300226115672000	2.) 24LI0006 - Construction of Multi-Purpose Building, Barangay Langgawisan, Maragusan, Davao de Oro	Const. Section	YES	Competitive Bidding	10/13/23-10/19/23	12/06/23	01/31/24	02/08/24	GoP	7000000	-	7000000	Construction of Complete Barangay Hall (12.75m x 13.35m) including Plumbing Works, Ceiling Works, Painting Works, Carpentry and Joinery Works, Electrical Works, Signage and Logo, Airconditioning Unit, Stainless Water Tank and Fire Extinguisher
300215103468000	3.) 24LI0019 - Construction Batutu River Irrigation System Katipunan Road - MC East, New Bataan, Davao de Oro (KATUBIGAN - Kalsada Tungo sa Patubigan)	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	01/31/24	02/08/24	GoP	28000000	-	28000000	Concreting (width = 6.10 m., thk. 230 mm) Sta. 1+973.000 – Sta. 2+373.000 = 1,400.00 m Roadway Excavation Installation of Metal Guardrails including Post with Metal Beam End Piece Application of ReflectORIZED Thermoplastic Pavement Markings
300230100193000	4.) 24LI0031 - Construction of Water Supply System, Barangay Paloc, Maragusan, Davao de Oro	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/23	01/31/24	02/08/24	GoP	5000000	-	5000000	Construction of Concrete Reservoir Construction of 1 unit Cistern (Intake Box) Construction of 1 unit Plumbing Works (Collection Box) Installation of PE Pipes, Valves and Pipe Fittings
320102106688000	5.) 24LI0013 - Construction of Flood Mitigation Structure along Agusan River (Manat River Junction), Poblacion, Monkayo, Davao de Oro Phase 2	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	02/13/24	02/20/24	GoP	100000000	-	100000000	Construction of Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for Back-slope Protection and End Protection Works Installation of Minor Drainages
320102106689000	6.) 24LI0014 - Construction of Flood Mitigation Structure along Agusan River, Barangay Mamunga, Monkayo, Davao de Oro	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	02/13/24	02/20/24	GoP	100000000	-	100000000	Construction of Concrete Revetment with Steel Sheet Pile for Foundation Construction of Grouted Riprap Back-slope Protection and End Protection Works

320102106692000	7.) 24LI0021 - Construction of Revetment along Agusan River (Upstream), Barangay Katipunan, Maragusan, Davao de Oro	Const. Section	YES	Competitive Bidding	11/22/23-11/28/23	12/12/23	02/13/24	02/20/24	GoP	100000000	-	100000000	Construction of Reinforced Concrete Revetment Construction of Grouted Riprap End Protection Works Installation of Minor Drainages Removal of Existing Slope Protection
300204101627000	8.) 24LI0022 - Tubo-tubo-Mamunga Road in support of Rice, Banana, and Oil Palm Production, Monkayo, Davao de Oro	Const. Section	YES	Competitive Bidding	11/22/23-11/28/23	12/12/23	02/13/24	02/20/24	GoP	200000000	-	200000000	Concreting (width = 6.70 m., thk. = 280 mm Sta. 1+100.000 – Sta. 1+924.000 = 824.00m Construction of Concrete Lined Canal and other Minor Drainage Structure Installation of Metal Guardrails including Post with Metal Beam End Piece Application of Reflectorized Thermoplastic Pavement Markings
300204101626000	9.) 24LI0023 - Naboc-Pilar-Tamia Road in support of Banana Industry, Monkayo-Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	11/22/23-11/28/23	12/12/23	02/13/24	02/20/24	GoP	200000000	-	200000000	Concreting (width = 6.10 m., thk.=280 mm) Sta. 0+000.000 – Sta. 0+802.000 = 802.000m Construction of other Minor Structure Embankment from borrow (Common Soil) Application of Reflectorized Thermoplastic Pavement Markings
300230100192000	10.) 24LI0024 - Construction of Water Supply System, Barangay Cambagang, Maragusan, Davao de Oro	Const. Section	YES	Competitive Bidding	11/22/23-11/28/23	12/12/23	02/13/24	02/20/24	GoP	50000000	-	50000000	Construction of Concrete Reservoir Installation of PE Pipes, Valves and Pipe Fittings
310208100640000	11.) 24LI0029 - Off-Carriageway Improvement: Construction of Traffic Island – Benigno S. Aquino Jr. National Highway (S01432MN) – K 1608+660 – K 1612+060	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/23	02/13/24	02/20/24	GoP	450000000	-	450000000	Construction of Center Island K 1608+660 – K 1612+060 = 3,400 meters AS PER RBIA K 1608+660 – K 1612+060 = 3,400 meters AS PER PLAN Installation of Solar LED Street Light with Double Arm Steel Post K 1608+660 – K 1612+060 = 163.00 units AS PER RBIA K 1608+660 – K 1612+060 = 163.00 units AS PER PLAN Embankment from Borrow (Common Soil) for Center Island Removal and Reconstruction of PCCP Installation of Hazard Markers and Delineators (Panel Type (L-Shaped) – Retroreflective Sheeting) Application of Reflectorized Traffic Paint Pavement Markings
300226115674000	12.) 24LI0034 - Construction of Multi-Purpose Building, Barangay Poblacion, Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	11/30/23-12/06/23	12/21/23	02/13/24	02/20/24	GoP	100000000	-	100000000	Construction of Multi-Purpose Building (Warehouse) which includes Reinforced Concrete Works, Finishing and Other Civil Works such as Carpenter and joinery works, Tile Works, Painting Works, Spandrel, Electrical Works, Exhaust Fan.

300226115677000	13.) 24LI0035 - Rehabilitation (Completion) of Multi-Purpose Building (Rural Health Unit Building), Monkayo, Davao de Oro	Const. Section	YES	Competitive Bidding	11/30/23-12/06/23	12/21/23	02/13/24	02/20/24	GoP	20000000	-	20000000	1.) Rehabilitation of Dietary and Laundry Building Includes the Following: - Demolition of Existing Walls, Tile Works, Ceiling Works, Canopy, Painting Works, Doors and Windows, Stainless Steel Cabinets and Counter, Chimney and Electrical Works. 2.) Construction of Two (2) Storey Building Includes the Following: - Demolition of Existing Buildings - Excavation Works, Embankment, Concrete Works and Reinforcing Steel Works and Masonry Works.
310202101764000	14.) 24LI0037 - Road Widening – Benigno S. Aquino Jr. National Highway – K1606+850 – K1607+000	Const. Section	YES	Competitive Bidding	11/30/23-12/06/23	12/21/23	02/13/24	02/20/24	GoP	15000000	-	15000000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing Width 6.7m, with Additional 2 Lanes, Total Width 13.4m K 1606+850 – K 1607+000 = 150 meters (AS PER RBIA) K 1606+850 – K 1607+000 = 150 meters (AS PER PLAN) Paved Shoulders, 230mm thk. Construction of Concrete Lined Canal Roadway Excavation Removal of Structures and Obstruction Construction of Retaining Wall Installation of Metal Guardrails including Post with Metal Beam End Piece Reflectorized Thermoplastic Pavement Markings White
300215102804000	15.) 24LI0009 - Construction of Road, Panansalan, Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	02/21/24	02/28/24	GoP	30000000	-	30000000	oncreting (width = 6.10 m., thk. 280 mm) Sta. 1+240.000 – Sta. 1+845.000 = 605.00 meters Construction of minor Drainage Structures Installation of Metal Guardrails including Concrete Post with Metal Beam End Piece Application of Reflectorized Thermoplastic Pavement Markings
300204101624000	16.) 24LI0018 - Construction of Revetment along Aunan Creek (Bridge Section Upstream) to Agusan River Phase II, Barangay Babag, Monkayo, Davao de Oro	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	02/21/24	02/28/24	GoP	20000000	-	20000000	Concreting (width = 6.10., thk.=280 mm) Sta. 0+000.000 – Sta. 1+050.000 = 950.00 m Construction of Minor Drainage Structure Application of Reflectorized Thermoplastic Pavement Markings
300226115673000	17.) 24LI0004 - Construction of Multi-Purpose Building, Barangay Pamintaran, Maragusan, Davao de Oro	Const. Section	YES	Competitive Bidding	10/13/23-10/19/23	12/06/23	03/04/24	03/12/24	GoP	6000000	-	6000000	Construction of Complete Barangay Hall (12.75m x 13.35m) including Plumbing Works, Ceiling Works, Painting Works, Carpentry and Joinery Works, Electrical Works, Signage and Logo, Airconditioning Unit, Stainless Water Tank and Fire Extinguisher.

300203102219000	18.) 24LI0008 - Ngan Road leading to Mandaya Village, Pansan Falls, Bongkilaton Cave and Tagbubunias Falls, Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	03/04/24	03/12/24	GoP	15000000	-	15000000	Concreting (width = 6.10 m., thk.=230 mm) Sta. 5+517.130 – Sta. 5+738.480 = 221.350 m Roadway Excavation Construction of Concrete Lined Canal and Other Minor Drainage Structures Application of Reflectorized Thermoplastic Pavement Markings
300203102221000	19.) 24LI0012 - San Jose Leading to Awao Falls, Brgy. San Jose, Monkayo, Davao de Oro	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	03/04/24	03/12/24	GoP	5000000	-	5000000	Concreting (width = 6.10 m., thk.=230 mm) Sta. 6+000.875 – Sta. 6+165.875 = 165.00m Construction of Concrete Lined Canal and other Minor Drainage Structure Installation of Metal Guardrails including Post with Metal Beam End Piece Application of Reflectorized Thermoplastic Pavement Markings
320102106687000	20.) 24LI0015 - Construction of Flood Mitigation Structure along Agusan River (Manat River Junction), Poblacion, Monkayo, Davao de Oro Phase 1	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	03/04/24	03/12/24	GoP	100000000	-	100000000	Construction of Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for Back-slope Protection and End Protection Works Installation of Minor Drainages
320102106695000	21.) 24LI0016 - Construction of Revetment along Aunan Creek (Bridge Section Upstream) to Agusan River Phase II, Barangay Babag, Monkayo, Davao de Oro	Const. Section	YES	Competitive Bidding	10/24/23-10/30/23	12/06/23	03/04/24	03/12/24	GoP	105348000	-	105348000	Construction of Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap Back-slope Protection and End Protection Works Installation of Minor Drainages
300105201197000	22.) 24LI0025 - Construction (Completion) of DPWH Davao de Oro 2nd DEO Building, Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	11/22/23-11/27/23	12/12/23	03/06/24	03/15/24	GoP	78146000	-	78146000	Construction/Completion of DPWH Davao de Oro 2nd DEO Building (Phase II) Includes the following; 1.) All Reinforced Concrete and Reinforcing Steel Works from 2nd Floor to Roof-deck. 2.) Installation and Laying of Exterior and Interior (4th floor interior walls are not included). 3.) Plastering Works from 2nd Floor to Roof-deck. 4.) Plumbing Works (Sewer Line Works and Downspout Only) 5.) Roof Framing, Roofing, Metal Deck Panel and Painting Works on Steel 6.) All Conduits, Boxes and Fittings for Electrical Works 7.) Construction of Water Pumping System

310202101763000	23.) 24LI0032 - Road Widening - Benigno S. Aquino Jr. National Highway- K 1414+(-401) - K 1414+109	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/24	03/06/24	03/15/24	GoP	25000000	-	25000000	Concreting of Additional 2 lanes (4 into 6 lanes, 280 mm thk.) Existing Width 13.4m, with Additional 2 Lanes, Total Width 20.10 m K 1414+(-401) – K 1414+109 = 510.00 meters AS PER RBIA K 1413+599 – K 1414+109 = 510.00 meters AS PER PLAN Construction of Concrete Lined Canal and Other Minor Drainage Structure Construction of 3m x 3m x 8m RCBC Embankment from borrow Removal of Structures and Obstruction Construction of Slope Protection (Grouted Riprap) Application of Reflectorized Thermoplastic Pavement Markings
310102101638000	24.) 24LI0033 - Preventive Maintenance of Road: Asphalt Overlay – Benigno S. Aquino Jr. National Highway (S01432MN) K 1608+000 – K 1613+320	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/24	03/06/24	03/15/24	GoP	100000000	-	100000000	Asphalt Overlay (width:6.7m., 50mm thk.) Lane 1 and 2 K 1608+000 – K 1608+666 = 666.000 meters AS PER PLAN Lane 2 and 3 K 1608+666 – K 1613+320 = 4,654.000 meters AS PER PLAN Lane 1 and 2 K 1608+000 – K 1608+660 = 660.000 meters AS PER RBIA Lane 2 and 3 K 1608+660 – K 1613+320 = 4,660.000 meters AS PER RBIA Application of Concrete Joint Sealant Construction of Center Island (K 1612+060 – K 1612+955 = 895.00 sq.m.) Installation of Solar LED Street Light with Double Arm Steel Post (44 units) Removal and Reconstruction of PCCP 28mm thk Installation of Regulatory Signs, Hazard Markers, Warning Signs, Tubular Markers and Delineators Application of Reflectorized Traffic Paint Pavement Markings Application of Reflectorized Thermoplastic Pavement Markings
300204101625000	25.) 24LI0020 - Mapawa-Tigbao-New Panay Road in support of the Banana and Rice Production, Maragusan, Davao de Oro	Const. Section	YES	Competitive Bidding	11/22/23-11/28/23	12/12/23	03/07/24	03/15/24	GoP	20000000	-	20000000	Concreting (width = 6.70 m., thk. = 280mm) Sta. 0+000.000 – 0+560.000 = 560.000m Paved Shoulder, 150mm thk. Construction of Slope Protection (Grouted Riprap) Installation of Metal Guardrails including Concrete Post Application of Reflectorized Thermoplastic Pavement Markings

300203102215000	26.) 24LI0027 - Bongkilaton Road leading to Mandaya Village, Pansan Falls, Bongkilaton Cave and Tagbubunias Falls, Brgy. Ngan, Compostela, Davao de Oro	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/24	03/07/24	03/15/24	GoP	15000000	-	15000000	Concreting (width = 6.10 m., thk. = 230mm) Sta. 0+000.000 – 0+318.000 = 318.000m Construction of Concrete Lined Canal and other Minor Drainage Structure Installation of Metal Guardrails including Post with Metal Beam End Piece Application of ReflectORIZED Thermoplastic Pavement Markings Installation of Hazard Markers, Chevron Signs
310202101768000	27.) 24LI0028 - Road Widening - Nabunturan - Maragusan Rd - K 1452+000 - K1453+061	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/24	03/07/24	03/15/24	GoP	50000000	-	50000000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing Width 6.7m, with Additional 2 Lanes, Total Width 13.4m K 1452+000 – K 1453+061 = 1,061.000 meters AS PER RBIA K 1452+120 – K 1453+061 = 941.000 meters AS PER PLAN Paved Shoulder, 230mm thk. Roadway Excavation Construction of Slope Protection (Grouted Riprap) Installation of Metal Guardrails including Concrete Post and Metal Beam End Piece Application of ReflectORIZED Thermoplastic Pavement Markings
310208100641000	28.) 24LI0030 - Off-Carriageway Improvement: Construction of Traffic Island-Montevista-Compostela-Mati Bdry. Rd. - K 1486+(-307) - K 1488+044	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/24	03/07/24	03/15/24	GoP	33568000	-	33568000	Construction of Center Island K 1486+(-307) – K 1488+044 = 2,370.00 meters AS PER RBIA K 1485+693 – K 1488+063 = 2,370.00 meters AS PER PLAN Installation of Solar LED Street Light with Double Arm Steel Post K 1486+(-307) – K 1488+044 = 114 units AS PER RBIA K 1485+693 – K 1488+044 = 114 units AS PER PLAN Embankment from Borrow (Common Soil) for Center Island Removal and Reconstruction of PCCP Application of ReflectORIZED Traffic Paint Pavement Markings Installation of Warning Signs 600mm x 600mm (W6-1B) Installation of Regulatory Signs and Hazard Markers Installation of Delineators (Panel Type (L-Shaped) – Retroreflective Sheetting) Application of ReflectORIZED Traffic Paint Pavement Markings Application of ReflectORIZED Thermoplastic Pavement Markings Installation of Tubular Markers, Collapsible Bollards

300204101623000	29.) 24LI0036 - Bantacan-Magsaysay Road in support of Coconut, Rice, and Banana Plantation, New Bataan, Davao de Oro	Const. Section	YES	Competitive Bidding	11/24/23-11/30/23	12/14/24	03/07/24	03/15/24	GoP	20000000	-	20000000	Concreting (width=6.70 m., thk.=280 mm) Sta. 0+000.000 – Sta. 0+220.000 = 220.00 meters (Section 1) Sta. 0+000.000 – Sta. 0+880.000 = 880.00 meters (Section 2) Roadway Excavation Application of Reflectorized Thermoplastic Pavement Markings
320101111395000	30.) 24LI0040 - Construction of Flood Control Structure along Agusan River, Prk. 6 Section, Barangay Poblacion, Monkayo, Davao de Oro Phase I	Const. Section	NO	Competitive Bidding	02/08/24-02/14/24	02/29/24	03/25/24	03/26/24	GoP	150000000	-	150000000	Construction of Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for End Protection Works Installation of Railings Removal of Existing Structure
320102106675000	31.) 24LI0043 - Construction of Revetment along Agusan River Phase 1, Purok 8, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/24-02/14/24	02/29/24	03/25/24	03/26/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for End Protection Works
310202101766000	32.) 24LI0010 - Road Widening – Benigno S. Aquino Jr. National Highway – K 1601+000 – K 1601+440	Const. Section	NO	Competitive Bidding	02/08/2024 – 02/14/2024	02/29/24	04/16/24	04/19/24	GoP	22750000	-	22750000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing Width 6.7m., with Additional 2 Lanes, Total Width 13.4m K 1601+000 – K 1601+440 = 440.00 meters AS PER RBIA K 1601+000 – K 1601+440 = 440.00 meters AS PER PLAN Paved Shoulders, 150 thk. Construction of Concrete Lined Canal and Other Minor Drainage Structure Roadway Excavation Removal of Structures and Obstruction Construction of Slope Protection (Grouted Riprap) Installation of Metal Guardrails including Concrete Post Installation of Hazard Markers, Chevron Signs Application of Reflectorized Thermoplastic Pavement Markings

310202101767000	33.) 24LI0011 - Road Widening – Benigno S. Aquino Jr. National Highway – K 1604+000 – K 1604+760	Const. Section	NO	Competitive Bidding	02/08/2024 - 02/14/2024	02/29/24	04/16/24	04/19/24	GoP	35000000	-	35000000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing Width 6.7m, with Additional 2 Lanes, Total Width 13.4m K 1604+000 – K 1604+760 = 760.00 meters AS PER RBIA K 1604+000 – K 1604+760 = 760.00 meters AS PER PLAN Paved Shoulders, 150mm thk. Construction of Concrete Lined Canal and other Minor Drainage Structure Roadway Excavation Removal of Existing Guardrails and Posts Removal of Structures and Obstruction Construction of Slope Protection (Grouted Riprap) Installation of Metal Guardrails including Concrete Post Application of Reflectorized Thermoplastic Pavement Markings
300227100146000	34.) 24LI0038 - Construction of Multi-Purpose Building (DEPED District Supervisor's Office) at Cabinuangan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/2024 - 02/14/2024	02/29/24	04/16/24	04/19/24	GoP	5000000	-	5000000	Construction of Admin Building including Foundation Works, Structural Works, Exterior and Interior Works (Tiles, Ceiling, etc.) Airconditioning Unit, Fire Extinguisher, Electrical Works and Plumbing Works.
310204102407000	35.) 24LI0039 - Mapawa-Bahi-Langgawisan, Maragusan, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/2024 - 02/14/2024	02/29/24	04/16/24	04/19/24	GoP	60000000	-	60000000	Concreting (width = 6.10m., thk. = 230 mm) Sta. 0+917.000 – Sta. 1+510.000 = 593.00 meters Paved Shoulders, 150mm thk. Roadway Excavation Construction of Concrete Lined Canal and other Minor Drainage Structure Application of Reflectorized Thermoplastic Pavement Markings
300226110259000	36.) 24LI0044 - Construction of Multi-Purpose Building, Purok 8, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/2024 - 02/14/2024	02/29/24	04/16/24	04/19/24	GoP	30000000	-	30000000	Construction/Completion of Multi-Purpose Building (Slaughterhouse) Phase 2 with Earthworks, Site Development, Plain and Reinforced Concrete Works, Finishing and Other Civil Works including Painting Works, Plumbing Works, Steel Doors and Windows, Railings, Structural Steel Works, Metal Structure, Electrical Works (Transformer with Billing Deposit, Generator Set with Complete Accessories and Generator Room), Mechanical Works (Airconditioning Unit, Fire Extinguisher, Overhead Tank including Structure, Water Pumping System, Valves and Fittings), CCTV (including Internet) Water Supply (Sewerage Treatment Facility) and Condemnation Pit (4m x 4m x 3m)

300226115649000	37.) 24LI0046 - Construction (Completion) of Multi-Purpose Building at New Alegria, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/2024 - 02/14/2024	02/29/24	04/16/24	04/19/24	GoP	5000000	-	5000000	Completion of Brgy. Hall Includes the following: 1.) Removal of Existing Masonry Work. 2.) Completion of Roofing and Roof Framing, Masonry Works, Tile Works, Ceiling Works, Plumbing Works, Electrical Works and 4 Sets Fire Extinguisher. 3.) Airconditioning Units 4.) Installation of Signage and Logo
320101112222000	38.) 24LI0017 - Construction of Upper Naboc CIS Protection Dike L/S at Dam Upstream, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/24- 02/14/24	03/07/24	04/17/24	04/19/24	GoP	15000000	-	15000000	Construction of Reinforced Concrete Revetment Installation of Gabions for Partition Construction of Grouted Riprap for End Protection Works
320101111396000	39.) 24LI0041 - Construction of Flood Control Structure along Agusan River, Prk. 6 Section, Barangay Poblacion, Monkayo, Davao de Oro Phase II	Const. Section	NO	Competitive Bidding	02/08/24- 02/14/24	03/07/24	04/17/24	04/19/24	GoP	150000000	-	150000000	Construction of Concrete Revetment with Steel Sheet Pile for Foundation Construction of Grouted Riprap Back-slope Protection Installation of Railings
320102106676000	40.) 24LI0042 - Construction of Revetment along Agusan River Phase 2, Purok 8, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/24- 02/14/24	03/07/24	04/17/24	04/19/24	GoP	150000000	-	150000000	Construction of Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for Back-Slope Protection Construction of End Protection Structure
320102106666000	41.) 24LI0047 - Construction of Flood Mitigation Structure along Agusan River Prk. 6, Osmeña, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/24- 02/14/24	03/07/24	04/17/24	04/19/24	GoP	120000000	-	120000000	Construction of Reinforced Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for Back-Slope Protection Construction of End Protection Structure
310203100789000	42.) 24LI0048 - Road Widening - Montevista-Compostela-Mati Bdry Rd - K1474 + 964 - K1476 + 348, K1474 + 358 - K1474 + 543	Const. Section	NO	Competitive Bidding	02/08/24- 02/14/24	03/07/24	04/17/24	04/19/24	GoP	61000000	-	61000000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing Width 6.7m, with Additional 2 lanes, Total Width 13.4m K 1474+358 - K 1474+543 AS PER RBIA K 1474+964 - K 1476+348 AS PER RBIA K 1474+358 - K 1474+543 = 185m AS PER PLAN K 1474+964 - K1476+343 = 1,379m AS PER PLAN Paved Shoulder, 150mm thk Roadway Excavation Construction of Slope Protection (Grouted Riprap) Construction of Concrete Lined Canal and other Minor Drainage Structure Installation of Metal Guardrails including Concrete Post Application of ReflectORIZED Thermoplastic Pavement Markings Removal of Structures and Obstruction Removal of Existing Guardrails and Posts

310202101606000	43.) 24LI0049 - Road Widening - Nabunturan - Maragusan Rd - K 1468+847 - K 1470+147	Const. Section	NO	Competitive Bidding	02/08/24- 02/14/24	03/07/24	04/17/24	04/19/24	GoP	64560000	-	64560000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing Width 6.7m, with Additional 2 Lanes, Total Width 13.4m K 1468+847 - K 1470+147 AS PER RBIA K 1468+760 - K 1470-060 = 1,300 meters AS PER PLAN Roadway Excavation Paved Shoulders, 230mm thk Construction of Concrete Lined Canal and other Minor Drainage Structure Removal of Structures and Obstruction Construction of Retaining Wall Construction of Slope Protection (Grouted Riprap) Removal and Installation of Metal Guardrails including Concrete Post Application of Reflectorized Thermoplastic Pavement Markings
300226115676000	44.) 24LI0050 - Construction of Multi-Purpose Building, Monkayo Central Elementary School, Barangay Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/23/24- 02/29-24	03/14/24	04/18/24	04/22/24	GoP	20000000	-	20000000	Development and construction of two complete single-storey buildings, each housing five classrooms. This encompasses earthworks, concrete works, finishing touches, and various engineering tasks such as plumbing, installation of steel windows with grilles, tiling (both glazed and unglazed), painting across concrete, masonry, wood, and steel surfaces, as well as the incorporation of reflective insulation, corrugated roofing, railings. structural steel works, metal structure accessories, electrical installations, and mechanical systems including ventilation, fire alarm systems, and fire extinguishers.
300226115655000	45.) 24LI0051 - Construction of Multi-Purpose Building at Cabaunangan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	02/23/24- 02/29-24	03/14/24	04/18/24	04/22/24	GoP	50000000	-	50000000	Construction of Complete Covered Court with concrete slab, painting works applied to steel, masonry and concrete surfaces, as well as marking court lines (floor finishes), installation of lighting fixtures, provision of weatherproof electrical outlets, and concrete pedestal for electrical service entrance.
300226115663000	46.) 24LI0052 - Construction of Multi-Purpose Building, Barangay Osmeña, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	02/23/24- 02/29-24	03/14/24	04/18/24	04/22/24	GoP	70000000	-	70000000	Construction of Complete Barangay Hall (12.75m x 14.50m) incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning for the Barangay Captain's office and conference hall, and the inclusion of stainless water tank and fire extinguisher

300219102686000	47.) 24LI0053 - Construction of Revetment along Aunan Creek (Junction L/S) leading to Agusan River, Barangay Babag, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/23/24- 02/29-24	03/14/24	04/18/24	04/22/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment with Concrete Barriers and Steel Sheet Piles for Foundation Construction of Grouted Riprap for Backslope Protection and End Protection Structure Construction of Gabions for End Protection Structure
310102101643000	48.) 24LI0054 - Preventive Maintenance of Road: Asphalt Overlay – Benigno S. Aquino Jr. National Highway K1414+800-K1417+000, K1419+385 – K1422+204, K1425+000 – K1425+291	Const. Section	NO	Competitive Bidding	02/23/24- 02/29-24	03/14/24	04/18/24	04/22/24	GoP	100000000	-	100000000	Asphalt Overlay (50mm thk.) L1, L2, L5, L6 K1414+800 – K1415+311 AS PER RBIA K1414+800 – K1415+311 = 511 meters AS PER PLAN L2, L5 K1415+311 – K1417+000 AS PER RBIA K1415+311 – K1417+000 = 1,689 meters AS PER PLAN L2, L5 K1419+385 – K1422+204 AS PER RBIA K1419+387 – K1422+211 = 2,824 meters AS PER PLAN L1, L2, L5, L6 K1425+000 – K1425+094 AS PER RBIA K1424+946 – K1425+040.814 = 94.814 meters AS PER PLAN L1, L6 K1425+094 – K1425+160 AS PER RBIA K1425+040.814 – K1425+105.750 = 64.936 meters AS PER PLAN L1, L2, L5, L6 K1425+160 – K1425+291 AS PER RBIA K1425+105.75 – K1425+237 = 131.25 meters AS PER PLAN Application of Concrete Joint Sealant Application of Reflectorized Thermoplastic Pavement Markings
310103101441000	49.) 24LI0055 - Preventive Maintenance of Road: Asphalt Overlay – Montevista – DNAS Rd K1413+000 – K1416+000, K1429+406 – K1431+541	Const. Section	NO	Competitive Bidding	02/23/24- 02/29-24	03/14/24	04/18/24	04/22/24	GoP	100000000	-	100000000	Asphalt Overlay (50mm thk.) L1, L2, L3, L4 K1413+000 – K1414+189 AS PER RBIA K1412+999 – K1414+189 = 1,190 meters AS PER PLAN L2, L3 K1414+189 – K1415+541 AS PER RBIA K1414+189 – K1415+489 = 1,300 meters AS PER PLAN L1, L2 K1415+541 – K1416+000 AS PER RBIA K1415+489 – K1415+887 = 398 meters AS PER PLAN L1, L2 K1429+406 – K1431+541 AS PER RBIA K1428+741 – K1430+859 = 2,118 meters AS PER PLAN Application of Concrete Joint Sealant Application of Reflectorized Thermoplastic Pavement Markings

300226115653000	50.) 24LI0056 - Construction of Multi-Purpose Building (Classroom) at Moncast, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/29/24-03/06/24	03/26/24	04/22/24	04/23/24	GoP	20000000	-	20000000	Construction of One (1) Unit. Two (2) Storey Six (6) (9.5m x 33.7m.) Classroom with Toilet, Provision of Safety Grilles (front window), Steel Casement (rear window), Fire Protection System, Fire Escape, Cistern and Overhead Tank, Blackboard, Painting Works and Electrical Works
300226115661000	51.) 24LI0057 - Construction of Multi-Purpose Building, Barangay Maparat, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	02/29/24-03/06/24	03/26/24	04/22/24	04/23/24	GoP	70000000	-	70000000	Construction of Complete Barangay Hall (12.75m x 14.50m) incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning for the Barangay Captain's office and conference hall, and the inclusion of stainless water tank and fire extinguisher.
300219102687000	52.) 24LI0061 - Construction of Revetment along Aunan Creek (Upstream L/S) leading to Agusan River, Barangay Babag, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/29/24-03/06/24	03/26/24	04/22/24	04/23/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment with Concrete Barriers and Steel Sheet Piles for Foundation Construction of Grouted Riprap for Backslope Protection and End Protection Works
320102106674000	53.) 24LI0062 - Construction of Revetment along Agusan River (Lower Mapawa Bridge Section), Mapawa, Maragusan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/12/24-03/18/24	04/02/24	04/22/24	04/23/24	GoP	100000000	-	100000000	Construction of Reinforced Concrete Revetment with Concrete Barriers and Steel Sheet Piles for Foundation Construction of Gabions for End Protection Works
320102106677000	54.) 24LI0063 - Construction of Revetment along Manat River (Upstream and Downstream L/S) leading to Agusan River Phase 1, Bankeruhan Norte, Montevista, Davao de Oro	Const. Section	NO	Competitive Bidding	03/12/24-03/18/24	04/02/24	04/22/24	04/23/24	GoP	120000000	-	120000000	Construction of Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for Backslope Protection and End Protection Works Installation of Minor Drainages

310202101765000	55.) 24LI0065 - Road Widening – Benigno S. Aquino Jr. National Highway – K1425+867 – K1426+179, K1606+609 – K1606+850	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	35000000	-	35000000	<p>Concreting of Additional 2 lanes (4 into 6 lanes, 280 mm thk.)</p> <p>Existing Width 13.4m. width Additional 2 Lanes, Total Width 20.10m</p> <p>K 1425+867 – K 1426+179 AS PER RBIA</p> <p>K 1425+885 – K 1426+168 = 283.00 meters AS PER PLAN</p> <p>Paved Shoulder, 230mm thk.</p> <p>Construction of Concrete Lined Canal and other Minor Drainage Structure</p> <p>Application of Reflectorized Thermoplastic Pavement Marking</p> <p>Roadway Excavation</p> <p>Construction of Sidewalk, 100 mm thk.</p> <p>Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.)</p> <p>Existing Width 6.7m, with Additional 2 Lanes, Total Width 13.4m</p> <p>K 1606+609 – K 1606+850 AS PER RBIA</p> <p>K 1606+609 – K 1606+850 = 241.00 meters AS PER PLAN</p> <p>Paved Shoulder, 230mm thk.</p> <p>Construction of Retaining Wall (Stone Masonry)</p> <p>Removal of Existing Guardrails and Posts</p> <p>Removal of Structure and Obstruction</p> <p>Installation of Metal Guardrails including Concrete Post and Metal Beam End Piece</p>
300226115652000	56.) 24LI0067 - Construction of Multi-Purpose Building (Building 2), Barangay Mangayon, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	5000000	-	5000000	<p>Construction of a complete concrete bleacher including painting works, reinforced concrete, structural steel, glass windows, wooden doors, fiber cement board for interior ceiling, metal spandrel for exterior ceiling, masonry, comfort rooms, a pediment between court and bleacher roofs, ramps, stairs, lighting fixtures, gutter, roof flashing, and tileworks.</p>
300105201474000	57.) 24LI0070 - Construction (Completion) of Multi-Purpose Building (CENRO Office) at Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	5000000	-	5000000	<p>Construction (Completion) of Multi-Purpose Building (CENRO) with Earthworks, Removal of Structures and Obstruction, Plain and Reinforced Concrete Works, Finishing and Other Civil Works including Glass Door and Windows, Ceiling Works (Acoustical Ceiling and Pre-painted Metal Panel), Wall (Aluminum Cladding, Logo and Stainless Steel Letters), Tile Works (Glazed, Unglazed and Tactile Blocks), Painting Works (CHB/Masonry and Steel), Structural Steel Works (Roof Framing), Metal Structure (Fire Escape), Waterproofing, Electrical Works (including Transformer and Billing Deposit) and Mechanical Works (Fire Alarm System and Fire Extinguishers and Wall Mounted Type (Inverter) Air Conditioning Units).</p>

30022611566000	58.) 24LI0071 - Construction of Multi-Purpose Building, Barangay Poblacion, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	10000000	-	10000000	Construction of Complete Covered Court, painting works applied to steel, masonry and concrete surfaces, as well as making court lines (floor finishes), installation of lighting fixtures, provision of weatherproof electrical outlets, and concrete pedestal for electrical service entrance.
300226115650000	59.) 24LI0073 - Construction (Completion) of Multi-Purpose Building, Davao de Oro State College, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	20000000	-	20000000	Construction (Completion) of Academic Building Phase III, Davao de Oro State College, Compostela, Davao de Oro with reinforced concrete works (3rd and 4th floor beams and columns, and 4th and 5th floor slab), finishing works, painting works (masonry and steel), tile works, plumbing works and electrical works.
300226115664000	60.) 24LI0074 - Construction of Multi-Purpose Building, Barangay Pagsabangan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	10000000	-	10000000	Construction of Covered Court with Bleacher including concrete slab, painting works applied to steel, masonry and concrete surfaces, as well as marking court lines (floor finishes), Electrical Works, and Other Metal Structures
300219102981000	61.) 24LI0075 - Construction of Flood Mitigation Structure, Purok 2 Creek, Gabi, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	5000000	-	5000000	Construction of Reinforced Concrete Box Culvert with Apron and Wingwall Construction of Grouted Riprap Revetment Channel Excavation Installation of Minor Drainage
300226115665000	62.) 24LI0076 - Construction of Multi-Purpose Building, Barangay Panansalan, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/22/24	04/23/24	GoP	5000000	-	5000000	Construction of Complete Covered Court with concrete slab, painting works applied to steel, masonry and concrete surfaces, as well as marking court lines (floor finishes), installation of lighting fixtures, provision of weatherproof electrical outlets, and concrete pedestal for electrical service entrance.
300215104100000	63.) 24LI0066 - Construction of Road, JNH Lincan to Barangay San Vicente – Barangay San Isidro, Montevista, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/16/24	04/23/24	04/24/24	GoP	100000000	-	100000000	Concreting (width = 6.10 m., 230 mm thk) Sta. 2+251.000 – Sta. 5+121.000 = 2,870 m Roadway Excavation Removal of Actual Structures/Obstruction Paved Shoulder 150mm thk Construction of Concrete Lined Canal and other Minor Drainage Structure Construction of Slope Protection (Grouted Riprap) Construction of Sidewalk with Curb and Gutter Installation of Metal Guardrails including Concrete Post with Metal Beam End Piece Installation of Warning Signs (W6-1B), Pedestrian and School Signs Pedestrian Crossing Ahead Installation of Regulatory Signs (R6-8C), Miscellaneous Signs Pedestrian Crossing Installation of Hazard Markers, Chevron Signs Application of Reflectorized Thermoplastic Pavement Markings

300215104102000	64.) 24LI0068 - Construction of Road, Monkayo-Boston Road (Monkayo Section), Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/24-03/31/24	04/18/24	04/23/24	04/24/24	GoP	80000000	-	80000000	Construction of Reinforced Concrete Retaining Wall Sta. 0+000.000 – Sta. 0+160.000 = 160.00 m Section 1 Sta. 0+020.000 – Sta. 0+145.000 = 125.00 m Section 2 Roadway Excavation Construction of Concrete Lined Canal
320102106671000	65.) 24LI0077 - Construction of Flood Mitigation Structure along Manat River (Manat Bridge Upstream) leading to Agusan River, Barangay New Visayas, Monte Vista, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment with Steel Sheet Piles for Foundation Construction of Reinforced Concrete Box Culvert with Apron and Wingwall Removal and Replacement of Existing PCCP – K1414+361.800 – K1414+376.800 = 15.000 lm. Remove and Reinstall Existing Guardrails Construction of Grouted Riprap End Protection Structure Construction of Grouted Riprap Back-slope Protection and Concrete Barriers Installation of Minor Drainages
300221106881000	66.) 24LI0078 - Construction of Road, Barangay Tandawan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	15000000	-	15000000	Concreting (width=6.10m., 230mm thk) Sta. 0+000.000-Sta. 0+128.452 = 128.452m Sta. 0+128.452-Sta. 0+132.012 = 3.56m RCBC (3m x 3m x 10m) Sta. 0+132.012-Sta. 0+260.000 = 127.988 Paved Shoulder 150mm thk Roadway Excavation Construction of Concrete Lined Canal and Other Minor Drainage Structure Construction of Slope Protection (Grouted Riprap) Installation of Metal Guardrails including Concrete Post and Metal Beam End Piece Application of ReflectORIZED Thermoplastic Pavement Marking
300226115660000	67.) 24LI0079 - Construction of Multi-Purpose Building, Barangay Manurigao, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	13000000	-	13000000	Construction of Completion Barangay Hall (12.75m x 14.50m) incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of solar panel with inverter and battery, and the inclusion of stainless water tank and fire extinguisher
300215104102000	68.) 24LI0081 - Construction of Revetment along Manat River leading to Agusan River at Inambatan Bridge (Downstream), Barangay Olaycon, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	100000000	-	100000000	Construction of Reinforced Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap for Backslope Protection Construction of Reinforced Concrete Barrier

300219102962000	69.) 24LI0082 - Construction of Revetment along Upper Agusan River, Barangay Osmeña, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	50000000	-	50000000	Construction of Reinforced Concrete Revetment with Concrete Barriers and Steel Sheetpiles for Foundation Construction of Grouted Riprap and Gabion End Protection Structures
300226115667000	70.) 24LI0083 - Construction of Multi-Purpose Building (Municipal Engineering Building), Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	10000000	-	10000000	The Rehabilitation of MPB (Municipal Engineering Building) includes the Following: 1.) Construction of Complete Powerhouse w/ Electrical Works 2.) Modular Cubicles, Tables, Chairs, and Cabinets 3.) WPC and Decorative Stone, Logo and Letters at Lobby and Brass Plate Marker 4.) 3 Units 75 KVA Transformers and Complete Accessories and Billing Deposit 5.) Airconditioning Units 6.) Site Development (Paver Blocks at the Front and Sides of the Building)
300226115645000	71.) 24LI0084 - Construction (Completion) of Multi-Purpose Building, Barangay Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	4000000	-	4000000	Construction (Completion) of Multi-Purpose Building with electrical works including conduits, boxes and fittings, wires and wiring devices, panelboard with main and branch breakers, and supply, delivery, installation, testing and commissioning of Three Phase Generator with Automatic Transfer Switch complete with accessories.
300226115671000	72.) 24LI0086 - Construction of Multi-Purpose Building, Barangay Poblacion, Maragusan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	8000000	-	8000000	Construction of Multi-Purpose Building (Covered Court) with Earthworks, Removal of Structures and Obstruction, Plain and Reinforced Concrete Works, Finishing and Other Civil Works including Catch Basin, Storm Drainage and Downspout, Painting Works (CHB/Masonry and Steel), Structural Steel Works (Roof Framing), Metal Structure and Electrical Works.
300219102980000	73.) 24LI0087 - Construction of Flood Mitigation Structure along Maputi Creek leading to Agusan River, Poblacion, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	50000000	-	50000000	Construction of Reinforced Concrete Revetment with Concrete Barriers Installation of Minor Drainages Channel Excavation
300226115658000	74.) 24LI0088 - Construction of Multi-Purpose Building, Barangay Bagongon, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	7000000	-	7000000	Construction of Complete Barangay Hall incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning for the Barangay Captain's office and conference hall, and the inclusion of stainless water tank and fire extinguisher.

300226115654000	75.) 24LI0089 - Construction of Multi-Purpose Building (Phase I), Barangay Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	04/23/24	04/24/24	GoP	30000000	-	30000000	Construction of Barangay Hall (Phase I) incorporating earthworks (excavation embankment and gravel fill), reinforced concrete works, plumbing, masonry works, cement plaster finishing, painting works, along with electrical works (conduits)
300219102979000	76.) 24LI0090 - Construction of Flood Mitigation Structure along Mamunga Creek leading to Agusan River, Barangay Mamunga, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/23/24	04/24/24	GoP	50000000	-	50000000	Construction of Reinforced Concrete Revetment with Concrete Barriers and mattresses for foot protection Installation of Gabion Closures Installation of Grouted Riprap for Backslope Installation of Groundsill
300226115669000	77.) 24LI0089 - Rehabilitation of Multi-Purpose Building, Cogonon, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-03/31/24	04/23/24	04/29/24	05/07/24	GoP	50000000	-	50000000	Construction/Rehabilitation of Multi-Purpose Building rubberized paint (court lines only), basketball goal, steel louvers and complete 8.5 x 11m Stage including Earthworks, Plain and Reinforced Concrete Works, Finishing and Other Civil Works including Painting Works (Masonry/Concrete and Steel, Structural Steel Works (Roof Framing), Fence and Electrical Works.
300205101349000	78.) 24LI0085 - Construction of Water System, Barangay San Miguel, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/23/24	04/29/24	05/07/24	GoP	50000000	-	50000000	Construction of 1 unit Concrete Reservoir Construction of 1 unit Sump tank Installation of PE Pipes, Valves and Pipe Fittings
300226115647000	79.) 24LI0091 - Construction (Completion) of Multi-Purpose building (IP building) at Barangay Mapeca, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	50000000	-	50000000	Construction/Completion of Multi-Purpose Building incorporating earthworks, reinforced concrete work, plumbing, tiling, ceiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning, and the inclusion of stainless water tank and fire extinguisher.
300226115657000	80.) 24LI0092 - Construction of Multi-Purpose Building at Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	100000000	-	100000000	Construction of Barangay Hall (Phase II) with reinforced, painting works applied to steel, masonry and concrete surfaces, installation of lighting fixtures, provision of weatherproof electrical outlets, and concrete pedestal for electrical service entrance

300215104083000	81.) 24LI0093 - Construction of Temporary Access Road for Mayaon Bridge along Montevista (Jct. Mayaon) -- Laak Diversion Road, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	25000000	-	25000000	Concreting (width = 6.10m., 230 mm thk) Sta. 0+000.000 -- Sta. 0+330.000 = 330.000 m Construction of Overflow Paved Shoulder 150mm thk Roadway Excavation Construction of Concrete Lined Canal and other Minor Drainage Structure Handlaid Rock Embankment Construction of Concrete, Slope Protection Installation of Metal Guardrail (Metal Beam) including Post Application of Reflectorized Thermoplastic Pavement Marking Installation of Single Arm Solar LED Roadway Lighting
300226115678000	82.) 24LI0094 - Rehabilitation of Multi-Purpose Building (Congressional), Barangay Poblacion, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	5000000	-	5000000	Rehabilitation of Building which includes earthworks, reinforced concrete works, carpentry and joinery works, floor finishes, painting works (steel), provision of oscillating fan and aircon, corrugated asphalt roofing and electrical works.
300219102681000	83.) 24LI0095 - Construction of Flood Mitigation Structure along Kalamokan Creek leading to Agusan River, Bangoy Bridge Section, Barangay San Roque, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment Construction of Grouted Riprap end Protection Works Removal of Existing Structures and Obstruction Installation of Minor Drainages
300219102978000	84.) 24LI0096 - Construction of Flood Mitigation Structure along Lower Magangit Creek, Barangay Magangit, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	10000000	-	10000000	Construction of Reinforced Concrete Revetment with concrete barriers and mattresses for foot protection Construction of Grouted Riprap end protection structure Removal of Existing Structures and Obstruction
300205101348000	85.) 24LI0097 - Construction of Water System, Barangay New Alegria, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	5000000	-	5000000	Construction of 1 unit Concrete Reservoir Construction of 1 unit Sump tank Installation of PE Pipes, Valves and Pipe Fittings
300205101347000	86.) 24LI0098 - Construction of Water System at Tandawan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	5000000	-	5000000	Construction of 1 Unit Steel Tank – 10k gallons Construction of Intake Box, Collection Box Installation of PE Pipes, Valves and Pipe Fittings
300219102684000	87.) 24LI0099 - Construction of Flood Mitigation Structure along Macao Creek leading to Agusan River at Purok 4A to Purok 2, Phase 1, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/27/24-04/02/24	04/23/24	04/29/24	05/07/24	GoP	75000000	-	75000000	Construction of Reinforced Concrete Box Culvert with Apron and Wingwall Construction of Reinforced Concrete Revetment with Mattresses for Foot Protection Installation of Minor Drainages

310203211030000	88.) 24LI0100 - Concreting of Brgy. Panansalan FMR Phase II, Brgy. Panansalan, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/24-04/11/24	04/25/24	05/20/24	05/24/24	GoP	15000000	-	15000000	Concreting of road (width=6.10m, thk. = 230mm) Sta. 1+845.000 – Sta. 2+283.000 = 438.00m Paved Shoulder 150mm thk. Roadway Excavation Construction of concrete lined canal and other minor drainage structures Installation of Metal Guardrails including Concrete Post with Metal Beam End Piece Application of Reflectorized Thermoplastic Pavement Markings Construction of DA Kilometer Post
310203211059000	89.) 24LI0101 - Concreting of Brgy. Poblacion FMR, Brgy. Poblacion, Maragusan, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/24-04/11/24	04/25/24	05/20/24	05/24/24	GoP	15000000	-	15000000	Concreting of road (width = 5.00m, thk. = 230mm) Sta. 0+000.000 – Sta. 0+709.000 = 709.00 m Roadway Excavation Construction of DA Kilometer Post
310203211032000	90.) 24LI0102 - Concreting of Brgy. Bankerohan Norte FMR, Brgy. Bankerohan, Montevista, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/24-04/11/24	04/25/24	05/20/24	05/24/24	GoP	15000000	-	15000000	Concreting of road (width = 5.00m, thk. = 230mm) Sta. 0+000.000 – Sta. 0+487.000 = 487.00 m Roadway Excavation Construction of concrete lined canal and other minor drainage structures Installation of Metal Guardrail Including Concrete Post and Metal Beam End Piece Construction of DA Kilometer Post
310203211031000	91.) 24LI0103 - Concreting of Purok 6 to Purok 3, Brgy. New Cebulan connecting to Junction Provincial Road going to Brgy. Mayaoon FMR Phase IV, Brgy. New Cebulan, Montevista, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/24-04/11/24	04/25/24	05/20/24	05/24/24	GoP	15000000	-	15000000	Concreting of road (width = 5.00m, thk. = 230mm) Sta. 0+000.000 – Sta. 0+552.000 = 552.00m Roadway Excavation Construction of concrete lined canal and other minor drainage structures Installation of Metal Guardrail Including Concrete Post and Metal Beam End Piece Installation of Metal Guardrail Including Concrete Post and Metal Beam End Piece
300101200001000	92.) 24LI0104 - Construction of 1 Unit of 2-Storey 4-Classroom School Building in Coronobe Integrated School, Maragusan, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/24-04/11/24	04/25/24	05/20/24	05/24/24	GoP	18371955	-	18371955	Construction of Complete Two(2) Storey Four(4) Classroom School Building with concrete parapet, corridor railings at 2nd floor, steel casement window at rear portion with security grilles for the front jalousie windows, fire protection system, overhead tank and cistern. Generator set and power house.

300101200001000	93.) 24LI0105 - Construction of 1 Unit of 1-Storey 2-Classroom School Building in Corazon C. Aquino NHS, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/24-04/11/24	04/25/24	05/20/24	05/24/24	GoP	5845350	-	5845350	Construction of Complete One(1) Unit, One(1)-Storey Two(2) Classroom School Building with Toilet attached. This also includes Window Grilles (rear and front), Concrete Parapet, Handwashing Facility, Permit and Clearances, and Site Development.
310203211058000	94.) 24LI0107 - Concreting of Brgy. New Magangit FMR, Brgy. Magangit, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	04/04/24-04/10/24	04/25/24	05/20/24	05/24/24	GoP	15000000	-	15000000	Concreting of road (width = 5.00m, thk. = 230mm) Sta. 0+000.000 – Sta. 0+630.000 = 630.00m Roadway Excavation Removal of Actual Structures/Obstruction Construction of RCBC (2.40m x 3.0m x 9.0m) Construction of concrete lined canal and other minor drainage structures Construction of DA Kilometer Post
310203211061000	95.) 24LI0108 - Concreting of Brgy. New Albay FMR, Brgy. New Albay, Maragusan, Davao de Oro	Const. Section	NO	Competitive Bidding	04/04/24-04/10/24	04/25/24	05/20/24	05/24/24	GoP	50000000	-	50000000	Concreting of road (width = 5.0m, thk. = 230mm) Sta. 0+000.000 – Sta. 1+520.000 = 1,520.00m Roadway Excavation Embankment from Borrow (Common Soil) Construction of RCBC (3m x 3m x 9m) Construction of concrete lined canal and other minor drainage structures Construction of DA Kilometer Post
320101111393000	96.) 24LI0109 - Construction of Flood Mitigation Structure along Aguibawa River, Bantacan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	04/04/24-04/10/24	04/25/24	05/20/24	05/24/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment with Concrete Barriers and Steel Sheet Piles for Foundation Construction of Reinforced Concrete Box Culvert (6.00m x 3.100m) with Barriers, Apron and Wingwall Removal and Replacement of Existing PCCP = 182.000 lm. Construction of Grouted Riprap End Protection Structure Construction of Grouted Riprap Back-slope Protection
300219102672000	97.) 24LI0110 - Construction of Flood Mitigation Structure along Maoao Creek leading to Agusan River at Purok 4A to Purok 2, Phase 2, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	04/04/24-04/10/24	04/25/24	05/20/24	05/24/24	GoP	100000000	-	100000000	Installation of High Density Polyethylene Pipes for Main drain Installation of Catch Basins with Manhole Removal and Replacement of Existing PCCP Installation of Sheetpiles for Temporary Retaining Wall

300226115659000	98.) 24LI0058 - Construction of Multi-Purpose Building, Barangay Bantacan, New Bataan, Davao de Oro	Const. Section	NO	Competitive Bidding	02/29/24-03/06/24	03/26/24	05/20/24	05/24/24	GoP	7000000	-	7000000	Construction of Complete Barangay Hall (12.75m x 14.50m) incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning for the Barangay Captain's office and conference hall, and inclusion of stainless water tank and fire extinguisher.
300226115662000	99.) 24LI0059 - Construction of Multi-Purpose Building, Barangay Ngan, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	02/29/24-03/06/24	03/26/24	05/20/24	05/24/24	GoP	7000000	-	7000000	Construction of Complete Barangay Hall (12.75m x 14.50m) incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning for the Barangay Captain's office and conference hall, and the inclusion of stainless water tank and fire extinguisher.
300226115651000	100.) 24LI0060 - Construction of Multi-Purpose Building (Building 1), Barangay Mangayon, Compostela, Davao de Oro	Const. Section	NO	Competitive Bidding	02/29/24-03/06/24	03/26/24	05/20/24	05/24/24	GoP	7000000	-	7000000	Construction of Complete Barangay Hall (12.75m x 14.50m) incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting, carpentry and joinery works, along with electrical work (lighting fixtures, outlets, and concrete pedestal), signage and logo installation, provision of air conditioning for the Barangay Captain's office and conference hall, and the inclusion of stainless water tank and fire extinguisher.
300226108920000	101.) 24LI0072 - Rehabilitation of Multi-Purpose Building (Sangguniang Bayan Office) at Barangay Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/25/2024 - 03/31/2024	04/16/24	06/11/24	06/18/24	GoP	30000000	-	30000000	Rehabilitation of Multi-Purpose Building (Sangguniang Bayan Office) with Earthworks, Removal of Structures and Obstruction, Plain and Reinforced Concrete Works, Finishing and Other Civil Works including Plumbing Works, Tempered Glass Door and Windows, Ceiling Works (Fiber Cement Board, Acoustical Ceiling and Pre-painted Metal Panel), Aluminum Cladding, Tile Works (Glazed and Unglazed), Painting Works (CHB/Masonry, Wood and Steel), Structural Steel Works, Waterproofing, Electrical Works and Mechanical Works.

300226115648000	102.) 24L0080 - Construction (Completion) of Multi-Purpose Building (Monkayo Municipal Dome), Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	03/26/24-04/01/24	04/18/24	06/11/24	06/18/24	GoP	15000000	-	15000000	Construction/Completion of MPB (Monkayo Municipal Dome) Includes the Following: 1) Construction/Completion of VIP Lounge (Complete w/ Electrical works). 2) Rehabilitation of Comfort Room at VIP Lounge. 3) Painting Works on the Rear Portion of Stage and on VIP Lounge Existing Structures. 4) Construction of Powerhouse w/ Distribution Transformer (3-100Kva) 5) 1-300Kva, 230v, 60Hz. Brand New Standby Three Phase Diesel Generator (Silent Type) 6) Airconditioning Units at VIP Lounge
300217100278000	103.) 24L0106 - Replacement of Mayaon Bridge along Montevista (Jct. Mayaon) – Laak Diversion Road, Davao de Oro	Const. Section	NO	Competitive Bidding	04/05/2024 - 04/11/2024	04/25/24	06/11/24	06/18/24	GoP	90000000	-	90000000	Construction of Concrete Approach Slab (width = 6.10m., thk. = 230 mm) Approach A Sta. 0+000.000 – Sta. 0+200.000 = 200.00 meters Approach Slab Sta. 0+200.000 – Sta. 0+204.000 = 4.00 meters Approach Slab Sta. 0+249.000 – Sta. 0+253.000 = 4.00 meters Approach B Sta. 0+253.000 – Sta. 0+453.000 = 200.00 Concrete Paving of Shoulders Installation of Road Sign and Hazard Marker (Chevron Signs) Installation of Metal Guardrails with Concrete Post and Metal Beam End Piece Application of Reflectorized Thermoplastic Pavement Markings Scope of Works (Bridge) : Construction of 1-45 In.m PSCG Bridge Sta. 0+204.000 – Sta. 0+249.000 = 45.00 meters Removal of Existing Structures/Obstruction Construction of Board Piles with Abutment Protection Construction of Grouted Riprap (Slope Protection) Application of Reflectorized Thermoplastic Pavement Markings

300205100015000	104.) 24LI0064 - Construction of Rainwater Collection System (RWCS): 2ND District Engineering Office, Compostela, Davao de Oro 1. Katipunan Elementary School, Brgy. Katipunan, New Bataan, Davao de Oro 2. Magsaysay Elementary School, Brgy. Magsaysay, New Bataan, Davao de Oro 3. San Vicente Integrated School, Brgy. San Vicente, Montevista, Davao de Oro 4. Maragusan Central Elementary School, Brgy. Poblacion, Maragusan, Davao de Oro 5. Olaycon Integrated School, Brgy. Olaycon, Monkayo, Davao de Oro 6. Union National High School – Mt. Diwata Annex, Brgy. Union, Monkayo, Davao de Oro 7. Montevista Stand Alone Senior High School, Brgy. Poblacion, Montevista, Davao de Oro	Maintenance Section	NO	Competitive Bidding	05/21/24 - 05/27/24	06/11/24	06/24/24	06/25/24	GoP	2970000	-	2970000	Construction of Rainwater Collection System (RWCS)
200000100020000	105.) 24LI0111 - Repair/Maintenance of Tigbawa Creek Revetment 4, Brgy. Poblacion, Montevista, Davao de Oro	Maintenance Section	NO	Competitive Bidding	05/21/24 - 05/27/24	06/11/24	06/24/24	06/25/24	GoP	4000000	-	4000000	Construction of Reinforced Concrete Revetment Section 1 Sta. 0+015.000 – Sta. 0+025.000 = 10.00 meters Section 2 Sta. 0+087.000 – Sta. 0+092.000 = 5.00 meters Section 3 Sta. 0+145.000 – Sta. 0+180.000 = 35.00 meters Section 4 Sta. 0+195.000 – Sta. 0+200.000 = 5.00 meters Section 5 Sta. 0+220.000 – Sta. 0+250.000 = 30.00 meters Section 6 Sta. 0+015.000 – Sta. 0+040.000 = 25.00 meters Section 7 Sta. 0+010.000 – Sta. 0+060.000 = 50.00 meters -Common Surplus Excavation Removal of Existing Reinforced Concrete Pavement Construction of Grouted Riprap Slope Protection
200000100019000	106.) 24LI0112 - Repair/Maintenance of DILG Building BJMP Guardhouse, Brgy. New Visayas, Montevista, Davao de Oro	Maintenance Section	NO	Competitive Bidding	05/21/24 - 05/27/24	06/11/24	06/24/24	06/25/24	GoP	1500000	-	1500000	Rehabilitation of Guardhouse including the following: Removal and Replacement of Roofing Removal of Structures and Obstruction Installation of Doors and Windows Completion of Roofing and Roof Framing, Masonry Works, Painting Works, Tile Works, Ceiling Works, Plumbing Works, Electrical Works and 2 Sets Fire Extinguisher.

300226115646000	107.) 24LI0114 - Rehabilitation (Completion) of Multi-Purpose Building (RHU Building), Phase III, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	05/29/24-06/04/24	06/18/24	06/24/24	06/25/24	GoP	50000000	-	50000000	Completion of 2 Storey RHU Building Includes the Following: 1)Concrete Works (on Remaining Footings, Columns and Grid Beams) 2)35 Steel Columns w/ Base Plate and Anchore Bolts (from ground floor to second floor) 3)Beams (at level 4 and level 8 beams) from A to H along GRID 1 to 8 "See Beam Plan for Reference" 4)Perimeter Wall and Embankment from Grid Beam to Finish Floor Line 5)Painting Works on Steel Structure w/ Fire Protection Coating
300232100034000	108.) 24LI0115 - Rehabilitation of Multi-Purpose Building (RHU Building), Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	05/29/24-06/04/24	06/18/24	06/24/24	06/25/24	GoP	10000000	-	10000000	Rehabilitation of MPB Includes the Following: 1)Nine (9) Steel Column at Level (0-4m) and Three (7) Steel Column at Level (4m-8m) 2)Steel Beams at Level 4 & 8 (Grid 5-8 between D to H) 3)Steel Beams at Level 4 (Grid 4-6 between H to K) at Level 8 (Grid 4-6 between H to I) 4)Steel Painting including Steel Fire Protection Paint
300226115670000	109.) 24LI0045 - Construction of Multi-Purpose Building at Monkayo Central ES, Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	02/08/24-02/14/24	-	-	-	GoP	25000000	-	25000000	Concreting of Additional 2 lanes (2 into 4 lanes, 280 mm thk.) Existing width 6.7m, with Additional 2 Lanes, Total Width 13.4m K1468+847 – K1470+147 = 1,300 meters AS PER RBIA K1468+847 – K1470+060 = 1,213 meters AS PER RBIA Roadway Excavation Paved Shoulders, 280mm thk Construction of Concrete Lined Canal and other Minor Drainage Structure Removal of Structure and Obstruction Construction of Slope Protection (Grouted Riprap) Construction of Retaining Wall Removal and Reinstallation of Metal Guardrails including Concrete Post Application of Reflectorized Thermoplastic Pavement Markings
300226115669000	110.) 24LI0116 - Construction of Multi-Purpose Building, Purok 6-A, Brgy Poblacion, Montevista, Davao de Oro	Const. Section	NO	Competitive Bidding	05/29/24-06/04/24	-	-	-	GoP	50000000	-	50000000	Construction of Multi-Purpose Building incorporating earthworks, reinforced concrete works, plumbing, tiling, cement plaster finishing, painting works, along with electrical work (lighting fixtures, outlets, and concrete pedestal)


310102101645000	111.) 24LI0117 - Preventive Maintenance of Road: Asphalt Overlay – Nabunturan – Maragusan Rd K1466+025 – K 1466+527, K1466+539 – K 1472+264	Const. Section	NO	Competitive Bidding	06/11/24- 06/17/24	07/02/24	07/24/24	07/26/24	GoP	100000000	-	100000000	Asphalt Overlay (50 mm thk.) Lane 1 & 2 K1466+025 – K1466+527 AS PER RBIA Lane 1 & 2 K1466+539 – K1470+147 AS PER RBIA Lane 2 & 3 K1470+147 – K1472+264 AS PER RBIA Application of Concrete Joint Sealant Application of Reflectorized Thermoplastic Pavement Markings K1466+025 – K1466+498 = 473.00m AS PER PLAN S1 K1466+524 – K1469+999 = 3,475.00m AS PER PLAN S2 K1469+999 – K1472+116 = 2,117.00m AS PER PLAN S2
310102101637000	112.) 24LI0118 - Preventive Maintenance of Road: Asphalt Overlay – Benigno S. Aquino Jr. National Highway (S01432MN) K1596+000 – K1597+366, K1599+000 – K1599+471, K1599+522 – K1601+816, K1601+835 – K1606+000, K1613+320 – K1613+604, K1613+651 – K1615+588, K1615+620 – K1615+778	Const. Section	NO	Competitive Bidding	06/11/24- 06/17/24	07/02/24	07/24/24	07/26/24	GoP	150000000	-	150000000	Asphalt Overlay (50 mm thk.) Lane 1 & 2 K1596+000 – K1597+271 AS PER RBIA Lane 2 & 3 K1597+271 – K1597+366 AS PER RBIA Lane 2 & 3 K1599+000 – K1599+291 AS PER RBIA Lane 1 & 2 K1599+291 – K1599+471 AS PER RBIA Lane 1 & 2 K1599+522 – K1601+816 AS PER RBIA Lane 1 & 2 K1601+835 – K1606+000 AS PER RBIA Lane 2 & 3 K1613+320 – K1613+540 AS PER RBIA Lane 1 & 2 K1613+540 – K1613+604 AS PER RBIA Lane 1 & 2 K1613+651 – K1613+700 AS PER RBIA Lane 2 & 3 K1613+700 – K1615+500 AS PER RBIA Lane 1 & 2 K1615+500 – K1615+588 AS PER RBIA Lane 1 & 2 K1615+620 – K1615+690 AS PER RBIA Lane 2 & 3 K1615+690 – K1615+778 AS PER RBIA Application of Concrete Joint Sealant Application of Reflectorized Thermoplastic Pavement Markings K1596+000 – K1597+196 = 1,196.00 m AS PER PLAN S1 K1597+196 – K1597+291 = 95.00 m AS PER PLAN S1 K1599+031 – K1599+325 = 294.00 m AS PER PLAN S2 K1599+325 – K1599+487 = 162.00 m AS PER PLAN S2 K1599+539 – K1601+826 = 2 287.00 m AS

310103101440000	113.) 24LI0119 - Preventive Maintenance of Road: Asphalt Overlay – Montevista – Compostela – Mati Bdry. Rd K1434+000 – K1438+002, K1470+773 – K1473+000, K1477+000 – K1478+794 (Section 2)	Const. Section	NO	Competitive Bidding	06/11/24- 06/17/24	07/02/24	07/24/24	07/26/24	GoP	150000000	-	150000000	Asphalt Overlay (50mm thk.) L1, L4 K1434+000 – K1436+367 AS PER RBIA L1, L2, L3, L4 K1436+367 – K1438+002 AS PER RBIA L1, L2 K1470+773 – K1473+000 AS PER RBIA L1, L2 K1477+000 – K1477+140 AS PER RBIA L2, L3 K1477+140 – K1478+794 AS PER RBIA Application of Concrete Joint Sealant Application of ReflectORIZED Thermoplastic Pavement Markings K1434+000 – K1436+375 = 2,375.00 m AS PER PLAN S1 K1436+375 – K1438+003.50 = 1,628.50 m AS PER PLAN S1 K1470+870 – K1472+846.5 = 1,976.500 m AS PER PLAN S2 K1477+000 – K1477+140 = 140.00 m AS PER PLAN S3 K1477+140 – K1478+794 = 1,654.00 m AS PER PLAN S3
310102101644000	114.) 24LI0120 - Preventive Maintenance of Road: Asphalt Overlay – Nabunturan - Maragusan Rd K1456+532 - K1458+603, K1458+633 – K1463+000 (Section 1)	Const. Section	NO	Competitive Bidding	06/11/24- 06/17/24	07/02/24	07/24/24	07/26/24	GoP	100000000	-	100000000	Asphalt Overlay (50mm thk.) L2, L3 K1456+532 – K1457+886 AS PER RBIA L1, L2 K1457+886 – K1458+603 AS PER RBIA L1, L2 K1458+633 – K1463+000 AS PER RBIA Application of Concrete Joint Sealant Application of ReflectORIZED Thermoplastic Pavement Markings K1456+521 – K1457+857 = 1,336.000 meters AS PER PLAN S1 K1457+857 – K1458+515.400 = 658.400 meters AS PER PLAN S1 K1458+545.600 – K1462+785.200 = 4,239.600 meters AS PER PLAN S2

310103101439000	115.) 24L10121 - Preventive Maintenance of Road: Asphalt Overlay – Montevista – Compostela – Mati Bdry. Rd K1428+000 – K1432+070, K1432+215 – K1434+000, K1478+794 – K1479+555, K1479+588 – K1481+062 (Section 1)	Const. Section	NO	Competitive Bidding	06/11/24- 06/17/24	07/02/24	07/24/24	07/26/24	GoP	150000000	-	150000000	Asphalt Overlay (50mm thk.) L1, L2, L3, L4 K1428+000 – K1428+338 AS PER RBIA L1, L4 K1428+338 – K1428+542 AS PER RBIA L1, L2, L3, L4 K1428+542 – K1429+923 AS PER RBIA L1, L4 K1429+923 – K1432+070 AS PER RBIA L1, L4 K1432+215 – K1434+000 AS PER RBIA L2, L3 K1478+794 – K1479+355 AS PER RBIA L1, L2 K1479+355 – K1479+555 AS PER RBIA L1, L2 K1479+588 – K1479+688 AS PER RBIA L2, L3 K1479+688 – K1480+062 AS PER RBIA Application of Concrete Joint Sealant Application of Reflectorized Thermoplastic Pavements Markings K1428+000 – K1428+338.10 = 338.10 m AS PER PLAN S1 K1428+338.10 – K1428+541.70 = 203.60 m AS PER PLAN S1 K1428+541.70 – K1429+879.50 = 1,337.80 m AS PER PLAN S1 K1429+879.50 – K1432+072.50 = 2,193.00 m AS PER PLAN S1 K1432+214 – K1434+000 = 1,786.00 m AS PER PLAN S2 K1478+794 – K1479+333.50 = 539.50 m AS PER PLAN S3 K1479+333.50 – K1479+523 = K1479+523 = 189.50 m AS PER PLAN S3 K1479+565 – K1479+674.30 = 109.30 m AS PER PLAN S4 K1479+674.30 – K1481+045.50 = 1,372.20
300215104087000	116.) 24L10122 - Construction of Road, Barangay Poblacion, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	06/19/24- 06/25/24	07/09/24	07/24/24	07/26/24	GoP	50000000	-	50000000	Concreting (width = 6.10 m., 230 mm thk) Sta. 0+341.500 – Sta. 1+466.510 = 1,125.010 m (Section 1) Sta. 0+000.000 – Sta. 0+341.140 = 341.140 m (Section 2) Sta. 0+000.000 – Sta. 0+100.000 = 100.000 m (Section 3) Sta. 0+000.000 – Sta. 0+763.850 = 763.850 m (Section 4) Paved Shoulder 150mm thk Roadway Excavation Construction of Concrete Lined Canal and Other Minor Drainage Structure Handlaid Rock Embankment Construction of slope protection (Grouted Riprap) Application of Reflectorized Thermoplastic Pavement Marking

300215104097000	117.) 24L10123 - Construction of Road, Barangay Rizal - Barangay Baylo, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	06/19/24-06/25/24	07/09/24	07/24/24	07/26/24	GoP	150000000	-	150000000	Concreting (width = 6.10 m., 230 mm thk) Sta. 0+341.500 - Sta. 1+486.510 = 1,125.010 m (Section 1) Sta. 0+000.000 - Sta. 0+341.140 = 341.140 m (Section 2) Sta. 0+000.000 - Sta. 0+100.000 = 100.000 m (Section 3) Sta. 0+000.000 - Sta. 0+783.850 = 783.850 m (Section 4) Paved Shoulder 150mm thk Roadway Excavation Construction of Concrete Lined Canal and Other Minor Drainage Structure Handlaid Rock Embankment Construction of slope protection (Grouted Riprap) Application of ReflectORIZED Thermoplastic Pavement Marking
320102106672000	118.) 24L10113 - Construction of Flood Mitigation Structure along Manat River leading to Agusan River, Barangay New Visayas, Montevista, Davao de Oro	Const. Section	NO	Competitive Bidding	06/28/24-07/04/24	07/09/24	07/24/24	07/26/24	GoP	150000000	-	150000000	Construction of Reinforced Concrete Revetment with Steel Sheet Piles for Foundation Construction of Grouted Riprap End Protection Structure Removal and Replacement of existing Irrigation Canal Installation of Drainage (Reinforced Concrete Pipe Culvert - 1520mm dia.)
310105101062000	119.) Benigno S. Aquino Jr. National Highway K1417+000 - K1419+835	Const. Section	NO	Competitive Bidding	06/24/24-06/30/24	07/16/24	07/22/24	07/26/24	GoP	150000000	-	150000000	Preventive Maintenance
310105101063000	120.) Benigno S. Aquino Jr. National Highway K1422+204 - K1425+000	Const. Section	NO	Competitive Bidding	06/24/24-06/30/24	07/16/24	07/22/24	07/26/24	GoP	150000000	-	150000000	Preventive Maintenance
300101200001000	121.) Construction of 2 Units of 2-Storey 10-Classroom School Building in Monkayo CES, Monkayo, Davao de Oro	Const. Section	NO	Competitive Bidding	06/24/24-06/30/24	07/16/24	07/22/24	07/26/24	GoP	75532695	-	75532695	Multi-Purpose Building
300200100003000	122.) Reconstruction/Rehabilitation of Damaged Paved Road (Approach Slab at Bangoy Bridge) - Montevista - Compostela - Mati Boundary (K1438+427 - K1438+577) which was damaged by Continuous Heavy Rains	Const. Section	NO	Competitive Bidding	06/24/24-06/30/24	07/16/24	07/22/24	07/26/24	GoP	19149000	-	19149000	Construction of Reinforced Concrete Revetment

Prepared By:


EDWIN L. PASQUAL, JR.
Head, Procurement Unit

Recommended by:


EDWIN L. JACOB
BAC Chairperson

Approved by:


MINDA R. ROSLINDA
District Engineer