

Republic of the Philippines DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS OFFICE OF THE SECRETARY

Bonifacio Drive, Port Area Manila

AUG 2 7 2010

08.31.2000

DEPARTMENT ORDER) No. 41) Series of 2010 $0? \cdot 4 - 7^{2}$) x - x - x - x - x - x - x - x - x - x SUBJECT

: Prescribing the Use of Coconut Bio-Engineering Technology Solutions in DPWH Projects

In order to fully support the program of the government to adopt indigenous products/technologies in infrastructure projects and generate employment in the countryside, the use of coconut bio-engineering products and solutions in all DPWH projects/activities that involve slope stabilization, soil conditioning, soil erosion prevention, river bank protection and/or hydroseeding is hereby prescribed to be given priority in the design consideration, for the information and guidance of all concerned DPWH Project Implementing Offices.

This Department Order is consistent with D.O. No. 62, series of 2009 entitled "*Reiterating D.O. Nos. 28 and 29, both series of 2008, re: DPWH Standard Specifications for By Bio-Engineering Product and Solutions (Item 519) and Coconut Bio-Engineering Solutions (Item 518),"* respectively and shall take effect immediately.

ROGELIÓ L. SINGSON

Secretary



Attachments: As stated

REPUBLIC OF THE PHILIPPINES DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS **OFFICE OF THE SECRETARY** MANILA DEC 1 1 2009 DEPARTMENT ORDER SUBJECT : Reiterating D.O. Nos. 28 and 29, both Series of 2008, re: DPWH Standard

No. **D**2 Series of 2009 **x-x-x-x-x-x-x-x-x-x-x** Reiterating D.O. Nos. 28 and 29, both Series of 2008, re: DPWH Standard Specifications for BY Bio-Engineering Products and Solutions (Item 519) and Coconut Bio-Engineering Solutions (Item 518), respectively

In line with and in full support of the program of the government to adopt relatively new indigenous products/technologies in our infrastructure projects that are specifically designed to prevent/mitigate the disastrous and devastating effects of natural calamities brought about by climate change, Department Order Nos. 28 and 29, both series of 2008 (copies attached, including their respective Specifications) allowing the use of coconut bio-engineering products/solutions in all DPWH projects/activities that involve slope stabilization, soil conditioning, soil erosion prevention and/or hydroseeding, are hereby reiterated, for the information and guidance of all concerned DPWH Project Implementing Offices.

Likewise, pursuant to Memorandum Circular No. 25 dated 02 September 2002 of the President of the Philippines entitled "Directing All National and Local Government Agencies, Bureaus, and Other Instrumentalities Including Agricultural Institutions and Councils to Use Coco Peat or Coir Dust and Coconut Fiber Materials for Soil Conditioning and Erosion Control", copy also attached, our Department is one (1) of the three (3) line agencies of the government that was tasked to adopt and promote the use of bio-engineering products/technologies (or any variations thereof) as the need arises, subject to the applicable specifications formulated for the product.

A Certificate of Conditional Approval had already been issued by this Department accrediting/allowing the use of the above-mentioned product/technology in DPWH projects.

This Order shall take effect immediately.

VICTOR A. DOMINGO Acting Secretary



Attachments: As stated.

MALACAÑANG Manila

MEMORANDUM CIRCULAR NO. 25

DIRECTING ALL NATIONAL AND LOCAL GOVERNMENT AGENCIES, BUREAUS, AND OTHER INSTRUMENTALITIES INCLUDING AGRICULTURAL INSTITUTIONS AND COUNCILS TO USE COCO PEAT OR COIR DUST AND COCONUT FIBER MATERIALS FOR SOIL CONDITIONING AND EROSION CONTROL

In line with the program to promote better farm practices and environment conservation to mitigate the effect of drought during El Niño years, all heads of National and Local Government agencies, bureaus, and instrumentalities including Government institutions and councils involved in the implementation of farming programs are hereby directed to prescribe the use of coco peat and other coconut husk materials in farming and horticulture as effective soil conditioner and water moisture conservator.

Likewise, the use of geo-textiles and bio-logs or fascines made from coir or coconut fiber is hereby prescribed for use in infrastructure and public work projects for soil erosion control, more particularly of the Department of Public Works and Highways. These coir products, proven for their high tensile strength are abundant, available and biodegradable.

The use of coir will further provide additional income to coconut farmers and generate more jobs in the countryside.

The Department of Agriculture, the Department of Public Works and Highways and the Philippine Coconut Authority shall issue the corresponding Implementing Guidelines within thirty (30) days from the date of issuance of this Memorandum Circular.

For strict compliance.

Manila, September 2, 2002

By the President:

ALBERTO G. ROMULO Executive Secretary

Mang



G	ERTIFIED COPY:
	1055
	LAMPERTOR, BARBIN
'sl	19-4-02 Malocasinag - 1900

BKS # 343 P3 12



REPUBLIC OF THE PHILIPPINES DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS OFFICE OF THE SECRETARY MANILA

MAY 1 4 2008

DEPARTMENT ORDER) No. 29) Series of 2008 - of . 16. of) x-x-x-x-x-x-x-x-x-x

SUBJECT: DPWH Standard Specifications For Coconet Bio-Engineering Solutions, Item 518

In line with the continuing efforts to upgrade the construction technology thru adoption of successful research studies, this Department has approved the use of **Coconet Bio-Engineering Solutions, Item 518** for controlling soil erosion and slope stabilization, subject to the specifications hereto attached. A Certificate of Conditional Approval had been issued by this Department, accrediting the use of Coconet Bio-Engineering Solutions in DPWH Projects, from January 2008 until January 2013.

This order shall take effect immediately.

HERMOGEI



Attachment: As stated

DPWH STANDARD SPECIFICATIONS FOR

ITEM 518 – COCONET BIO-ENGINEERING SOLUTIONS

518.1 Description

This item covers installation of coconut coir fiber made into geonets such as coco-nets/mats, coco-logs/fascines, coco-twines and coco peat as bioengineering materials for controlling soil erosion and slope stabilization in accordance with the cross section shown on the Plans or as directed by the Engineer.

518.2 Definition

For the purpose of this item, the following terms shall be defined:

a)	Coconut Geonets	-	any coconut coir fiber-based placed in sloping lands and embankments to hold the vulnerable soil and permit vegetative growth to control surface erosion and conserve the productivity of the soil.
b)	Coco-net	-	coconut coir fiber twine woven into blankets of different density.
c)	Coco-log/Fascine	-	a tubular structure of coconut coir fiber blankets of different diameter filled with coco coir, and/or coco peat.
d)	Coco coir twine	-	a string made of coconut coir strands twisted together.
e)	Coco coir peat	-	a natural and residual materials from coconut coir which serves as soil conditioner.

518.3 Material Requirements

518.3.1 Coconut Coir

Coconut coir fiber materials for use in fabrication of coconut geonets shall be a multi-cellular fiber with 12 to 24 microns in diameter and the ratio of

length to diameter shall be 35. The fiber shall also be hygroscopic, with moisture content of 10% to 12% at 65% humidity and 22% to 55% at 95% relative humidity.

518.3.2 Coco-net and Coco-log/Fascine

The hand-spun coco coir twine that is to be woven into coconut geonets shall have a diameter of 5mm plus or minus 10%. The coco coir twine shall have a tensile strength of not less than 150N.

Coco-net and Coco-log/fascine shall conform to Table 1 and Table 2 respectively.

Table 1 Physical Properties of Coco-net

Type of Coco-net	Average Number Of Twines at Crosswise Direction	Average Number Of Twines at Lengthwise Direction	Density (min) (gm/m ²)
Coco-net 400	40	40	400
Coco-net 700	40	70	700
Coco-net 900	70	70	900

Table 2 Physical Properties of Coco-log

Type of Coco-log/Fascine	Diameter (min) (cm)	Weight (min) (Kg/m)
Coco-log 100	10	2.0
Coco-log 200	20	4.5
Coco-log 300	30	10
Coco-log 400	40	20
Coco-log 500	50	30

518.3.3 Backfill

Backfill shall be of the class indicated on the Plans and shall conform to the requirements of Item 104 – Embankment.

518.3.4 Bamboo Stakes

Bamboo stakes shall be mature and shall be 3 to 4 cm in width and 25 to 30 cm long.

518.3.5 Live Plant Stakes

Live plant stakes shall be kept moist and installed the same day they were prepared.

518.4 Construction Requirements

518.4.1 Quality Control

The coconut geonets manufacturer shall be responsible for establishing and maintaining a quality control program to assure compliance with the requirements of this specification.

518.4.2 Equipment

Equipment and tools necessary for handling materials and performing all parts of the works shall be approved by the Engineer as to design, capacity and mechanical condition. The equipment shall be at the jobsite sufficiently ahead of the start of construction operations.

518.4.3 Site Measurement

Site measurements shall be done to prepare specific lengths of the coco-nets to conform the necessary area requirements and the necessary length for coco-logs/fascines to be installed/placed.

518.4.4 Preparation of Bed

Site for net installation shall be graded and sloped to the approved design and any runoff control such as diversions, dikes and berms shall be completed prior to installation. All depression/gullies and eroded portions shall be backfilled for the coco-nets to snugly come in contact with the soil surface. The face of the slope shall be smoothened. Rocks, clods, vegetation (deemed detrimental to the erosion control system to be installed), and other obstructions shall be removed from tip to toe of the slope to ensure complete contact of the coco-nets with the soil.

Existing vegetations that are considered not detrimental shall be retained, but shall be trimmed down to facilitate the installation of the coconut geonets.

518.4.5 Anchoring

1. Common Soil

The coconut geonets shall be secured to the ground using bamboo pegs. An average of 3 pegs per square meter shall be used to ensure uniform contact of coco-net to the ground surface. For loose soils, longer pegs shall be used to have sufficient ground penetration to resist pullout.

2. Compacted Soil

A combination of bamboo pegs and U-shaped wire staples may be used for compacted, hard to penetrate soil. An average of 3 pegs/staples per square meter shall be used to ensure uniform contact of coco-net to the ground surface.

3. Hard Rock

The coconut geonets shall be anchored to solid rock surfaces using metal stake pins with a minimum diameter of 8mm and length of 20 to 30 cm.

518.4.6 Installation/Placing of Coconut Geonets

The coconut geonets shall be used on critical cut slopes, embankments and disturbed soils generally steeper than 3:1, where water velocities are likely to wash out soils and new vegetation. Coco-nets shall be placed and anchored on the graded surface of the slope to maximize net contact with the slope surface. Installation shall begin at the top of the slope with the coco-net laid down and securely anchored 1m from the edge of the slope by folding underneath the leading edges of the coco-net to ensure that no twines would come loose. After which the coco-nets shall then be unrolled downslope in the direction of the water flow. Adjacent coco-nets/coco-mats shall be installed side-by-side and shall be sewn together using coco coir twine. The coco-nets shall be laid loosely (not stretched) on the ground. Coconet shall then be fastened and secured firmly to the ground in accordance to Subsection 518.4.5, Anchoring. Anchoring shall be at right angle to the ground surface.

When necessary, coco-logs/fascines shall be used in conjunction with coco-nets installation to reduce long slopes and as major stopper of downward movement of soil as rainwater carries them downslope. It shall be placed across the slope on contour and shall be pegged with lives stakes (vegetative cuttings from locally suitable plants) to the ground at 1m intervals. For slopes with loose soil, the coco-logs/fascines shall be installed on trenches. The trench shall be deep enough to accommodate half the diameter of the coco-logs. Contour interval shall be 1 to 8m depending on the steepness of the slope and the erodibility of the soil.

518.4.7 Placing of Coco Coir Peat (Soil Conditioner)

After the installation of coconut geonets, coco coir peat-soil mixture shall be distributed evenly on the net protected slope. Thumping and raking shall follow to make the mix settle underneath to ensure appropriate soil moisture and nutrient release as grasses and other planting materials shall be planted.

518.4.8 Vegetation

1. Vetiver Grass Hedgerow

Live hedgerow of vetiver grass (or any local suitable species) slips shall be planted on the slopes at 10 to 50 cm plant interval depending on the erosivity of the soil, the steepness of the slope, and the design waterflow. Row distance shall likewise depend on the steepness of the slope, and shall range from 1 to 4 m.

2. Grass cover

Fast growing leguminous creeping/twining grass cover shall be used for slope faces requiring immediate vegetative cover. It shall be applied to the soil at a rate depending on the desired plant density and the calculated on-site mortality rate of the plants.

3. Trees

If trees shall be used to stabilize a slope, species that have sturdy, long, and deep-penetrating roots shall be selected.

Whereas, in water channels or rivers, appropriate plants that can thrive in water or water saturated condition, while functioning to prevent bank erosion shall be used. Numerous other considerations shall be taken into account in choosing the proper planting materials. These plant properties shall include, drought resistance, effect on local ecology, aesthetics, etc.

518.4.9 Performance Monitoring

Post project monitoring shall include checking on any breaks of the installed coconut geonets especially at the point of junctions, the growth of grasses and the manifestation of any failure of germination of plants and the sudden outburst of rain that might have inflicted damaged to some sections. Repair works shall be done on damaged sections of the slope and replacement shall be done in case of plant mortality.

Watering, weeding and fertilization may be done subject to the discretion of the contractor's bioengineer or plant specialist. Maintenance activities shall be terminated upon the recommendation of the bioengineer and approval of the owner.

518.5 Certification

The manufacturer shall file with the purchaser a certificate stating the name of the manufacturer, the composition of the coconut geonets as bioengineering materials and other pertinent information so as to fully describe the coir materials. The manufacturer shall include in the certificate a guarantee stating that the bioengineering materials that are furnished meet the required specifications. The certificate shall be attested by a person having legal authority to bind the company. Either mismarking or misrepresentation by the manufacturer shall be reason to discontinue acceptance under these specifications. The discontinuance of acceptance will be considered to be notice to all wholesalers, jobbers, distributors, agents and other intermediates handling the manufacturer's product.

518.6 Method of Measurement

The area to be paid for under this Item shall be the number of square meter of coco-net, linear meter for coco-log/fascines, square meter of live vetiver grass hedgerow and square meter of effective vegetative growth for grass cover, installed/placed and accepted into the completed project.

518.7 Basis of Payment

The accepted quantity, measured as prescribed in Section 518.6 shall be paid for at the contract unit price for coconut geonets, which price and payment shall be full compensation for preparation of bed and furnishing of all materials for placing/installation of coconut geonets and for furnishing all labor, maintenance of plants, equipment, tools and incidentals necessary to complete the Item.

Payment will be made under:

Pay Item Number	Description	Unit of Measurement
1	Coco-net	Square meter
2	Coco-logs/Fascine	Linear meter
3	Vegetation	Square meter

KEPUBLIC OF THE PHILIPPINES DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS OFFICE OF THE SECRETARY



CERTIFICATE OF CONDITIONAL APPROVAL

Product/Technology Accreditation

This is certify that

COCONET BIO-ENGINEERING SOLUTIONS

(Developed by Coco Technologies Corporation)

which is exclusively marketed and distributed in the Philippines by:

Hung Coco Coir Products

with office address at

107 Don A. Roses Ave., Brgy. Laging Handa, Quezon City

is duly accredited for use in DPWH projects as soil erosion control products and solutions in slopes, embankments and shore protection works, subject to its specifications (hereto attached) pursuant to the provisions of DPWH Department Order No.189, series of 2002.

This accreditation shall remain in force until expiry date printed below, subject to compliance with the requirements of the aforementioned Department Order.

Conditional Approval No.	:	014
Date Issued	:	January 2008
Expiry Date	:	January 2013

DANE, JR. HERMOGENES Secretary WIN8U00264

97. 13 DP64 05-16-2008 **REPUBLIC OF THE PHILIPPINES** DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS **OFFICE OF THE SECRETARY** MANILA MAY 1 4 2008



SUBJECT: DPWH Standard Specifications For BY Bio-Engineering Products and Solutions, Item 519

86

In line with the continuing efforts to upgrade the construction technology thru adoption of successful research studies, this Department has approved the use of **BY Bio-Engineering Products and Solutions, Item 519** for controlling soil erosion and slope stabilization, subject to the specifications hereto attached. A Certificate of Conditional Approval had been issued by this Department, accrediting the use of Bio-Engineering Products and Solutions in DPWH Projects, from August 2007 until August 2012.

This order shall take effect immediately.

HERMOGE



Attachment: As stated

DEPARTMENT ORDER No. 28 Series of 2008 ANNEX Page 1 of 7

DPWH STANDARD SPECIFICATIONS FOR

ITEM 519 – BY BIO-ENGINEERING PRODUCTS AND SOLUTIONS

519.1 Description

This item covers installation of coconut fiber made into geonets such as coconets/mats, coco-logs/fascines, coco-twines and coco peat as bioengineering materials for controlling soil erosion and slope stabilization in accordance with the cross section shown on the Plans or as directed by the Engineer.

519.2 Definition

For the purpose of this item, the following terms shall be defined:

a) Coconut Geonets	-	any coconut coir fiber-based placed in sloping lands and embankments to hold the vulnerable soil and permit vegetative growth to control surface erosion and conserve the productivity of the soil.
b) Coco-net/Coco-mat -		A woven coconut coir fiber twine stitched into blankets of different density.
c) Coco-log/Fascine	-	a tubular structure of coconut coir fiber blankets of different diameter filled with coco coir, and/or coco peat.
d) Coco coir twine	-	a string made of coconut coir strands twisted together.
e) Coco coir peat	-	a natural and residual materials from coconut coir which serves as soil conditioner.

519.3 Material Requirements

519.3.1 Coconut Coir

Coconut coir fiber materials for use in fabrication of coconut geonets shall be a multi-cellular fiber with 12 to 24 microns in diameter and the ratio of

length to diameter shall be 35. The fiber shall also be hygroscopic, with moisture content of 10% to 12% at 65% humidity and 22% to 55% at 95% relative humidity.

519.3.2 Coco-net/coco-mat and Coco-log/Fascine

The hand-spun coco coir twine that is to be woven into coconut geonets shall have a diameter of 5mm plus or minus 10%. The coco coir twine shall have a tensile strength of not less than 150N.

Coco-net/coco-mat and Coco-log/fascine shall conform to Table 1 and Table 2 respectively.

Table 1

Physical Properties of BY-F Products (Coco-net/Coco-mat)

Type of Coco-net	Average Number Of Twines at Crosswise Direction	Average Number Of Twines at Lengthwise Direction	Density (min) (gm/m ²)
BY-C 400	40	40	400
BY-C 700	40	70	700
BY-C 900	70	70	900

Table 2

Physical Properties of BY-F Products Coco-log/Fascines

Type of Coco-log/Fascine	Diameter (min) (cm)	Weight (min) (Kg/m)
BY-F 100	10	2.0
BY-F 200	20	4.5
By-F 300	30	10
BY-F 400	40	20
By-F 500	50	30

Table 3

Physical Properties of BY-F Products (Coco-Mats/Stitched Mat-BYM)

Type of Coco-Mats/Stitched Mats	Diameter (min) (cm)	Weight (min)
BY-M 1000	1.1	1000

519.3.3 Backfill

Backfill shall be of the class indicated on the Plans and shall conform to the requirements of Item 104 – Embankment.

519.3.4 Bamboo Stakes

Bamboo stakes shall be mature and shall be 3 to 4 cm in wide and 25 to 30 cm long.

519.3.5 Live Plant Stakes

Live plant stakes shall be kept moist and installed the same day they were prepared.

519.4 Construction Requirements

519.4.1 Quality Control

The coconut geonets manufacturer shall be responsible for establishing and maintaining a quality control program to assure compliance with the requirements of this specification.

519.4.2 Equipment

Equipment and tools necessary for handling materials and performing all parts of the works shall be approved by the Engineer as to design, capacity and mechanical condition. The equipment shall be at the jobsite sufficiently ahead of the start of construction operations.

519.4.3 Site Measurement

Site measurements shall be done to prepare specific lengths of the coco-nets/coco-mats to conform the necessary area requirements and the necessary length for coco-logs/fascines to be installed/placed.

519.4.4 Preparation of Bed

Site for net installation shall be graded and sloped to the approved design and any runoff control such as diversions, dikes and berms shall be completed prior to installation. All depression/gullies and eroded portions shall be backfilled for the coco-nets to snugly come in contact with the soil surface. The face of the slope shall be smoothened. Rocks, clods, vegetation (deemed detrimental to the erosion control system to be installed), and other obstructions shall be removed from tip to toe of the slope to ensure complete contact of the coco-nets with the soil.

Existing vegetations that are considered not detrimental shall be retained, but shall be trimmed down to facilitate the installation of the coconut geonets.

519.4.5 Anchoring

1. Common Soil

The coconut geonets shall be secured to the ground using bamboo pegs. An average of 3 pegs per square meter shall be used to ensure uniform contact of coco-net to the ground surface. For loose soils, longer pegs shall be used to have sufficient ground penetration to resist pullout.

2. Compacted Soil

A combination of bamboo pegs and U-shaped wire staples may be used for compacted, hard to penetrate soil. An average of 3 pegs/staples per square meter shall be used to ensure uniform contact of coco-net to the ground surface.

3. Hard Rock

The coconut geonets shall be anchored to solid rock surfaces using metal stake pins with a minimum diameter of 8mm and length of 20 to 30 cm.

519.4.6 Installation/Placing of Coconut Geonets

The coconut geonets shall be used on critical cut slopes, embankments and disturbed soils generally steeper than 3:1, where water velocities are likely to wash out soils and new vegetation. Coco-nets/cocomats shall be placed and anchored on the graded surface of the slope to maximize net contact with the slope surface. Installation shall begin at the top of the slope with the coco-net/coco-mat laid down and securely anchored 1m from the edge of the slope by folding underneath the leading edges of the coco-net to ensure that no twines would come loose. After which the coco-nets/coco-mats shall then be unrolled downslope in the direction of the water flow. Adjacent coco-nets/coco-mats shall be installed side-by-side and shall be sewn together using coco coir twine. The coco-nets/coco-mats shall be laid loosely (not stretched) on the ground. Coco-net/coco-mats shall then be fastened and secured firmly to the ground in accordance to Subsection 519.4.5, Anchoring. Anchoring shall be at right angle to the ground surface.

When necessary, coco-logs/fascines shall be used in conjunction with coco-nets/coco-mats installation to reduce long slopes and as major stopper of downward movement of soil as rainwater carries them downslope. It shall be placed across the slope on contour and shall be pegged with lives stakes (vegetative cuttings from locally suitable plants) to the ground at 1m intervals. For slopes with loose soil, the coco-logs/fascines shall be installed on trenches. The trench shall be deep enough to accommodate half the diameter of the coco-logs. Contour interval shall be 1 to 8m depending on the steepness of the slope and the erodibility of the soil.

519.4.7 Placing of Coco Coir Peat (Soil Conditioner)

After the installation of coconut geonets, coco coir peat-soil mixture shall be distributed evenly on the net protected slope. Thumping and raking shall follow to make the mix settle underneath to ensure appropriate soil moisture and nutrient release as grasses and other planting materials shall be planted.

519.4.8 Vegetation

1. Vetiver Grass Hedgerow

Live hedgerow of vetiver grass (or any local suitable species) slips shall be planted on the slopes at 10 to 50 cm plant interval depending on the erosivity of the soil, the steepness of the slope, and the design waterflow. Row distance shall likewise depend on the steepness of the slope, and shall range from 1 to 4 m.

2. Grass cover

Fast growing leguminous creeping/twining grass cover shall be used for slope faces requiring immediate vegetative cover. It shall DEPARTMENT ORDER No. <u>28</u> Series of 2008 ANNEX Page 6 of 7

be applied to the soil at a rate depending on the desired plant density and the calculated on-site mortality rate of the plants.

3. Trees

If trees shall be used to stabilize a slope, species that have sturdy, long, and deep-penetrating roots shall be selected.

Whereas, in water channels or rivers, appropriate plants that can thrive in water or water saturated condition, while functioning to prevent bank erosion shall be used. Numerous other considerations shall be taken into account in choosing the proper planting materials. These plant properties shall include, drought resistance, effect on local ecology, aesthetics, etc.

519.4.9 Performance Monitoring

Post project monitoring shall include checking on any breaks of the installed coconut geonets especially at the point of junctions, the growth of grasses and the manifestation of any failure of germination of plants and the sudden outburst of rain that might have inflicted damaged to some sections. Repair works shall be done on damaged sections of the slope and replacement shall be done in case of plant mortality.

Watering, weeding and fertilization may be done subject to the discretion of the contractor's bioengineer or plant specialist. Maintenance activities shall be terminated upon the recommendation of the bioengineer and approval of the owner.

519.5 Certification

The manufacturer shall file with the purchaser a certificate stating the name of the manufacturer, the composition of the coconut geonets as bioengineering materials and other pertinent information so as to fully describe the coir materials. The manufacturer shall include in the certificate a guarantee stating that the bioengineering materials that are furnished meet the required specifications. The certificate shall be attested by a person having legal authority to bind the company. Either mismarking or misrepresentation by the manufacturer shall be reason to discontinue acceptance under these specifications. The discontinuance of acceptance will be considered to be notice to all wholesalers, jobbers, distributors, agents and other intermediates handling the manufacturer's product.

519.6 Method of Measurement

The area to be paid for under this Item shall be the number of square meter of coco-net/coco-mat, linear meter for coco-log/fascines, square meter of live vetiver grass hedgerow and square meter of effective vegetative growth for grass cover, installed/placed and accepted into the completed project.

519.7 Basis of Payment

The accepted quantity, measured as prescribed in Section 519.6 shall be paid for at the contract unit price for coconut geonets, which price and payment shall be full compensation for preparation of bed and furnishing of all materials for placing/installation of coconut geonets and for furnishing all labor, maintenance of plants, equipment, tools and incidentals necessary to complete the Item.

Payment will be made under:

Pay Item Number	Description	Unit of Measurement
1	Coco-net/Coco-mat	Square meter
2	Coco-logs/Fascine	Linear meter
3	Vegetation	Square meter

Republic of the Philippines Department of Public Works and Highways OFFICE OF THE SECRETARY



CERTIFICATE OF CONDITIONAL APPROVAL

Product Accreditation

This is to certify that

BY BIO-ENGINEERING PRODUCTS and SOLUTIONS

which is exclusively distributed in the Philippines by:

SAMASA Consortium, Incorporated

with office address at

5th Floor 111 Paseo de Roxas Building, Paseo de Roxas Legazpi Village, Makati, Philippines

is duly accredited for use in DPWH projects as soil erosion control products and solutions in slopes, embankments and riverbanks, subject to its specifications (hereto attached) pursuant to the provisions of DPWH Department Order No. 189, series of 2002.

This accreditation shall remain in force until expiry date printed below, subject to compliance with the requirements of the aforementioned Department Order.

Conditional Approval No. Date Issued Expiry Date

<u>912</u> August 2007 August 2012

:

WIN7U00219 HERMOGE

Secretary

VE. JR.