


Contract ID: 25JF0009

Contract Name: BIP - Access Roads and/or Bridges from the National Road/s leading to Major/ Strategic Public Buildings/ Facilities - Construction of Road from National Highway, Barangay Mirangan - Sitio Botongan, Lagting, Siay, Zamboanga Sibugay (Phase 3)



Republic of the Philippines
Department of Public Works and Highways
ZAMBOANGA SIBUGAY 2ND DISTRICT ENGINEERING OFFICE
Lower Ipil Heights, Ipil, Zamboanga Sibugay



SUPPLEMENTAL BULLETIN NO. 2025-19
June 16, 2025

Subject: Revision of Bill of Quantities

This Supplemental Bulletin No. 2025-19 is issued to provision in the Bidding documents (BDs) for the above stated Contract, as follows:

	Current Provision of BDs (including Previous Amendments)	Amended Provision of BDs under this Supplemental Bulletin
Bill of Quantities	As Published in the Bidding Documents	See Revised Bill of Quantities

PUBLISHED BILL OF QUANTITIES (From)

Pay Item No.	Description	Unit	Quantity
(1)	(2)	(3)	(4)
PART A	Facilities For The Engineer		
A.1.1(8)	Provision of Field Office for the Engineer (Rental Basis)	month	5.84
A.1.4(1)	Provision of Progress Photographs	month	5.84
PART B	Other General Requirements		
B.3	Permits and Clearances	l.s.	1.00
B.4 (1)	Construction Survey and Staking	km.	0.58
B.5	Project Billboard / Signboard	each	2.00
B.7(2)	Occupational Safety and Health Program	l.s	1.00
B.8(1)	Traffic Management	month	5.84
B.9	Mobilization/Demobilization	l.s	1.00
PART C	EARHTWORKS		
102(2)	Surplus Common Excavation	Cu.m	2,178.57
103(1)a	Structure Excavation, Common Soil	cu.m.	312.17
103(5)a	Shoring, Cribbing, and related works, Shoring	l.s	1.00
104(1)a	Embankment From Roadway Excavation, Common Soil	cu.m	312.17

Contract ID: 25JF0009

Contract Name: BIP - Access Roads and/or Bridges from the National Road/s leading to Major/ Strategic Public Buildings/ Facilities - Construction of Road from National Highway, Barangay Mirangan - Sitio Botongan, Lagting, Siay, Zamboanga Sibugay (Phase 3)

105(1)a	Subgrade Preparation, Common Material	sq.m	1,401.55
PART D	SUBBASE AND BASE COURSE		
200(1)	Aggregate Subbase Course	cu.m	696.54
PART E	SURFACE COURSE		
311(1)a	Portland Cement Concrete Pavement (Unreinforced), 0.15m thk., 14 days	Sq.m	1,122.00
311(1)c1	Portland Cement Concrete Pavement (Unreinforced), 0.23m. thk., 14 days	sq.m	280.60
311(2)a	Portland Cement Concrete Pavement (Unreinforced), 0.15m. thk., 14 days	Sq.m	719.80
PART F	BRIDGE CONSTRUCTION		
401(1)a1	Metal Railing, Grade 36, Steel	m.	1,314.79
403(5)a1	Structural Steel, Furnished, Fabricated and Erected, Grade 36	Kg.	26,582.00
403(7)	Bolts and Nuts and Washers	l.s	1.00
404(1)a	Reinforcing Steel, Grade 40	Kg	27,463.33
404(1)b	Reinforcing Steel, Grade 60	Kg.	5,693.60
405(1)b3	Structural Concrete, 27.68 MPa, Class A, 28 days.	Cu.m	442.23
407(8)	Lean Concrete, Class B (16.5 MPa)	Cu.m	3.97
412(1)c	Elastomeric Bearing Pads	Each	8.00
414(1)	Forms and Falsework	l.s	1.00
PART G	DRAINAGE AND SLOPE PROTECTION STRUCTURES		
506(1)	Stone Masonry	m ³	192.18
PART C	FINISHING AND OTHER CIVIL WORKS		
1032(1)c	Painting Works, Steel	Sq.m	239.36

REVISED BILL OF QUANTITIES (To)

Pay Item No.	Description	Unit	Quantity
(1)	(2)	(3)	(4)
PART A	Facilities For The Engineer		
A.1.1(8)	Provision of Field Office for the Engineer (Rental Basis)	month	5.84
A.1.4(1)	Provision of Progress Photographs	month	5.84
PART B	Other General Requirements		
B.3	Permits and Clearances	l.s.	1.00
B.4 (1)	Construction Survey and Staking	km.	0.58
B.5	Project Billboard / Signboard	each	2.00
B.7(2)	Occupational Safety and Health Program	l.s	1.00
B.8(1)	Traffic Management	month	5.84

Contract ID: 25JF0009

Contract Name: BIP - Access Roads and/or Bridges from the National Road/s leading to Major/ Strategic Public Buildings/ Facilities - Construction of Road from National Highway, Barangay Mirangan - Sitio Botongan, Lagting, Siay, Zamboanga Sibugay (Phase 3)

B.9	Mobilization/Demobilization	l.s	1.00
PART C	EARHTWORKS		
102(2)	Surplus Common Excavation	Cu.m	2,178.57
103(1)a	Structure Excavation, Common Soil	cu.m.	312.17
103(5)a	Shoring, Cribbing, and related works, Shoring	l.s	1.00
104(1)a	Embankment From Roadway Excavation, Common Soil	cu.m	312.17
105(1)a	Subgrade Preparation, Common Material	sq.m	1,401.55
PART D	SUBBASE AND BASE COURSE		
200(1)	Aggregate Subbase Course	cu.m	696.54
PART E	SURFACE COURSE		
311(1)a	Portland Cement Concrete Pavement (Unreinforced), 0.15m thk., 14 days	Sq.m	1,077.00
311(1)c1	Portland Cement Concrete Pavement (Unreinforced), 0.23m. thk., 14 days	sq.m	524.60
311(2)a	Portland Cement Concrete Pavement (Unreinforced), 0.15m. thk., 14 days	Sq.m	658.80
PART F	BRIDGE CONSTRUCTION		
401(1)a1	Metal Railing, Grade 36, Steel	m.	1,314.79
403(5)a1	Structural Steel, Furnished, Fabricated and Erected, Grade 36	Kg.	26,582.00
403(7)	Bolts and Nuts and Washers	l.s	1.00
404(1)a	Reinforcing Steel, Grade 40	Kg	25,996.92
404(1)b	Reinforcing Steel, Grade 60	Kg.	5,693.60
405(1)b3	Structural Concrete, 27.68 MPa, Class A, 28 days.	Cu.m	431.01
407(8)	Lean Concrete, Class B (16.5 MPa)	Cu.m	3.97
412(1)c	Elastomeric Bearing Pads	Each	8.00
414(1)	Forms and Falsework	l.s	1.00
PART G	DRAINAGE AND SLOPE PROTECTION STRUCTURES		
506(1)	Stone Masonry	m ³	192.18
PART C	FINISHING AND OTHER CIVIL WORKS		
1032(1)c	Painting Works, Steel	Sq.m	239.36

This Supplemental Bulletin shall form an integral part of the said Bidding Documents.

For the guidance and information of all concerned.


CHRISTOPHER L. EBAL
Assistant District Engineer
BAC Chairperson