



Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
ZAMBOANGA DEL NORTE
1st DISTRICT ENGINEERING OFFICE
Segabe, Piñan, Zamboanga del Norte, Region IX



Name of Procuring Entity:	Request for Quotation	P.R. No.:	25-06-041
Revised on:		Date:	10/27/2025
Standard Form/Title:	Office/End-User:	MAINTENANCE SECTION	
COMPANY NAME :			
ADDRESS :			
TEL NO./FAX NO. :			
TIN :			

Please quote your lowest price on the item(s) listed below, subject to the Terms and Condition stated below and submit your quotation duly signed by your representative not later than 10:00 A.M. of **JUL 02 2025** in the return enveloped attached herewith, to the BAC Secretariat, DPWH Compound, Segabe, Piñan, Zamboanga del Norte.

TERMS AND CONDITIONS:

- All entries must be typewritten or legibly written
- Delivery period within thirty (30) c.d. upon receipt of the approved funded Purchase Order (P.O.). Administrative penalties pursuant to Sec. 69 of the Revised IRR-RA 9184 shall be imposed for non-delivery without valid reason
- Warranty shall be for a minimum of three (3) months for supplies & materials; one year for Equipment; 3 years IT Equipment from date of acceptance by the end-user,
- Price validity shall be for a period of sixty (60) calendar days.
- G-EPS Registration Certificate/Mayor's Permit/DTI shall be attached upon submission of the quotation.
- Bidders shall submit original brochures showing certification of the product.
- Please indicate the brand for each item being offered.
- The approved budget ceiling for this procurement is P **989,931.80**
- Bidders shall submit omnibus sworn statement for SVP w/ ABC above two hundred thousand pesos out not more than one million as per ANNEX "H" Appendix "A" of the Rev. IRK of RA 9184


SANTIAGO D. TOLENTINO, II
Assistant District Engineer
AC BAC, Chairperson

Item No.	ITEMS & DESCRIPTIONS	QTY	UNIT	UNIT PRICE	TOTAL PRICE
1	Solar Illuminated Road Studs (Freight and Handling Cost included)	110	pcs		
2	Concrete Epoxy A & B	2.20	gal		
	Note: Solar Illuminated Road Studs a. Dimension - 143mm dia. X 47mm *Solar Panel - Mono (Single) crystalline 5V, 120mAh * Security- 6pcs Stainless Steel Safety Locks *Battery- Anti Heat Lithium Iron Phosphate (LifePO4) 3.2V, 1500mAh * LED chip- 10mm, 0.2w per chip Super Bright * Weight- 1000 g. Gradient on LED Slides - 30 degrees * Operating Temperature-20°C to 65°C *Compression Test-30 Tons * Body-Aluminum Die Cast Coated with Zinc Metal *Top-Polycarbonate (with IPO Registration), (with BRS/MIRDC Testing Certificate),(Cylindrical top "no corners"/ Cylindrical spaced grooves side walls with "SLX" security post), (Aluminum Alloy Coated with Zinc Metal), (Vertical oriented spaced grooves), (With "Horizontal Cuts"), (With "Annular Channels"), (With Solar Cell and Integrated Circuit Coated with High Quality Clear Polycarbonate with Crisscrossing Reinforcing Ribs				
	The awarding for this RFQ will be on a lump-sum basis.				
	Prospective Suppliers must quote for all of the items.				
	Otherwise they will be subjected for disqualification.				
Purpose:	Supply and Delivery of 110pcs Solar Illuminated Road Studs, 2.2 gal Concrete Epoxy A & B For use in the Repair/Maintenance of National Roads and Bridges. Installation of Internally Illuminated (Solar) Pavement Levelled Marker/Stud Flush Type (Mono-directional or Uni directional) 143mm dia along: Dipolog-Polanco-Piñan Jct. Oroquieta Rd. K1824+255 to K1824+745.50				

Total Amount

Brand Model:

Delivery Period:

Warranty:

Price Validity:

After having carefully read and accepted your General Conditions, I / We quote you on the Item(s) at prices note above.
If the space for Delivery Period, Warranty and Price Validity are left blank, it means that I concur with the Terms and Conditions specified by DPWH.

Telefax: 065-213-6395

dpwh_segabe@yahoo.com

Printed Name / Signature / Date

Tel. No./Cellphone No./E-mail Address