



Republic of the Philippines  
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS  
**OFFICE OF THE SECRETARY**  
Manila



Reference Number: **XII-024**  
Project ID: **P00909109MN**

May 26, 2025

**MEMORANDUM**

**FOR :** **EUGENIO R. PIPO, JR.**  
Undersecretary for Regional Operations  
in CAR, Regions I, II, IX, X, XI, XII, and XIII


This refers to the memorandum dated 14 May 2025 of DPWH Region XII Director **BASIR M. IBRAHIM**, endorsing the request of District Engineer **LEODERICK IAN S. SELVIDO, MPA, Cotabato 1<sup>st</sup> District Engineering Office**, for the **modification** of the project under FY 2025 GAA, to wit;

As per GAA/Original			As Modified		
Project Description					
<b>UACS No. 310108102210000</b> <b>Project ID: P00909109MN</b>  OO1: Ensure Safe and Reliable National Road System – Asset Preservation - Rehabilitation/ Reconstruction of National Roads with Slips, Slope Collapse, and Landslide - Secondary Roads  Banisilan-Gulling-Alamada-Libungan Rd - K1674 + 550 - K1674 + 860			OO1: Ensure Safe and Reliable National Road System – Asset Preservation - Rehabilitation/ Reconstruction of National Roads with Slips, Slope Collapse, and Landslide - Secondary Roads  Banisilan-Gulling-Alamada-Libungan Rd - <b>K1675 + 339.00 - K1675 + 430.00, K1675 + 470.00 - K1675 + 560.00, K1675 + 570.00 - K1675 + 584.00, K1675 + 610.00 - K1675 + 640.00, K1675 + 680.00 - K1675 + 769.00</b>		
Type of Work/ Physical Target	Unit Cost	Allocation	Type of Work/ Physical Target	Unit Cost	Estimated Cost
CW-1- Construction of Road Slope Protection Structure;  1,550.00 Square Meter	₱ 11,760.00/ Square meter	₱ 18,228,000.00	CW-1- Construction of Road Slope Protection Structure;  1,579.15 Square Meter	₱ 11,542.92 / Square meter	₱ 18,228,000.00
EAO	-	₱ 372,000.00	EAO	-	₱ 372,000.00
Total:		₱ 18,600,000.00	Total:		₱ 18,600,000.00
Justification: Decrease in the unit cost/increase in the physical target based on the validated and approved Detailed Unit Price Analysis (DUPA) and Program of Works (POW). <ul style="list-style-type: none"><li>Change in stationing to <u>avoid</u> overlapping with FY <u>2024</u> Slope Protection Project P00800553MN and prioritize road segments that urgently need slope protection structures where slips and scouring have occurred. See attached Straight Line Diagram.</li><li>The project involves different types of slope protection structures including gravity wall (rubble concrete), grouted riprap and reinforced concrete slope each in different sections. The project also includes removal and replacement of damaged 0.28m thk. PCCP, lined canal with paved shoulder and other road facilities such as metal guardrails, warning sign and thermoplastic pavement markings.</li></ul>					

AL-EO-202505-01024

- The derived unit cost is based on the validated and approved Program of Works (POW) and Detailed Unit Price Analysis (DUPA).


Based on our evaluation, the submitted request for modification of the said project is in order; hence, approval hereof is recommended.

  
**LORETA M. MALALUAN, CESO IV**  
Assistant Secretary for Regional Operations  
in CAR, Regions I, II, IX, X, XI, XII, XIII, and NCR

**RECOMMENDING APPROVAL:**

  
**MARIA CATALINA E. CABRAL, Ph.D., CESO I**  
Undersecretary for Planning  
and Public-Private Partnership Services

**APPROVED/DISAPPROVED:**

  
**EUGENIO R. PIPO, JR.**  
Undersecretary for Regional Operations  
in CAR, Regions I, II, IX, X, XI, XII, and XIII

2.3 mksa/AVS/LMM/ERP