

Southern Mindoro DEO Annual Procurement Plan for FY 2024

Code (PAP)	Procurement Project	PMO/ End-User	Is this an Early Procurement Activity? (Yes/no)	Mode of Procurement	Schedule for Each Procurement Activity				Source of Funds	Estimated Budget (Php)			Remarks (Brief description of Project)
					Advertisement/ Posting of IR/REI	Submission/ Opening of Bids	Notice of Award	Contract Signing		Total	MOOE	CO	
310102101632000	Preventive Maintenance – Secondary Roads – Bongaong – Sagana – Roxas - San Aguilino Rd – KO105+456 – KO105+674, Bongaong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	03-Nov-23	23-Nov-23	13-Feb-24	19-Feb-24	GoP	4,117,960.00		4,117,960.00	Road Length = 0.2360 Lane KM, Pavement Width (Carriageway) = 6.10 m, Asphalt Thickness = 80 mm. See Plan and Details.
310102101633000	Preventive Maintenance – Secondary Roads – Bongaong – Sagana – Roxas – San Aguilino Rd – KO110+736 – KO111+005, Bongaong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	23-Jan-24	26-Jan-24	GoP	8,748,460.00		8,748,460.00	Preventive Maintenance – Secondary Roads – Bongaong – Sagana – Roxas – San Aguilino Rd – KO110+736 – KO111+005, Bongaong, Road Length = 0.5400 Lane KM, Pavement Width (Carriageway) = 6.10m, Asphalt Thickness = 80 mm. See Plan and Details.
310102101634000	Preventive Maintenance – Secondary Roads – Bongaong – Sagana – Roxas - San Aguilino Rd – KO111+334 – KO111+736, Bongaong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	27-Oct-23	16-Nov-23	23-Jan-24	26-Jan-24	GoP	29,840,020.00		29,840,020.00	Road Length = 1.808 Lane KM, Pavement Width (Carriageway) = 13.40 m, Asphalt Thickness = 80 mm. See Plan and Details.
310102101635000	Preventive Maintenance – Secondary Roads – Calapan South Road – KO260+230 – KO260+418, KO260+736 – KO260+991, Bongaong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	03-Nov-23	23-Nov-23	23-Jan-24	26-Jan-24	GoP	19,446,140.00		19,446,140.00	Road Length = 1.012 Lane KM, Pavement Width (Carriageway) = 6.70 m, Pavement Width (Thickness) = 6.70 m, Asphalt Thickness = 80 mm. Installation of 16 sets Solar LED Street Light. See Plan and Details.
31011100712000	Construction/Upgrade/Rehabilitation of Drainage Along National Roads – Secondary Road – Calapan South Road – KO260+663.00 – KO260+662.00, Genil, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	22-Jan-24	26-Jan-24	GoP	9,133,661.99		9,133,661.99	Completion of Covered Court. This includes earthworks, civil works, masonry palling, steel palling, roofing works and painting works.
310202101674000	Road Widening – Secondary Road – Bongaong – Sagana – Roxas – San Aguilino Road – KO129+062 – KO129+207, Roxas, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	22-Jan-24	26-Jan-24	GoP	6,292,400.00		6,292,400.00	Road Widening – Secondary Road – Bongaong – Sagana – Roxas – San Aguilino Road – KO129+062.00 – KO129+198.8, @ Left Side, Length = 136.8 L.M., KO129+062 – KO129+207 @ Right Side, Length = 146.0 L.M., Pavement Width = 3.05m, Thickness = 0.28m thick. Construction of Covered Lined Canal at Left Side = 136.8 L.M. Right Side = 146.0 L.M. Installation of 3 pcs – Solar LED Street Light. See Plans and Details.
310202101676000	Road Widening – Secondary Roads – Calapan South Road – KO144 + 011.00 – KO144+387.00, Mansalay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	30-Jan-24	05-Feb-24	GoP	12,896,776.39		12,896,776.39	Road Widening – Secondary Roads – Calapan South Road – KO144+011.00 – KO144+387.00, 0.752 lane km (376.00 lin.), Pavement Width = 3.35m, Pavement thickness = 0.26m thick, Concrete Shoulder Width = Varies max. 2.00. Construction of Metal Guardrails 7.9m. Construction of 9 pcs. Solar LED Street Light. See Plans and Details.
310202101675000	Road Widening – Secondary Roads – Calapan South Road – KO140 + 283.00 – KO140+405.00, Roxas, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	26-Jan-24	31-Jan-24	GoP	5,260,565.63		5,260,565.63	Road Widening – Secondary Roads – Calapan South Road – KO140+283.00 – KO140+405.00, Length=122.00 lin., Pavement Width = 3.35m, Pavement thickness = 0.26m thick, Shoulder Width = 1.50m. Construction of Covered Lined Canal at bothsides, Length = 122.00 lin., Extend 1 lines – RCPC – 0.51m dia. x 3.0m @ right side & 2.0m @ left side. Provide 8 – Type HescoMat @ bothsides. See Plans and Details.
310202101677000	Road Widening – Secondary Roads – Calapan South Road – KO150+681 – KO150+775, KO151+011 – KO151+074, Mansalay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	22-Jan-24	26-Jan-24	GoP	5,631,000.00		5,631,000.00	Road Widening – Secondary Roads – Calapan South Road – KO150+681 – KO150+775, L.S. L= 94.1m, KO150+701 – KO150+775, RS, L= 74.1m., KO151+011 – KO151+704, L.S. L=63.1m, Total Widening Length= 221.1m, (0.221 km.), Pavement Width = 3.35m, 0.26m thick, Concrete Shoulder Width= 1.50m, KO150+775, L.S. L=94.1m, KO150+681 – KO150+775, RS, L=94.1m, KO151+011 – KO151+074 L.S. L= 63.1m, Total Concrete Shoulder Length = 261.1m, Shoulder Width = 2.0m, 0.15m thick. Installation of Metal Guardrails, L.S. L= 96.25m (25 spans) and R.S. L= 87.63m (23 spans), Extension of 2 – 1.20m dia. and 4 – 0.90m dia RCPC. See Plans and Details.

310202101673000	Road Widening - Secondary Road - Calapan South Road - KO167+710 - KO167+675, Maranay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	23-Jan-24	26-Jan-24	Gap	7,114,800.00	7,114,800.00	Road Widening - Secondary Road - Calapan South Road - KO167+710 - KO167+675, Road Length=0.33 lane km, Pavement Width = 6.70m, Pavement thickness = 0.20m Pk, Concrete Shoulder Width @ borders = 2.00m, Pavement thickness = 0.20m, Construction of Slope Protection @ Left Side, L = 5.00 km, Installation of LED Solar Integrated Street light with 8m angle - Arm (Curve) Pole - 15 pcs.
310202101673000	Road Widening - Secondary Road - Calapan South Road - KO171+651.00 - KO172+116.00, Balacaca, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	22-Jan-24	26-Jan-24	Gap	9,947,000.00	9,947,000.00	Road Widening - Secondary Road - Calapan South Road - KO171+651.00 - KO172+116.00 - Road Length = 0.50 Lane KM, Pavement Width = 6.70 - 7.30m, Pavement Thickness = 0.20 m, Concrete Shoulder Width @ Left Side = 2.00m, Pavement Thickness = 0.15m, Construction of Open U-lined Canal @ Right Side, L = 250.00 L.M.
310202101680000	Road Widening - Secondary Road - Calapan South Road - KO180+715 - KO180+607, Balacaca, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	22-Jan-24	26-Jan-24	Gap	3,156,573.13	3,156,573.13	Road Widening - Secondary Road - Calapan South Road - KO180+607, Road Length = 0.20 L.M, Pavement Width = 3.35 m, Thickness = 0.20m thick, Paving of Shoulder Bopside Area = 255.5 sq.m, Installation of 4 pcs - Solar LED Street Light, See Plans & Details.
	Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Bangsod River Control, Sta. 0+300 - Sta. 0+718 (Balle Bridge Abutment B - Upstream), Barangay Balle, Goria, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	13-Feb-24	19-Feb-24	Gap	67,550,000.00	67,550,000.00	Gabion Length = 418.00 m, Installation of 6 layer Gabion 1.00m x 1.00m x 2.00m with closure at the beginning and end of the project, Construction of the Cap, 0.60m x 0.60m and installation of Steel Sheet Piles, Length = 418.17m, See Plans and Details.
	Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Bangsod River Control, Sta. 6+309 - Sta. 7+240 (Upstream - Right Side), Barangay Corrazon, Bansud, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	13-Feb-24	19-Feb-24	Gap	67,550,000.00	67,550,000.00	Construction of Gabion Retainment w/ Steel Piles at existing gabion retainment of Bansud River, Gabion Length = 431.00 L.M, Installation of 5-layer Gabion 1.00m x 1.00m x 2.00m with Closure at the end of the project, Installation of Steel Sheet Piles 6.00m length with 431.20m length of pile cap, Installation of 1 line of RCPC 1+0.90M x 9.00M at specified location, Provide S-Type Headwalls at Both Ends of RCPC, See Plans and Details.
	Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Bangsod River Control, Sta. 2+320 - Sta. 2+798 (Downstream - Right Side), Barangay Araso, Bangsod, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	13-Feb-24	19-Feb-24	Gap	67,550,000.00	67,550,000.00	Construction of Gabion Retainment w/ Steel Piles at existing gabion retainment of Bangsod River, Gabion Length = 478.00 L.M, Installation of 6-layer Gabion 1.00 m x 1.00 m x 2.00 m with Closure at the beginning and end of the project, Construction of Pile cap 0.60 m x 0.60 m and installation of Steel Sheet Piles, Length = 478.17m, Installation of 2 lines of RCPC 1+0.90M x 8.00M, Provide S-Type Headwalls at Both Ends of RCPC, See Plans and Details.
	Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of Pula River Control, Sta. 9+070 - Sta. 9+450 (Upstream - Left Side), Barangay Panibsan Masik, Pnamayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	13-Feb-24	19-Feb-24	Gap	67,550,000.00	67,550,000.00	Construction of Gabion Retainment w/ Steel Piles at existing gabion retainment of Pula River, Gabion Length = 420.00 L.M, Installation of 6-layer Gabion 1.00 m x 1.00 m x 2.00 m with Closure at the end of the project, Installation of Steel Sheet Piles 6.00m length with 420.42m length of pile cap, Installation of 1 line of RCPC 1+0.90M x 8.00M at specified location, Provide S-Type Headwalls at Both Ends of RCPC, See Plans and Details.
320102100940000	Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of River Control Structure along Camaral River, Camarung Section, Balacaca, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	22-Jan-24	26-Jan-24	Gap	29,400,000.00	29,400,000.00	Construction of River Control Structure along Camaral River, Camarung Section, Gabion Length = 180.00 L.M, Construction of 6-layer Gabion 1.00m x 1.00m x 2.00m with closure at the beginning and end of the project, Construction of Pile Cap 0.60m x 0.60m, and installation of Steel Sheet Piles, Length = 180.16m, Construction of stone masonry at the beginning of project near the existing abutment, See plans and details.
320102100945000	Construction/Rehabilitation of Flood Mitigation Facilities within Major River Basins and Principal Rivers, Construction of River Control Structure along Goria River, Maing Section, Goria, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	30-Jan-24	05-Feb-24	Gap	29,400,000.00	29,400,000.00	Construction of Gabion Retainment w/ Steel Piles of Balle River, Gabion Length = 190.00 L.M, Installation of 5-layer Gabion 1.00m x 1.00m x 2.00m with closure at the beginning and end of the project, Installation of Steel Sheet Piles 6.00 m length with 190.16m length of pile cap, See Plans and details.
300201100965000	Construction/Improvement of Access Roads leading to Airports (Kalasid Tunga as Palawan, Palas at Dauogan Program - Kalapanan) - Pnamayan Airport Road, Pnamayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	23-Jan-24	26-Jan-24	Gap	18,753,280.00	18,753,280.00	Road Length 1,308 lane km/ 545.00 linear meters, Pavement Width = 6.70 m, Pavement Thickness = 0.20 m, Shoulder Width @ Both Sides = 1.00 m, Construction of Open U-lined Canal L = 267.40 L.M, Construction of Built-up Headwall at Existing Structure - see plan details.

300203102413000	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (Tourism Road Infrastructure Program – TRIP) San Roque – San Juan – Talambo Road, Brgy. San Juan, Balabac, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	22-Jan-24	26-Jan-24	GOP	9,800,000.00		9,800,000.00	Construction of Road Length = 0.80 Lane Km. Pavement Width = 6.10m. Pavement Thickness = 0.23m. Concrete Shoulder Width @ 0.15m. Retaining wall L = 67.50 L.M. Extension/Division of 1 – 0.60m da. and 6 – 0.90m da. RCPC. Provide 5-Type Headwall.
300203102414000	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (Tourism Road Infrastructure Program – TRIP) Calagui Road leading to Casatagan Beach and Mangla Marine Protected Area (MMPA), Marausay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	23-Jan-24	26-Jan-24	GOP	4,900,000.00		4,900,000.00	Length = 266 L.M. (0.52 Lane Km). Pavement Width = Min. 6.10m. Pavement Thickness = 0.23m. Shoulder Width = 1.00m. Construction of Slope Protection Length = 20.00 m.m.
300203101214000	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (Tourism Road Infrastructure Program – TRIP) Internal Access Road to Sitio Pasmang, Maribala, leading to Maribala Watersite II, Bansud, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	23-Jan-24	26-Jan-24	GOP	14,699,969.11		14,699,969.11	Length = 600 L.M. (1.0 Lane Km). Shoulder Length = 420.00m. Construction of Retaining wall 338.00 L.M. Construction of Open U-lined Canal 58,750 L.M. Installation of Metal Garantis = 363 L.M. Installation of 2 Lines – RCPC – 0.61m da x 10.0m. Provide 5-Type Headwall @ Bofside. See Plan & Details.
300203101695000	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (Tourism Road Infrastructure Program – TRIP) – NJL leading to Punturan Cave and Bamboo Plantation, Gloria, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	22-Jan-24	26-Jan-24	GOP	14,700,000.00		14,700,000.00	Road Area = 4,727.50 sq.m. Pavement Width = 6.10m. Pavement Thickness = 0.23m. Concrete Shoulder Width @ 0.15m. Pavement Thickness = 0.15m. Construction of Slope Protection L = 61.60 L.M. Installation of Slope Barre 910m da. RCPC and Double Barre of 910 and 1200m da. RCPC. See Plan and Details.
300203101213000	Construction/Improvement of Access Roads leading to Declared Tourism Destinations (Tourism Road Infrastructure Program – TRIP) – Brgy. Malalay to Brgy. Bung Lupu to Wiliang Langit Falls, Gloria, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	22-Jan-24	26-Jan-24	GOP	14,700,000.00		14,700,000.00	Construction/Improvement of Access Roads – Brgy. Malalay to Brgy. Bung Lupu to Wiliang Langit Falls (RCPC) = 4.0 LANE FOR (2.00 L.M.). Carriageway Width = 6.10m. Pavement Thickness = 0.20m. Construction of Slope Protection @ Right Side Length = 188.0 L.M. Construction of Slope Protection @ Left Side Length = 294.8 L.M. Installation of Open U-lined Canal @ Left Side Length = 294.8 L.M. Installation of RCPC – 1.220m da x 10.0m – 1 Line. RCPC – 2 – 1.220m da x 10.0m – Provide S-Type Headwall @ Bofside. See Plan & Details.
300214101141000	Installation of Signage – Warning, Advisory and Regulatory Signs and Pavement Markings – Pedestrian and Pedestrian/Tenuring along Calapan South Rd – K0087+000 – K0089+000, Palanayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	03-Nov-23	23-Nov-23	22-Jan-24	26-Jan-24	GOP	1,029,000.00		1,029,000.00	Installation of Warning Signs – 4 pcs and Application of Pedestrian Lane Pavement Markings. Installation of LED Solar Integrated Steel Light with 8 meter Single – Arm (Curve) Pole – 6 pcs.
300214101146000	Installation of Signage, Warning, Advisory and Regulatory Signs, Pavement Markings, Centerlines, Edge lines (including Profile Edge Lines) and Inverted Parking, Ban Parking, Inverted Bus/Jeepney Stop, Reckless Bus/Jeepney Stop along Calapan South Road K0068 + 000-K0069 + 600, Brgy. Marinhadico, Palanayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	22-Jan-24	26-Jan-24	GOP	465,100.00		465,100.00	Application of Pavement Markings and Pedestrian Lane Pavement Markings – 329.50 sq.m. Installation of Regulatory Signs = 4 pcs.
300214101146000	Installation of Signage, Warning, Advisory and Regulatory Signs, Pavement Markings, Centerlines, Edge lines (including Profile Edge Lines) and Inverted Parking, Ban Parking, Inverted Bus/Jeepney Stop, Reckless Bus/Jeepney Stop along Calapan South Rd – K0075+000-K0076+000, Brgy. Balabacan, Gloria, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	22-Jan-24	26-Jan-24	GOP	1,597,400.00		1,597,400.00	Installation of Warning Signs – 2 pcs and Regulatory Signs – 4 pcs. Application of Pavement Markings – 209.00 sq.m. Solar LED Street Light – 6 sets @ 20m interval.
300214101144000	Installation/Improvement of Signage – Warning, Advisory and Regulatory Signs and Pavement Markings – Centerlines, Edge lines (including Profile Edge Lines) and Inverted Parking, Ban Parking, Inverted Bus/Jeepney Stop, Reckless Bus/Jeepney Stop along Calapan South Rd – K0201+000 – K0201+500, Balabac, Oriental Mindoro	Construction Section	YES	Competitive Bidding	27-Oct-23	16-Nov-23	22-Jan-24	26-Jan-24	GOP	2,273,600.00		2,273,600.00	Installation of Warning Signs – 5 pcs. Installation of Hazard Markers – 28 pcs. Application of Pedestrian Lane Pavement Markings – 10 meter Single – Arm (Curve) Pole – 7 pcs.
300214101142000	Installation/Improvement of Signage, Pavement Markings along Calapan South Rd – K0072+000 – K0074+000, Palanayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	03-Nov-23	23-Nov-23	22-Jan-24	26-Jan-24	GOP	1,283,800.00		1,283,800.00	Installation of Warning Signs – 5 pcs and Regulatory Signs – 27 pcs. Application of Pedestrian Lane Pavement Markings – 10 each. Construction of Concrete Shoulder – Length = 88.00 m.m. Width = 3.30m wide. Thickness = 0.15m. See Plan & Details.
300216104704000	Sustainable Infrastructure Project Alleviating Gaps (SIPAG) – Construction of Marausay – Sabang Road, Palanayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	30-Jan-24	05-Feb-24	GOP	49,000,000.00		49,000,000.00	Construction of Marausay – Sabang Road – Length (RCPC) = 4.0 Lane km (2,000.00 L.M.). Carriageway Width = 6.10 m. Pavement Thickness = 0.23 m. Construction of 2 – Single Barrel Box Culvert = 3.0 m x 3.0 m x 8.0 m. Station 1 + 409.0 and Station 1 + 501.10 (respectively). Construction of Retaining Wall @ Left Side Length = 873.0 L.M. @ Right Side Length = 904.50 L.M. Construction of Open U-lined Canal @ Both Side Length = 220.81 L.M. Installation of 3 Lines – RCPC – 0.61 m da x 9.0 m. Provide S-Type Headwall @ bofside. See Plans and Details.

300215104705000	Sustainable Infrastructure Projects Alleviating Gaps (SIPAG) - Construction of Pili - Bantad Road, Pinarayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	23-Jan-24	26-Jan-24	Gap	29,400,000.00		29,400,000.00	Construction of Pili - Bantad Road, Pinarayan, Road Length = 2.400 Lane KM, Pavement Width = 5.00 m, Pavement Thickness = 0.23m, Concrete Shoulder Width @ Both Sides = 1.00 m, Pavement Thickness = 0.15 m, Construction of Slope Protection, L = 94.50 L.M. Construction of Retaining Wall, total length, L=600.75 L.M. Installation of 5 line RCPC, 1.20m dia x 8.0m RCPC, 1 line RCPC 1.20m dia, X 14m RCPC, 2 line RCPC 0.50m dia, X 12.0m RCPC, 1 line RCPC 0.50m dia, X 8.0m RCPC, and 5 line RCPC 0.60m dia, X 8.0m RCPC, Construction of Concrete Guardrails, total length, L = 500.75 L.M. See Plans and Details.
300215104707000	Sustainable Infrastructure Project Alleviating Gaps (SIPAG) - Construction of Sta Isabel - Guinawa Road, Pinarayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	30-Jan-24	05-Feb-24	Gap	49,000,000.00		49,000,000.00	Construction of Sta. Isabel - Guinawa Road, Pinarayan - Road Length = 4.0 Lane km, Pavement Width = 5.0 m, Pavement Thickness = 0.23 m, Concrete Shoulder Width @ both sides = 1.00m, Pavement Thickness = 0.15m, Construction of Slope Protection, L = 270.00 L.M. Construction of Retaining Wall, total length, L = 25.00 L.M. Installation of 5 line RCPC 0.50 m dia x 9.0m RCPC, Construction of Open Ureth Drainage, total length, L = 1,156.50 L.M. Drainage invert roller width = 0.50 m / 1.10 m, Drainage Invert roller Ridge = 1.00 / 1.15 m. See Plans and Details.
300221106041000	Construction of Road Leading to PUP RTC & AFP, Barangay Pag-asa, Bantad, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	23-Jan-24	26-Jan-24	Gap	9,900,000.00		9,900,000.00	Construction of Road Leading to PUP RTC & AFP, Barangay Pag-asa, Length = 600.00 L.M (1.0 Lane km) Pavement Width = Min. 5.0 m, Pavement Thickness = 0.23 m, Concrete Shoulder Width = varies, Construction of Retaining Wall, Length = 247.59 L.M. Solar LED Street Light = 3 sets @ 25 m interval. See Plans and Details.
300221106049000	Construction of Road Barangay Arano - Masaguis, Bongbong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	22-Jan-24	26-Jan-24	Gap	4,950,000.00		4,950,000.00	Construction of Road Barangay Arano - Masaguis, Road Length = 0.4460 Lane KM, Pavement Width = 5.00m, Pavement Thickness = 0.23m, Shoulder Width @ Both Sides = 1.00m, Construction of Retaining Wall @ Both Sides 178.6 L.M. See Plans and Details.
300221106050000	Construction of Road, Barangay B. Del Mundo, Marasay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	22-Jan-24	26-Jan-24	Gap	4,950,000.00		4,950,000.00	Construction of Road Total Length = 327.50 L.M (0.6650 Lane km) Pavement Width = Min. 2.50 m, Pavement Thickness = 0.23 m, Shoulder Width = varies, Construction of Retaining Wall, Length = 147.50 L.M. See Plans and Details.
300221106054000	Construction of Road, Sitio Bihisan, Barangay Bantad, Pinarayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	22-Jan-24	26-Jan-24	Gap	19,800,000.00		19,800,000.00	Construction of Road, Pavement Length = 1,600 lane km, Pavement Width = 2.50 m wider lane km, Pavement Thickness = 0.23 m, Shoulder Width @ both sides = 1.00 m, Construction of Slope protection, L = 415.00 L.M and construction of open lined canal @ L/S L = 160.00 L.M. See Plans and Details.
30022102064000	Construction of Drainage Canal, Barangay Maugap, Bulasao, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	22-Jan-24	26-Jan-24	Gap	4,950,000.00		4,950,000.00	Construction of Drainage Canal, Length = 480.00 L.M, Concrete Shoulder Length (for B/S) = 136.0 m (166.40 m, Concrete Shoulder Width = 1.00m / 1.50m, Concrete Shoulder Thickness = 0.15 m, Construction of PCPC 0.23 mm PK at Road Gap and Redding for RCPC installation, Length = 0.0522 lane km, Width = 2.50 m lane km, Installation of 1-910 RCPC x 8.00 pcs, provide S-Type Headwall
300226113413000	Construction (Completion) of Legislative Building at Barangay Zone III, Pinarayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	22-Jan-24	26-Jan-24	Gap	19,800,000.00		19,800,000.00	Construction of 4 storey legislative building. This includes clearing of site, earthworks, reinforced structural concrete, masonry works, door joints, doors, plastering, roofing works and roughing-in for cold water lines, sewerages, mechanical works and electrical works.
300226113431000	Construction (Completion) of Legislative Building at Barangay Bagumbayan, Roxas, Oriental Mindoro	Construction Section	YES	Competitive Bidding	20-Oct-23	14-Nov-23	22-Jan-24	26-Jan-24	Gap	14,850,000.00		14,850,000.00	This includes earthworks, civil works, masonry piling, wood piling, mechanical works, and painting works.
300226113432000	Construction (Completion) of Multi-Purpose Building, Barangay Pousak, Bongbong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	22-Jan-24	26-Jan-24	Gap	1,980,000.00		1,980,000.00	Construction (Completion) Multi-Purpose Building. This includes concrete structure, construction of intermediate columns at both sides (front and rear), installation of end wall cover at both ends (front and rear) and painting of covered court (columns, beams, and concrete grates).

30022611343000	Construction (Completion) of Multi-Purpose Building, Barangay Bagong Silat, Bualacao, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	22-Jan-24	26-Jan-24	GoP	1,980,000.00		1,980,000.00	Completion of 1 unit Multi-Purpose Building (Covered Court) 18.00m x 30.00 m. This includes concreting of 4 sets column footing & column, beam and slab. This also includes fabrication and installation of 2 side flashings, 2 sets of basketbar boarding and electrical works.
300226113434000	Construction (Completion) of Multi-Purpose Building, Barangay Bukal, Bongabong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	26-Jan-24	31-Jan-24	GoP	1,980,000.00		1,980,000.00	Completion of 1 unit Multi-Purpose Building (Covered Court) 18.00m x 30.00 m. This includes concreting of 4 sets column footing & column, beam and slab. This also includes fabrication and installation of 2 side flashings, 2 sets of basketbar boarding and electrical works.
300226113435000	Construction (Completion) of Multi-Purpose Building, Barangay Camunang, Bualacao, Oriental Mindoro	Construction Section	YES	Competitive Bidding	29-Sep-23	19-Oct-23	22-Jan-24	26-Jan-24	GoP	1,980,000.00		1,980,000.00	Completion of Covered Court. This includes earthworks, civil works, masonry piling, steel piling, roofing works and painting works.
300226113436000	Construction (Completion) of Multi-Purpose Building, Barangay Daynagan, Bongabong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	23-Jan-24	26-Jan-24	GoP	1,980,000.00		1,980,000.00	Construction (Completion) Multi-Purpose Building (Construction of Stage and painting of existing concrete floor area). This includes earthworks, reinforced concrete slab, finished floor, 10mm thick concrete floor, wall, partition, sewer line works, storm drainage and downspout, electrical, plumbing fixtures, cold water line, ceiling, finishing hardware, aluminum glass windows (awning type), frames, doors (wood panel), vent wall flaring, pre-painted metal sheets, glazed and uplized tiles, cement plaster finish, masonry, wood, and steel painting, reflective insulation, PVC doors, masonry works, metal structures, and electrical works.
300226113437000	Construction (Completion) of Multi-Purpose Building, Barangay Maasin, Bualacao, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	23-Jan-24	26-Jan-24	GoP	1,980,000.00		1,980,000.00	Completion of 1-unit Multi-Purpose Building (Covered Court) 15.00m x 27.00 m. This includes concreting of 4 sets of column footing and column, beam and slab. This is also includes fabrication and installation of 2 side flashings.
300226113438000	Construction (Completion) of Multi-Purpose Building, Barangay Pangajayan, Pinarayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	22-Jan-24	26-Jan-24	GoP	2,970,000.00		2,970,000.00	1.) Complete Construction of 2-Storey Building at Barangay Pangajayan, Pinarayan, Oriental Mindoro (stairs 1m width, awning windows at front, left and right side of the building and fireweed at rear side of the building, balcony and PWD ramp at the front. See details and plans.
300226113439000	Construction (Completion) of Multi-Purpose Building, Barangay Potacion, Marasay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	30-Jan-24	05-Feb-24	GoP	4,950,000.00		4,950,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court) 18.00m x 30.00m. This includes concreting of column footing, column, footing for beam, slab, beam and girder. Fabrication and installation of truss and roofing works. Installation of downspout and additional entrenchment.
300226113440000	Construction of Multi-Purpose Building at PNP, Barangay Cacaman, Pinarayan, Oriental Mindoro	Construction Section	YES	Competitive Bidding	18-Oct-23	07-Nov-23	30-Jan-24	05-Feb-24	GoP	4,950,000.00		4,950,000.00	Construction of Two-Storey Multi-Purpose Building at PNP Compound (8m x 10.7m building floor area). This includes earthworks, concrete works, finishing, masonry works, installation of doors and windows, ceiling works, plastering and painting of masonry, wood and steel, roofing works, plumbing and electrical works.
300226113441000	Construction (Completion) of Multi-Purpose Building, Barangay Orcuna, Bongabong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	27-Oct-23	16-Nov-23	22-Jan-24	26-Jan-24	GoP	1,980,000.00		1,980,000.00	Completion of Two Storey Multi-Purpose Building. This includes additional concrete works, plastering, masonry, wood and steel painting, installation and painting of doors, ceiling works, installation of sewer and cold water line, plumbing fixtures, septic tank and electrical works.
300226113442000	Construction of Potacion Multi - Purpose Building, Barangay Tawas, Bongabong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	22-Sep-23	12-Oct-23	22-Jan-24	26-Jan-24	GoP	4,950,000.00		4,950,000.00	Construction of 1-unit Multi-Purpose Building (Covered Court) 18.00m x 30.00m. This includes concreting of column footing, column, footing for beam, slab, beam and girder. Fabrication and installation of truss and roofing works. Installation of downspout and additional entrenchment (0.30m from FGL).
300226113443000	Construction of Multi-Purpose Building, Gatz Elementary School, Barangay San Roque, Bualacao, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	26-Jan-24	31-Jan-24	GoP	4,950,000.00		4,950,000.00	Construction of 1 unit Multi-Purpose Building (8.50m x 27.00m) complete

300226113444000	Construction (Completion) of Multi-Purpose Building, Magdalena Unal Suyen Memorial Elementary School, Barangay Ipi, Bongaong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Oct-23	26-Oct-23	22-Jan-24	26-Jan-24	GP	2,970,000.00		2,970,000.00	Construction of 1 Unit Multi-Purpose Building (8.50m x 18.00m) Enclosing Installation and partial masonry paint.
31011100713000	Construction/Upgrade/Rehabilitation of Drainage Along National Route - Secondary Roads - Calapan South Road - (K0089-377 - K0089-415) Bansud, Oriental Mindoro	Construction Section	YES	Competitive Bidding	27-Oct-23	16-Nov-23	13-Feb-24	19-Feb-24	GP	17,640,000.00		17,640,000.00	Construction / Upgrade/ Rehabilitation of Drainage Along National Roads - Secondary Roads - Calapan South Road - (K0089-377 - K0089-415) Bansud, Oriental Mindoro. Construction of Covered Lined Drainage. Length = 160.00 L.M. Construction of Slope Protection. Length = 190.00 L.M. Construction of Concrete Shoulder @ Both Sides. Length 933.00 L.M. Width = 2.00 m. Pavement Thickness = 0.15 m. See Plan and Details.
310202101681000	Road Widening - Secondary Roads Calapan South Road K0138+131 - K0138+473, Roxas, Oriental Mindoro	Construction Section	YES	Competitive Bidding	27-Oct-23	16-Nov-23	22-Jan-24	26-Jan-24	GP	14,121,738.63		14,121,738.63	Road Widening - Secondary Roads Calapan South Road K0138+131 - K0138+473, Length = 0.64 Lane KM (342.00 L.M.). Concrete Shoulder, 654.00m length, 1.5m - 2.0m width. Construction of Retaining Wall 183.00 L.M. Construction of Covered Lined Canal 510.00 L.M. @ Both Side
300214101143000	Installation/Application/Construction of Signage-Warning, Advisory and Regulatory Signs and Pavement Markings-Centerlines, Edge-lines, Pedestrian and Pedestrian Fencing along Calapan South Rd - K0089-000-K0095+000, Bansud, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	22-Jan-24	26-Jan-24	GP	4,664,800.00		4,664,800.00	Application of Pavement Markings = 3,669.67 sq.m. Number of Signs = 22 pieces
300214101147000	Intervention/Countermeasures of Blackspot Identified Locations along Calapan South Road, Bongaong, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	26-Jan-24	31-Jan-24	GP	2,117,780.00		2,117,780.00	Installation of Warning Signs-5 pcs and Regulatory Signs-5 pcs. Guide of Information Signs- 2 pcs. Application of Pavement Markings- 654 sq. m Solar LED Steel Light = 6 Sats @ 25m interval
300214101145000	Installation/Application/Construction of Signage-Warning, Advisory and Regulatory Signs and Pavement Markings-Centerlines, Edge-lines, Pedestrian and Pedestrian Fencing Along Bongaong-Sigara-Roxas-San Aquino Rd - K0125+700-K0126+200, Roxas, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	22-Jan-24	26-Jan-24	GP	607,600.00		607,600.00	Application of Pavement Markings - 217.27 sq.m. Number of Pedestrian Railings = 19 pieces
310202101682000	Road Widening - Secondary Roads - Calapan South Road K0176+215 - K0176+535, Balaena, Oriental Mindoro	Construction Section	YES	Competitive Bidding	14-Nov-23	05-Dec-23	30-Jan-24	05-Feb-24	GP	17,768,380.00		17,768,380.00	Road Length = 0.64 Lane KM, Pavement Width = 3.35 m/ Lane km, Pavement Thickness = 0.28 m, Concrete Shoulder Width @ Both Sides varies, Pavement Thickness=0.23 m, Construction of open lined canal = 653.00 Lm. Installation of LED Solar Integrated Streetlight with 8 meter Single - Arm (Curve) Pole - 16 pcs
310305102181000	Widening of Permanent Bridges, Buduran Br. (B00233MR) Along Calapan South Road, Mansalay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	06-Dec-23	27-Dec-23	22-Jan-24	26-Jan-24	GP	49,000,000.00		49,000,000.00	Widening of 385.88 sq.m. PSCG Br., from 2 Lanes to 4 Lanes, 1 span, 15.63 L.M. Br. Const. of 6.0 L.M. Approach Slab @ Approach "A" & "B". Widening/Carriageway = 0.875 lane km, 3.35m wide, 0.28m thick. Shoulder = 0.576 lane km, varies width of 0.80 & 2.00m, 0.23m thick. Construction of 191.60 Lm Retaining Wall with 32 sets Concrete Guardrails. Construction of 146.20 Lm bank protection works.
310305102182000	Widening of Permanent Bridges, Barabod Br. (B00070MR) along Calapan South Rd, Mansalay, Oriental Mindoro	Construction Section	YES	Competitive Bidding	24-Nov-23	14-Dec-23	23-Jan-24	26-Jan-24	GP	22,540,000.00		22,540,000.00	Widening of 200.38 sq.m. RCDD Br., from 2 Lanes to 4 Lanes, 1 span, 15.63 L.M. Br. Const. of 6.0 L.M. Approach Slab @ Approach "A" & "B". Widening of Carriageway = 0.10074 Lane Km, 3.65m Wide, 0.28m thick. Const. of Bike Lane = 0.10074 Lane Km, 2.00 m Wide, 0.23 m thick. Construction of Retaining wall = 124.74 L.M. (for Road and 12.00 L.M. (for River). Concrete Guardrails in Approach = 28 sets.

Submitted by:


ALELI GILY U. MANALAYSAY
 OIC, Procurement Unit

Recommended by:


ALFREDO ENRIQUETA JR.
 PAC Chairman
 Chief, Construction Section

Approved by:


ANNE LYN E. PABOLTA
 District Engineer