

DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS

Contract ID : 22KA0015
 Contract Name : Retrofitting/Strengthening of Permanent Bridges:
 Nasinabong Bridge (B01643MN) along Kapalong-Talaingod-Valencia Road
 Contract Location : San Fernando, Bukidnon, 2nd LD

Bukidnon 1st District Engineering Office Malaybalay City

SUPPLEMENTAL BULLETIN NO. 1 October 25, 2021

Subject: Revision of Quantities

This Supplemental Bulletin No. 1 is issued to amend provision in the bidding documents (BDs) for the above stated contract as follows:

As Advertised "				'As Revised 1''			
Pay Item No.	Description	Quantity	Unit	Pay Item No.	Description	Quantity	Unit
PART I	OTHER GENERAL REQUIREMENTS			PART I	OTHER GENERAL REQUIREMENTS		
B.5	Project Billboards/Signboards (1 DPWH, 1 COA billboard)	1.00	each	B.5	Project Billboards/Signboards (1 DPWH, 1 COA billboard)	1.00	each
B.7(2)	Occupational Safety and Health Program	1.00	ls	B.7(2)	Occupational Safety and Health Program	1.00	ls
B.8(2)	Traffic Management (Layout 7, Case 1)	1.00	ls	B.8(2)	Traffic Management (Layout 7, Case 1)	1.00	ls
B.9	Mobilization/ Demobilization	1.00	ls	B.9	Mobilization/ Demobilization	1.00	ls
PART II	CIVIL WORKS			PART II	CIVIL WORKS		
PART A	EARTHWORKS			PART A	EARTHWORKS		
102(2)	Surplus Common Excavation	283.68	cu.m.	102(2)	Surplus Common Excavation	252.99	cu.m.
PART B	SURFACE COURSES			PART B	SURFACE COURSES		
302(2)	Emulsified Asphalt (Tack Coat)	238.00	sq.m	302(2)	Emulsified Asphalt (Tack Coat)	238.00	sq.m
310(1)c	Bituminous Concrete Wearing Surface Course, Hot Laid (50 mm) thick	238.00	sq.m	310(1)c	Bituminous Concrete Wearing Surface Course, Hot Laid (50 mm) thick	238.00	sq.m
PART C	BRIDGE RETROFITTING			PART C	BRIDGE RETROFITTING		
411(2)	Bridge Painting (Concrete)	181.00	sq.m	411(2)	Bridge Painting (Concrete)	180.11	sq.m
414(1)	Forms and Falseworks	1.00	ls	414(1)	Forms and Falseworks	1.00	ls
416(1)c	Carbon Fiber Sheet	174.13	sq.m	416(1)c	Carbon Fiber Sheet	174.13	sq.m
416(1)e	Carbon Fiber Plate	30.00	sq.m	416(1)e	Carbon Fiber Plate	30.00	sq.m
517(1)a	Drain Pipe, Galvanized	14.00	l.m	517(1)a	Drain Pipe, Galvanized	14.00	l.m
628(3)	Epoxy Injection on Crack	18.00	lm	628(3)	Epoxy Injection on Crack	18.00	lm
PART D	BANK AND SLOPE PROTECTION REPAIR			PART D	BANK AND SLOPE PROTECTION REPAIR		
506(1)	Stone Masonry	12.00	cu.m.	506(1)	Stone Masonry	12.75	cu.m.
511(1)a3	Gabions (1m x 1m x 2m)	450.00	cu.m	511(1)a3	Gabions (1m x 1m x 2m)	405.00	cu.m
508(1)	Hand-Laid Rock Embankment	67.50	cu.m.	508(1)	Hand-Laid Rock Embankment	60.75	cu.m.
PART E	MISCELLANEOUS			PART E	MISCELLANEOUS		
612(1)	Reflectorized Thermoplastic Pavement Markings (White)	7.00	sq.m	612(1)	Reflectorized Thermoplastic Pavement Markings (White)	7.00	sq.m
612(2)	Reflectorized Thermoplastic Pavement Markings (Yellow)	10.50	sq.m	612(2)	Reflectorized Thermoplastic Pavement Markings (Yellow)	10.50	sq.m

DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS

This Bid Bulletin shall form an integral part of the said Bidding Documents.

For the guidance and information of all concerned

OCTAVIUS CESAR E. AZURA

BAC Chairman

Received by the Bidder:

Name and Signature of Bidder's Representative

Position

Date received _____