

Department of Public Works and Highways

Contract ID : 22KB0189
Contract Name : Repair/Maintenance of DILG Building-Maramag Police Station Building
Location of the Contract : Brgy. Anahawon, Maramag, Bukidnon

Republic of the Philippines
Department of Public Works and Highways
**BUKIDNON SECOND
DISTRICT ENGINEERING OFFICE**
Regional Office X
Pinamaloy, Don Carlos, Bukidnon
SUPPLEMENTAL BULLETIN NO. 1
August 12, 2022



Subject : Revised Scope of Work, Bill of Quantities, Specification/s and Equipment Requirement for Contract ID No22KB0189
: Schedule of Bid Opening

This Supplemental Bulletin No. 1 issued due to revision/change of Scope of Work, Bill of Quantities, Specification/s and Equipment Requirement for the above stated Contract, as follows:

I – Scope of Work:

Current Provision of BDs (including Previous Amendments)	Amended Provision of BDs under this Supplemental Bid Bulletin
<p><u>Previous Scope of Work</u></p> <p>Removal and replacement of all toilet plumbing fixtures, floor drains, p-traps, floor and wall tiles, installation of glass door and windows at roof deck and repainting of entire building.</p>	<p><u>New Scope of Work</u></p> <p>Removal and replacement of all toilet plumbing fixtures, floor drains, p-traps, floor and wall tiles, installation of glass door and windows at roof deck and repainting of entire building; Repair of damaged ceiling and installation of glass door and windows at roof deck; Installation of new septic vault; and Repainting of interior and exterior walls, steel components on windows, grills, railings, flag pole and ceiling at roof deck only.</p>

II – Bill of Quantities:

BILL OF QUANTITIES					
Part No. _____		Part Description : _____			
Item No	Description	Quantity	Unit	Unit Price (Pesos)	Amount (Pesos)
B.5	Project Billboard / Signboard	2.00	each	In words: Pesos and In figures: Php	In figures: Php
B.7(2)	Occupational Safety and Health Program	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
B.9	Mobilization / Demobilization	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
801(1)	Removal of Structures and Obstruction	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
803(1)a	Structure Excavation (Common Soil)	25.25	Cu.m	In words: Pesos and In figures: Php	In figures: Php
903(1)	Formworks and Falseworks	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
1001(8)	Sewer Line Works	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
1001(11)	Septic Vault (Concrete/CHB)	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
1002(4)	Plumbing Fixtures	1.00	Ls	In words: Pesos and In figures: Php	In figures: Php
1003(1)c1	Ceiling, 6mm (Metal Frame, Marine Plywood)	32.00	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1007(1)b	Aluminum Framed Glass Door (Swing Type)	2.10	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1008(1)a	Aluminum Glass Windows (Sliding Type)	28.00	Sq.m	In words: Pesos and In figures: Php	In figures: Php

1008(1)d	Aluminum Glass Windows (Fixed Type)	45.09	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1018(1)	Glazed Tiles and Trims	75.60	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1018(2)	Unglazed Tiles	20.11	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1032(1)a	Painting Works (Masonry/Concrete)	1,407.22	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1032(1)b	Painting Works (Wood)	204.48	Sq.m	In words: Pesos and In figures: Php	In figures: Php
1032(1)c	Painting Works (Steel)	467.41	Sq.m	In words: Pesos and In figures: Php	In figures: Php
X-X-X-X-X					
Amount in Figure and in words					

III – Specification/s: (Section VI of the Bidding Requirements)

Part II

B.5 Project Billboard/Signboard

Quantity	Unit	Description
64	sq.ft	8' x 8' Tarpaulin
48	bd.ft	Good Lumber (Frames)
1	kg	Assorted Common Working Nails
1.5	sheet	1/2" Marine Plywood

B.7(2) Occupational Safety and Health Program

1 – Safety Practitioner/Officer (Part Time)

Quantity	Unit	Description
		- Personal Protective Equipment
980	man-days	8' x 8' Tarpaulin
980	man-days	Good Lumber (Frames)
980	man-days	Assorted Common Working Nails
980	man-days	1/2" Marine Plywood
1	set	PPE Signage (4' x 8')
1	set	Safety First (4' x 4')
1	set	Warning Signs (2' x 3')
1	roll	Caution Tape, 1000 ft

		- Antiseptics and Disinfectants
	L	Sanitation Solution
	L	Ethyl Alcohol
	can	Disinfectant Spray
	L	Liquid Hand Soap

Part III

Formworks and Falseworks

Item	Specification
903(1)	H-Frame 1.7 m x 1.2m, set 2 pcs H-frames 4 pcs diagonal cross braces 4 pcs horizontal braces 8 pcs joint pins Shoring Jack, 3.8 m full extension Adjustable U-head Jack, 0.6m Adjustable Base Jack, 0.6m 1-1/2" GI Pipe x 6.0 m 1-1/2" GI Pipe x 3.0 m 1-1/2" GI Pipe x 4.0 m 1-1/2" GI Pipe x 1.0 m Tie Rod x 0.60m Round Wing Nut Ordinary Plywood (4 sheets) Good Lumber (87 bd.ft) Assorted Common Wire Nails (3 kg)

Storm Drainage and Sewerage System

Item	Description	Specification
1001(8)	Sewer Line Works	100mm PVC Pipe S-1000 (5 lengths) 100mm PVC Tee (3 pcs) 100mm PVC Clean Out (3 pcs) 75mm PVC P-trap (5 pcs) Solvent Cement (400 cc) (1 can)
1001(11)	Septic Vault (Concrete/CHB)	150mm thk CHB (Non - Load Bearing) Cement (Portland) Sand Gravel Reinforcing Steel 12mmØ GI tie Wire #16 Cement-based Waterproofing

Plumbing Works

Item	Description	Specification
1002(4)	Plumbing Fixtures	Water Closet w/ complete fitting & acc. (8 sets) Lavatory w/ complete fittings & acc. (4 sets) Urinal w/ complete fittings & acc. (2 sets) Sink w/ complete fittings & acc. (4 sets) 150x150mm Floor Drain (8 sets) Showerhead (1 set)

Carpentry and Joinery Works

Item	Description	Specification
1003(1)c1	Ceiling, 6mm (Metal Frame, Marine Plywood)	6mm thk, Marine Plywood

Aluminum Framed Glass Door

Item	Description
1007(1)b	Aluminum Framed Glass Door (Sliding Type)

Aluminum Framed Glass Windows

Item	Description
1008(1)a	Aluminum Glass Windows (Sliding Type)
1008(1)d	Aluminum Glass Windows (Fixed Type)

Ceramic/Granite Tiles

Item	Description	Specification
1018(1)	Glazed Tiles and Trims	300x600mm Ceramic Wall Tiles
1018(2)	Unglazed Tiles	300x300mm Ceramic Floor Tiles (Non-Skid)

Painting, Varnishing and Other Related Works

Item	Description	Specification
1032(1)a	Painting Works (Masonry/Concrete)	Concrete Neutralizer Concrete Sealer/Primer Patching Compound Semi Gloss Latex (two coat only)
1032(1)b	Painting Works (Wood)	Glazing Putty Flat wall Enamel Enamel Quick Dry Paint Thinner Tinting Color (Optional)
1032(1)c	Painting Works (Steel)	Red Oxide Primer Enamel Paint Paint Thinner Tinting Color (Optional)

IV – Equipment Requirement:

1	Backhoe, SE 130 LC-2 (0.80 cu.m/1.04 cu.yd)	1	Bar Cutter (Single Phase)
1	Dump Truck, All Models (12 cu.yd)	1	Bar Bender
1	One Bagger Mixer (4-6 cu.ft/min)		

V – Schedule:

5.1 Deadline of Buying Bid Documents – 8:30AM, August 22, 2022
(Issuance of Order of Payment)

5.2 Deadline of Submission of Bids – 9:30am, August 22, 2022
(Receipt of Bids)

5.3 Opening of Bids – 10:00AM, August 22, 2022

Meeting ID: **826 9126 6569**

Passcode: **BAC081922**



NORMA A. OGABANG
BAC Chairperson

R10.10 BAC/jvj/JFP/MDVjr