Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
Bulacan First District Engineering Office
Tikay, City of Malolos, Bulacan

Name of Procuring Entity : Bulacan Ist DEO	Purchase Request No.24-07-260
Revised on :	Date : 07/29/2024
Standard Form/Title : **REQUEST FOR QUOTATION**	Office/End-User: Maintenance
COMPANY NAME :	
ADDRESS :	
TEL. NO./FAX NO. :	TIN :

Please quote your lowest price on the item(s) listed below, subject to the Terms and Conditions stated below and submit your sealed/open quotation duly signed by your representative not later than 10:00 A.M. of August 14, 2024 in the return envelope attached herewith.

TERMS AND CONDITIONS :

1. All entries must be typewritten or legibly written.
2. Delivery period within 10 days upon receipt of the approved funded Purchase Order (P.O.) Administrative penalties pursuant to Sec. 69 of the Revised IRR-RA 9184 shall be imposed for non-delivery without valid reason
3. Warranty shall be for a minimum of three (3) months for supplies & materials, one year for Equipment from date of acceptance by the end-user.
4. Price validity shall be for a period of one hundred twenty (120) calendar days.
5. G-EPS Registration Certificate shall be attached upon submission of the quotation.
6. Bidders shall submit original brochures showing certifications of the product, if applicable.
7. Please indicate the brand for each items being offered.
8. The approved budget ceiling for this procurement Is 915,040.00

EVELYN T. DE JESUS
VICE CHAIRPERSON

Item No.	ITEMS & DESCRIPTION	QTY.	UNIT	UNIT PRICE	TOTAL PRICE
	1. Solar Powered Led Roadway Lighting (200watts)	8.00	each		
	Solar Photovaltaic Panel:18V/200 Watts (should be greater than 90% after 10 years and less than 80% after 25 years); Lifetime > 25years; weight < 25kgs,; Materials-Monocrystalline/ Polycrystalline Silicon; Allowable Ambient Polycrystalline Silicon; Allowable Ambient Temperature Range -40°C to +60°				
	Battery: Input Voltage 12.8 V; Lithium-Ion Grade A LifePO4 120aH/12.8V Battery; Lifetime- 6 to 8 years; Charging Discharging Cycles- 2000; Charging - 6 to 7 Hours; Working Time under Rainy Days; 8 to 12 days				
	Charge Controller: Microcomputer Intelligent Control for Circuit Protection				
	LED Lamp: Industrial Grade High Lumens Chips, Luminous Flux: 21600 Luminous Flux: 6000 to 30,000 Lumens; Lifetime :> 50,000 hours Housing-High Preasure die cast aluminum with heat management system and rust resistant				
	Lighting Time: 10/12 hrs,/day sustain 8 to 12 days rainy days				
	IP Rating: IP67 waterproof rating				
	Warranty Period: 6 years minimum				
	2. Mounting Height Pole				
	Height: 8.0 meters with 3.0 meters single Mast Arm				
	Round Steel Tapered Post: 4.0 mm Thickness; Bottom 200 mm. dia Top 150 mm. dia.	8.00	each		
	Base Plate: 25 mm x 450 mm x 450 mm				
	Stiffener Plate: 4pcs.-16 mm x 200 mm x 100 mm x 20 mm				
	Hot Dip Galvanized Anchor Bolt: 4pcs. 25 mm. dia. X 500 mm A307 with nuts and washers				

To be used for the supply and delivery of Materials for the installation of Solar Street Lights along Manila North Road, this district

Brand and Model : **Warranty :**

After having carefully read and accepted your general Conditions, I/ We quote you on the item(s) at prices note above.

Please email your quotation at:
rfqdpwhbul1deo@gmail.com

Printed Name/ Signature/ Date

Tel. Nos. (044) 794-2245 loc 31448 Telefax: 794-2245

Tel. No./ Cellphone No./ E-mail Address