



Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
Region III
OFFICE OF THE REGIONAL DIRECTOR
Sindalan, City of San Fernando, Pampanga



March 14, 2024

**NOTICE OF PROCUREMENT
THRU ALTERNATIVE METHODS**

Please be informed that the Department of Public Works and Highways, Regional Office No. III, Sindalan, City of San Fernando, Pampanga through the Bids and Awards Committee (BAC) shall be undertaking thru ***Small Value Procurement*** the hereunder project, pursuant to Section 53.9 of the Revised IRR of RA 9184, to wit:

Purchase Request No.	Description	Amount
2024-03-0049 dated March 13, 2024	Procurement of Metal Beam for Repair and Maintenance of National Roads of DPWH Bataan Sub (3rd) District Engineering Office, Balanga City, Bataan.	PHP 995,669.00



IGNACIO F. EVANGELISTA
Chief, Legal Division
(BAC-Chairman)

✉ Email: region3@dpwh.gov.ph
☎ Tel. No.: (045) 649-4142






RVF/BDE/KOL



GENERAL NOTES :

1. MATERIALS & WORKMANSHIP SHALL CONFORM WITH THE DPWH STANDARD SPECIFICATIONS FOR HIGHWAYS, BRIDGES & AIRPORTS 2004 EDITION VOLUME II.
2. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS INDICATED OTHERWISE.
3. CONCRETE POST SHALL CONFORM WITH THE REQUIREMENTS OF CLASS "C" CONCRETE, ITEM 405 AND REINFORCING STEEL SHALL CONFORM WITH REQUIREMENTS OF REINFORCING STEEL, ITEM 404.
4. BOLT HOLES ON CONCRETE POST SHALL BE 2.0 mm LARGER THAN BOLT DIAMETERS AND ALL BOLTS SHALL BE PAINTED TWO (2) COAT OF RED LEAD PAINT.
5. GAUGE OF FLEX BEAMS GUARDRAIL SHALL BE AS INDICATED IN PLANS OR SPECIFICATIONS.
6. ALL NUTS SHALL BE WELDED TO BOLTS AFTER TIGHTENING.
7. ALL LAPS OF GUARD RAILS SHALL BE IN THE DIRECTION OF TRAFFIC FLOW.

GUARDRAIL DETAILS



SCALE

NTS

SECTION OF POST

SPOT DETAIL