

Republic of the Philippines
 Department of Public Works and Highways
 Bureau : DPWH
 Region : IX
 District/City : Zamboanga City
PROGRAM OF WORK
 (For all types of Project)

Date :

NAME/LOCATION OF PROJECT :		Appropriation : P 109,213,000.00
CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE		Source of Funds : CY-2018
PROJECT CATEGORY :		Issued Obligated Authority :
FLOOD CONTROL		Released :
PROJECT DESCRIPTION :		Cal. Days to Complete : 247 Calendar Days
Scope of Work : Construction of Flood Control		Desirable Starting Date : Upon Approval
NET LENGTH :		Mode of Implementation :
Downstream:		
Beg. Of Project 0 + 000.00		
End Of Project 0 + 569.5		
Net Length : 569.50000 In.m.		569.50

MINIMUM EQUIPMENT REQUIREMENT :

Description	No.	Description	No.	Description	No.
Dumpruck (10-Wheeler)	12	Water Pump	1	Project Engineer	1
Drop Hammer	4	Cutting Outfit	1	Materials Engineer	1
Crawler Crane	2	Concrete Vibrator	2	Geomeitric Surveyor	1
Truck mounted Crane	1	Air compressor	2	Foreman	1
Road Grader	2	Bar Cutter	1	Materials Lab. Tech.	1
Road Roller	2	Bar Bender	1	Mason	10
Payloader	4	Conc. Mixer (1-Bagger)	2	Carpenter	6
Water Truck	2	Plate Compactor	1	Laborers (Skilled)	10
Water Tank	2	Jack Hammer	1	Laborers (Unskilled)	20
Backhoe with breaker	1	Diesel Hammer	1		
Vibro Hammer	1	Service Truck	1		


ESTIMATED COST OF PROPOSED WORK

ITEM NO.	DESCRIPTION	% OF TOTAL	UNIT	QUANTITY	DIRECT COST	
					TOTAL	UNIT COST
PART B - OTHER GENERAL REQUIREMENTS						
A.1.1(3)	Construction of Field Office for the Engineer	0.566	L. S.	1.00	481,851.56	481,851.56
A.1.1(11)	Provision of Furnitures/Fixtures, Equipment & Appliances for the Field Office for the Engineer	0.230	L. S.	1.00	196,288.00	196,288.00
A.1.2 (5)	Operation & Maintenance of Gov't Service Vehicle	0.421	L.S.	1.00	358,604.73	358,604.73
B.4(1)	Construction Survey and Staking	0.070	k.m.	0.570	59,646.82	104,735.41
B.5	Project Billboard	0.009	units	2.00	7,538.90	3,769.45
B.7	Occupational Safety and Health Program	0.552	L. S.	1.00	470,334.00	470,334.00
B.9	Mobilization & Demobilization	0.639	L. S.	1.00	544,688.00	544,688.00
PART C - EARTHWORKS						
1702(1)	Structure Excavation	1.052	cu.m.	3,897.00	896,760.69	230.12
PART J - FLOOD CONTROL AND DRAINAGE						
404(1)a	Reinforcing Steel, (Grade 40)	0.536	kg.	9,278.00	456,706.94	49.22
404(1)b	Reinforcing Steel, (Grade 60)	0.488	kg.	8,088.00	415,987.25	51.43
405(1)b3	Structural Concrete, fc" = 27.58 MPA	3.597	cu.m.	473.00	3,064,573.95	6,479.01
1716(6)	Structural Steel Sheet Piles, Furnished	43.717	In.m.	11,392.00	37,249,332.74	3,269.78
1716 (12)	Structural Steel Sheet Piles, Driven	9.626	In.m.	11,392.00	8,202,267.58	720.00
1716(16)	Steel Sheet Test Piles, Furnished and Driven	0.105	In.m.	16.00	89,576.95	5,598.56
PART G - DRAINAGE AND SLOPE PROTECTION						
1710(5)	Grouted Riprap, Class "A"	9.158	cu.m.	1,568.00	7,802,998.24	4,976.40
1713(1)	Rubble Concrete	6.641	cu.m.	1,600.00	5,658,396.92	3,536.50
508(1)	Handlaid Rock Embankment	22.593	cu.m.	13,471.00	19,250,433.91	1,429.03
TOTAL					P	85,205,987.19


NAME OF PROJECT : CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

BREAKDOWN OF ESTIMATED EXPENDITURES	% OF TOTAL	AMOUNT
I. ESTIMATED COST		
A. DIRECT COST		
A.1. Materials	60.90	66,510,503.50
A.2. Labor	4.54	4,960,119.15
A.3. Equipment Expenses	12.58	13,735,364.54
SUB-TOTAL (DIRECT COST)	78.02	85,205,987.19
B. INDIRECT COST (Per D.O. # 57)		
B.1. Overhead, Contingency & Misc. (10 % Max. of D.C.)	7.66	8,363,607.25
B.2. Profit (8 % Max. of D.C.)	6.18	6,744,215.56
C. VAT (5 % of D.C. and I.C. per D.O. 197 S. 2016)	4.59	5,015,690.50
SUBTOTAL (CONTRACT COST)	96.44	105,329,500.49
II. ESTIMATED GOVERNMENT EXPENDITURES		
1. Engineering and Administrative Overhead (3.5%)	3.50	3,822,455.00
2. Detailed Engineering (1%)	0.00	
3. Reserved for the Payment of RROW	0.06	61,044.51
4. Provisional Sum	0.00	
TOTAL ESTIMATED PROJECT COST	100.00	109,213,000.00

Prepared :


JOSEPHINE B. RENGQUINO
Engineer II

Checked :


JERALD R. BARRERA
Engineer II


Submitted :


LEONCIO B. SOLAMILLO
Chief, Construction Division

Recommending Approval:


CAYAMOMBAO D. DIA
Assistant Regional Director

Approved:


JORGE U. SEBASTIAN, JR. CESO III
Regional Director

APPROVED BUDGET FOR THE CONTRACT
CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Project Name and Location

Stations: Downstream:

Length: 569,50000

Contract Duration : 247 Calendar Days

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	ESTIMATED DIRECT COST	MARK-UPS IN PERCENT			TOTAL MARK-UPS	VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
					OCM	PROFIT	%					
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9)	(10)	(11)	(12)	(13)
PART B - OTHER GENERAL REQUIREMENTS												
A.1.(3)	Construction of Field Office for the Engineer	1.00	L.S.	481,851.56	10.00	8.00	18.00	86,733.28	28,429.24	115,162.52	597,014.08	
A.1.(11)	Provision of Furniture/Fixtures, Equipment & Appliances for the Field Office for the Engineer	1.00	L.S.	196,288.00		8.00	8.00	15,703.04	10,599.55	26,302.59	222,590.59	
A.1.2 (5)	Operation & Maintenance of Gov't Service Vehicle	1.00	L.S.	358,604.73				-	17,930.24	17,930.24	376,534.97	
B.4(1)	Construction Survey and Staking	0.57	Km.	59,646.82	10.00	8.00	18.00	10,736.43	3,519.16	14,255.59	73,902.41	129,767.18
B.5	Project Billboard	2.00	units	7,538.90	10.00	8.00	18.00	1,357.00	444.80	1,801.80	9,340.70	4,670.35
B.7	Occupational Safety and Health Program	1.00	L.S.	470,334.00		8.00	8.00	37,626.72	25,398.04	63,024.76	533,358.76	
B.9	Mobilization & Demobilization	1.00	L.S.	544,688.00			0.00	-	27,234.40	27,234.40	571,922.40	
PART C - EARTHWORKS												
1702(1)	Structure Excavation	3,897.00	cum.	896,760.69	10.00	8.00	18.00	161,416.92	52,908.88	214,325.80	1,111,086.49	285.11
PART J - FLOOD CONTROL AND DRAINAGE												
404(1)a	Reinforcing Steel, (Grade 40)	9,278.00	kg.	456,706.94	10.00	8.00	18.00	82,207.25	26,945.71	109,152.96	565,859.90	60.99
404(1)b	Reinforcing Steel, (Grade 60)	8,088.00	kg.	415,987.25	10.00	8.00	18.00	74,877.70	24,543.25	99,420.95	515,408.20	63.73
405(1)b3	Structural Concrete, (c' = 27.58 MPa	473.00	cum.	3,064,573.95	10.00	8.00	18.00	551,623.31	180,809.86	732,433.17	3,797,007.12	8,027.50
1716(6)	Structural Steel Sheet Piles, Furnished	11,392.00	lin.m.	37,249,332.74	10.00	8.00	18.00	6,704,879.89	2,197,710.63	8,902,590.53	46,151,223.27	4,051.26
1716 (12)	Structural Steel Sheet Piles, Driven	11,392.00	lin.m.	8,202,267.58	10.00	8.00	18.00	1,476,408.17	483,933.79	1,960,341.95	10,162,609.54	892.08
1716(16)	Steel Sheet Test Piles, Furnished and Driven	16.00	lin.m.	89,576.95	10.00	8.00	18.00	16,123.85	5,285.04	21,408.89	110,985.85	6,936.62
PART G - DRAINAGE AND SLOPE PROTECTION												
1710(5)	Grooved Riprap, Class "A"	1,568.00	cum.	7,802,998.24	10.00	8.00	18.00	1,404,539.68	460,376.90	1,864,916.58	9,667,914.82	6,165.76
1713(1)	Rubble Concrete	1,600.00	cum.	5,658,396.92	10.00	8.00	18.00	1,018,511.45	333,845.42	1,352,356.86	7,010,753.79	4,381.72
508(1)	Handled Rock Embankment	13,471.00	cum.	19,250,433.91	10.00	8.00	18.00	3,465,078.10	1,135,775.60	4,600,853.71	23,851,287.62	1,770.57
				85,205,987.19				15,107,822.80	5,015,690.50	20,123,513.30	105,329,500.49	

Prepared /Submitted by :

BELEN A. SAPALLERA
Engineer IV - Chairman Estimating Committee

Recommending Approval:

CAYAMORABAO D. DIA
Assistant Regional Director

Approved :

JOSEF B. SERRANO JR., SERRANO
Regional Director

PROJECT : C

WORK PROGRAMME/SCHEDULE

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	DURATION NO. OF DAYS	WEEKS (6 WORKING DAYS)																																							
PART B - OTHER GENERAL REQUIREMENTS																																												
A.1.(1)(3)	Construction of Field Office for the Engineer	1.00	L.S.	15.00																																								
A.1.(1)(1)	Provision of Furniture/Fixtures, Equipment & Appliances for the Field	1.00	L.S.	247.00																																								
A.1.2 (5)	Operation & Maintenance of Govt Service Vehicle	1.00	L.S.	247.00																																								
B.4(1)	Construction Survey and Staking	0.57	k.m.	5.70																																								
B.5	Project Billboard	2.00	units	0.25																																								
B.7	Occupational Safety and Health Program	1.00	L.S.	247.00																																								
PART B - EARTHWORKS																																												
1702(1)	Structure Excavation	3,897.00	cum.	24.36																																								
PART J - FLOOD CONTROL AND DRAINAGE																																												
1716(6)	Structural Steel Sheet Piles, Furnished	11,392.00	In.m.	14.83																																								
1716 (12)	Structural Steel Sheet Piles, Driven	11,392.00	In.m.	71.20																																								
1716(16)	Steel Sheet Test Piles, Furnished and Driven	16.00	In.m.	0.25																																								
404(1) c	Reinforcing Steel, (Grade 40)	9,278.00	kg.	3.22																																								
404(1) b	Reinforcing Steel, (Grade 60)	8,088.00	kg.	2.81																																								
405(1) b3	Structural Concrete, f'c = 27.58 MPa	473.00	cum.	14.08																																								
PART G - DRAINAGE AND SLOPE PROTECTION																																												
1710(5)	Grooved Riprap, Class "A"	1,568.00	cum.	52.27																																								
1713(1)	Rubble Concrete	1,600.00	cum.	47.62																																								
508(1)	Hemlock Rock Embankment	13,471.00	cum.	53.88																																								
DEMOLITION																																												

Prepared:

Submitted:

Approved:

JOSEPHINE B. RENGOLLO

LEONCIO B. SOLAMILLO

JORGE H. SEBASTIAN, JR., CEO III
Regional Director

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: A.1.1(3) Construction of Field Office for the Engineer

Unit of Measurement: L. S.

Output per hour:

Quantity: 1.00

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor					
a. Const. Foreman		1	15.00	611.92	9,178.80
b. Masons		4	15.00	443.20	26,592.00
c. Carpenters		4	15.00	443.20	26,592.00
d. Laborers		8	15.00	342.24	41,068.80
Sub-total for A				P	103,431.60
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)					
a. Bagger Mixer		1	15.00	1,376.00	20,640.00
b. Water Truck		1	1.00	19,600.00	19,600.00
c. Minor Tools, 10% of Labor				P	10,343.16
Sub-total for B					50,583.16
Total (A+B)					154,014.76
D. Output/day					
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials					
Gravel Bedding		0.00	cu.m.	956.50	-
Selected Fill		0.00	cu. m.	456.50	-
Soil Poisoning		0.00	lit.	1,900.00	-
Portland Cement		220.00	bag	283.00	62,260.00
Crushed gravel		15.00	cu.m.	956.50	14,347.50
Washed Sand		25.00	cu.m.	956.50	23,912.50
Deformed Bars, Grade 60		800.00	kg.	42.00	33,600.00
No. # 16 G.I. Tie Wire		35.00	kg.	70.00	2,450.00
Coco Lumber		600.00	bd.ft.	15.00	9,000.00
Ordinary Plywood, 1/4" x 4' x8"		0.00	pcs.	853.00	-
CWN, Assorted		20.00	kg.	75.00	1,500.00
CHB 6" thick		850.00	pc.	20.00	17,000.00
10mm dia. X 6m RSB		150.00	kg.	43.00	6,450.00
D-1, Hollow Core Flush Type swing door, complete w/ accessories		1.00	set	1,495.20	1,495.20
W-1, Jalousie window, 1.4mx 1.2m.		0.00	set	1,176.00	-
W-2, Jalousie window, 2.8m x 1.2m		0.00	set	2,352.00	-
65 x 65 x 6mm Angle Bar		400.00	kg.	48.00	19,200.00
50 x 50 x 6mm Angle Bar		200.00	kg.	48.00	9,600.00
50 x 50 x 4mm Angle Bar		120.00	kg.	48.00	5,760.00
Purlins C-150x50x3mm		35.00	kg.	48.00	1,680.00
16mm dia. Cross Bracing		65.00	kg.	50.00	3,250.00
16mm dia. Turn Buckle		30.00	pc.	230.00	6,900.00
12mm thk. Base plate		45.00	kg.	48.00	2,160.00
10mmthk batten plate		30.00	kg.	48.00	1,440.00
Sub-total for E				P	222,005.20
Total Cost For Materials					327,836.80
Direct Cost (C + E)					481,851.56
Overhead, Contingencies and Miscellaneous			10% per D.O.197 s 2016		48,185.16
Contractor's Profit (CP)			8% per D.O.197 s 2016		38,548.12
Value Added Tax (VAT)			5% per D.O.197 s 2016		28,429.24
Total Unit Cost					597,014.08

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: A.1.1(3) Construction of Field Office for the Engineer

Unit of Measurement: L.S.

Output per hour:

Quantity: 1.00

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor					
a.	Const. Foreman	1		611.92	-
b.	Masons	4		443.20	-
c.	Carpenters	6		443.20	-
d.	Laborers	10		342.24	-
Sub-total for A					P
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)					
a.	Bagger Mixer	1		1,376.00	-
b.	Water Truck	1		19,600.00	-
c.	Minor Tools, 10% of Labor			0.00	-
Sub-total for B					P
C.	Total (A+B)				-
D. Output/day					
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials					
10mm dia. Sag rod		15.00	kg.	48.00	720.00
20mm dia. X 350mm Anchor Bolts		15.00	pc.	150.00	2,250.00
Welding Rod		25.00	kg.	130.00	3,250.00
Primer, Zinc Chromate		5.00	gal.	531.00	2,655.00
Pre-painted G.I. Roofing Sht. Long span		55.00	sq.m.	420.00	23,100.00
Pre-painted flashing Ridge Roll GA24.0.60m w		10.00	ln.m.	189.00	1,890.00
Pre-painted flashing, GA 24		2.00	ln.m.	189.00	378.00
Teckscrew 1-1/2"		1,000.00	pc.	1.25	1,250.00
Roof Sealant		2.00	lit.	230.00	460.00
Rough Lumber, Sun dries Tanguile		700.00	bd.ft.	37.00	25,900.00
Finishing Nails		5.00	kg.	280.00	1,400.00
Wood Preservative Brown		-	lit.	7,245.00	-
2 x 40w Fluorescent lighting fixtures		5.00	set	1,450.00	7,250.00
Porcelain Ceiling Outlet w/female		2.00	pc.	50.00	100.00
Duplex Convenience Outlet		3.00	pc.	170.00	510.00
Two gang Switch		3.00	pc.	132.00	396.00
3.50mm2 THW		2.00	roll	3,600.00	7,200.00
8.00mm2 THW		20.00	m.	69.33	1,386.60
15mm dia. PVC pipe		20.00	pc.	76.00	1,520.00
15mm dia. PVC Coupling		20.00	pc.	27.00	540.00
15mm dia. PVC Elbow		20.00	pc.	26.00	520.00
15mm dia. PVC Clamp		50.00	pc.	8.00	400.00
20mm dia. RSC Pipe		4.00	pc.	240.00	960.00
20mm dia. RSC Coupling		3.00	pc.	36.00	108.00
20mm dia. RSC Elbow		3.00	pc.	30.00	90.00
20mm dia. RSC Clamp		10.00	pc.	18.00	180.00
20mm dia. Service Entrance Cap		2.00	pc.	101.50	203.00
Wire Holder		2.00	pc.	50.00	100.00
Utility Box		7.00	pc.	32.00	224.00
Octagon Box		50.00	pc.	34.00	1,700.00
Sub-total for E					P
Sub-total for E					86,640.60
F. Direct Cost (C + E)					86,640.60
G. Overhead, Contingencies and Miscellaneous	10% per D.O.197 s 2016				
H. Contractor's Profit(CP)	8% per D.O.197 s 2016				
I. Value Added Tax (VAT)	5% per D.O.197 s 2016				
L. Total Unit Cost					

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: A.1.1 (3) Construction of Field Office for the Engineer
Unit of Measurement: L. S.
Output per hour:
Quantity: 1.00

Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials					
Electrical Tape(big)		7.00	pc.	28.00	196.00
Panel Board 9 Side main w/ branches)		2.00	set	2,750.00	5,500.00
Water Closet(include fitting&Accessories)		1	set	6,062.00	6,062.00
Lavatory(include fitting & accessories)		1	set	4,512.00	4,512.00
1/2" GI Pipe S-40		2	pc.	292.00	584.00
1/2" Water Faucet		2	pc.	165.00	330.00
1/2" Assorted Connector		8	pc.	19.00	152.00
4" PVC Series 1000		1	pc.	640.00	640.00
2" PVC Series 1000		1	pc.	305.00	305.00
4" PVC Assorted Connector		6	pc.	77.00	462.00
2" PVC Assorted Connector		8	pc.	56.00	448.00
Sub-total for E				P	19,191.00
F. Direct Cost (C + E)					19,191.00
G. Overhead, Contingencies and Miscellaneous					-
H. Contractor's Profit(CP)					
I. Value Added Tax (VAT)					
L. Total Unit Cost					

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: A.1.1(11) Provision of Furnitures/Fixtures, Equipment & Appliances for the Field Office for
Unit of Measurement: L. S. the Engineer
Output per hour:
Quantity: 1.00

Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Office Equipment/Facilities& Supplies				
White Board , 3' x 6'	1	each.	2,000.00	-
8-seater Monoblock Dining Table	1	unit	3,000.00	-
Monoblock Backrest Chair	12	pcs.	500.00	-
Plastic Pail & Basin	2	set	300.00	2,000.00
Aluminum Cookware	1	set	3,000.00	3,000.00
each Plate, Glass, Spoon & Fork	1	doz	1,900.00	6,000.00
6" Sleeping Bed, Good quality w/ pillows & blanket	3	each.	5,000.00	600.00
Office Table, Jr. Executive type	1	each.	7,000.00	3,000.00
w/ chair				1,900.00
Drawing Table	1	each.	5,000.00	15,000.00
Computer Table	1	each.	3,000.00	7,000.00
Cartridge(Computer Printer/Ink)	6	sets	1,800.00	-
CD RW	15	pc.	35.00	5,000.00
DVD Recordable & Writer	2	pc.	55.00	3,000.00
Bond paper (Long)	16	ream	330.00	10,800.00
Bond paper (Short)	15	ream	270.00	525.00
Yellow pad	6	pads	34.00	110.00
Scotch Tape	6	rolls	45.00	5,280.00
Masking Tape	6	rolls	134.00	4,050.00
Batteries" Energizer"	15	pc.	48.00	204.00
Ballpen	4	box	200.00	270.00
Pencil Lead, No. 5	4	box	150.00	804.00
Paper Clip(Plastic coated)	4	box	40.00	720.00
Fastener(plastic coated)	6	box	60.00	800.00
Eraser(Ink, pencil)	6	box	20.00	600.00
Staple wire	6	box	250.00	160.00
Cutter blade	3	box	250.00	360.00
Glue, 130 grams	6	bottle	85.00	120.00
Correction Fluid Pen	6	bottle	50.00	1,500.00
Brown Envelope, Long & Short	5	doz.	85.00	750.00
Expanded Envelope, long	5	doz.	125.00	510.00
Colored Pencil, 12s	6	set	145.00	300.00
Folder, short	6	doz.	90.00	425.00
Folder, long	6	doz.	95.00	625.00
Pentel pen (Assorted colors)	6	pcs.	60.00	870.00
White Board Marker(Assorted colors)	6	pcs.	85.00	540.00
Letter Envelope, White(Long)	1	box	100.00	570.00
Data File Folder	6	pcs.	100.00	360.00
Sign Pen, Assorted Colors	2	doz.	900.00	510.00
				100.00
				600.00
				1,800.00
				-
F. Sub-total for E			P	80,763.00
F. Direct Cost (C + E)				196,288.00
G. Overhead, Contingencies and Miscellaneous				-
H. Contractor's Profit(CP)		8% per D.O.197 s 2016		15,703.04
I. Value Added Tax (VAT)		5% per D.O.197 s 2016		10,599.55
L. Total Unit Cost				222,590.59

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: A.1.1(11) Provision of Furnitures/Fixtures, Equipment & Appliances for the Field Office for
Unit of Measurement: L. S. the Engineer
Output per hour:
Quantity: 1.00

Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials	Office Equipment/Facilities& Supplies				
	Desktop Computer	1	unit	60,000.00	60,000.00
	Digital Camera (12 MP)	1	unit	10,000.00	10,000.00
	Computer Printer (Scanner & Xerox)	1	unit	5,000.00	5,000.00
	USB (16GB)	2	pcs.	800.00	1,600.00
	Water Dispenser	1	unit	7,000.00	7,000.00
	Electric Fan	2	pcs.	1,500.00	3,000.00
	Steel Cabinet	1	unit	4,500.00	4,500.00
	Gas Stove w/tank	1	set	3,500.00	3,500.00
	stove tank refill	6	tanks	890.00	5,340.00
	Wall Clock	2	pcs.	350.00	700.00
	Rice Cooker	1	unit	1,200.00	1,200.00
	Scientific Calculator	1	pc.	2,500.00	2,500.00
	Electric Airpot	1	unit	1,500.00	1,500.00
	water container	4	pcs.	200.00	800.00
	puncher	1	pc.	250.00	250.00
	Stapler no. 35	2	pcs.	350.00	700.00
	Bulletin/Cork Board 2" x 3"	2	pc.	500.00	1,000.00
	Scissors	5	pcs.	35.00	175.00
	Record Book (500 leaves)	6	pcs.	110.00	660.00
	Folding beds	2	pcs.	1,700.00	3,400.00
	Bedsheets (Single)	6	pcs.	200.00	1,200.00
	Rechargeable Lamps	2	unit	750.00	1,500.00
				-	-
				-	-
				-	-
				-	-
				-	-
				-	-
				-	-
Sub-total for E				P	115,525.00
F.	Direct Cost (C + E)				115,525.00
G.	Overhead, Contingencies and Miscellaneous				-
H.	Contractor's Profit (CP)				
I.	Value Added Tax (VAT)				
L.	Total Unit Cost				

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:	A.1.2 (5)	Operation & Maintenance of Go'vt Service Vehicle

Unit of Measurement: L.S.

Output per hour:

Quantity: 1.00

	Quantity.	Designation	No. of Persons	No. of Days	Daily Rate	Amount
A. Labor a. Service Driver	1.00		1	247.00	443.20	109,470.40
						- - - - - - -
					P	109,470.40
B.		Name and Capacity	No. of Equipment	No. of Days	Daily Rate	Amount
a.		GOV'T SERVICE VEHICLE	1	8.23		- - - - - - - -
						- -
					P	109,470.40
C.		Total (A+B)				109,470.40
D.		Output/day				
E.		Name and Specifications	Quantity	Unit	Unit Cost	Amount
a.		Materials	2,470.00	liter	42.00	103,740.00
b.		liters, Diesel Fuel	1.00	I.s.	15,561.00	15,561.00
c.		Engine Oil & Lubricants	5.00	p.c.s.	9,500.00	47,500.00
d.		Tires	1.00	L.S.	82,333.33	82,333.33
		Spare parts etc.				- - - - - -
					P	249,134.33
F.		Sub-total for E				358,604.73
G.		Direct Cost (C + E)				-
H.		Overhead, Contingencies and Miscellaneous Contractor's Profit(C/P)				-
I.		Value Added Tax (VAT) 5% per D.O.197 s 2016				17,930.24
L.		Total Unit Cost				376,534.97

jcbor

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:

Construction Survey and Staking

Unit of Measurement: k.m.

Output per hour:

Quantity: 0.57

Quantity:	Designation	No. of Persons	No. of Days	Daily Rate	Amount
A.	Labor For Fieldworks: (assumed output = 300 In.m.) a. Geodetic Engineer b. Skilled Laborer c. Laborer	1 1 1	1.90 1.90 1.90	833.31 443.20 342.24	1,581.90 841.34 649.69 -
	For Office works: (assumed output = 100 In.m.) a. Geodetic Engineer b. Skilled Laborer	1 1	5.70 5.70	833.31 443.20	4,745.70 2,524.02 - -
	Sub-total for A				P 10,342.65
B.	Name and Capacity	No. of Equipment	No. of Days	Daily Rate	Amount
a.	Equipment, (2014 ACEL Rates) Total Station complete w/ accessories	1	1.90	800.00	1,518.67 - - - - - - -
	Sub-total for B				P 1,518.67
C.	Total (A+B)				11,861.32
D.	Output/day				
E.	Name and Specifications	Quantity	Unit	Unit Cost	Amount
a.	Materials Standard Stake Plan (800mm x 910mm plotting)	123.00	sheets	200.00	24,600.00 -
b.	blue print as stake plan miscellaneous(5% of Materials)	615.00	pcs.	34.00	20,910.00 2,275.50 - - - - - -
	Sub-total for E				P 47,785.50
F.	Direct Cost (C + E)				59,646.82
G.	Overhead, Contingencies and Miscellaneous				5,964.68
H.	Contractor's Profit(CP)				4,771.75
I.	Value Added Tax (VAT)				3,519.16
L.	Total Unit Cost				129,767.18

icbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:

B.5 Project Billboard

Unit of Measurement: units

Output per hour:

Quantity: 2.00

[illegible]

jcbor

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: B.7 Occupational Safety and Health Program

Unit of Measurement: L. S.

Output per hour:

Quantity: 1.00

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor	a. Safety Practitioner	1	61.75	443.20	27,367.60
	b. First Aider	1	247.00	342.24	84,533.28
	c. laborers (flagmen) - 2 laborers/shift	4	247.00	342.24	338,133.12
					-
Sub-total for A					450,034.00
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)	a.				-
					-
					-
					-
Sub-total for B					-
C.	Total (A+B)				450,034.00
D.	Output/day				
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials	a. Pairs, Rubber Boots Men, Long, with Steel Toe, Black	20.00	pair	400.00	8,000.00
	b. Pairs, Working Gloves (Maong Materials)	20.00	pair	15.00	300.00
	c. Pcs., Rain Coats (Rainforced, Hip Length Small, Medium, & Large)	20.00	pcs.	100.00	2,000.00
	d. Barricades/Signboards	1.00	L.S	10,000.00	10,000.00
					-
Sub-total for E					20,300.00
F.	Direct Cost (C + E)			P	470,334.00
G.	Overhead, Contingencies and Miscellaneous				
H.	Contractor's Profit (CP)		8% per D.O.197 s 2016		37,626.72
I.	Value Added Tax (VAT)		5% per D.O.197 s 2016		25,398.04
L.	Total Unit Cost				533,358.76

jcbr

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Mobilization & Demobilization

L.S.

Quantity: 1.00

[illegible]

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: 1702(1) Structure Excavation

Unit of Measurement: cu.m.

Output per hour: 20.00

Quantity: 3,897.00

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor	a. Const. Foreman	1	24.36	611.92	14,904.08
	b. Laborers	3	24.36	342.24	25,007.05
Sub-total for A					P 39,911.13
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)	a. Dump Truck	2	24.36	11,360.00	553,374.00
	b. Backhoe Minor Tools(10% of Labor Cost)	1	24.36	12,296.00	299,484.45
Sub-total for B					P 856,849.56
Total (A+B)					896,760.69
C. Output/day		160.00 cu.m./day			
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials	a.				-
					-
Sub-total for E					P -
Sub-total for E					896,760.69
F. Direct Cost (C + E)					
G. Overhead, Contingencies and Miscellaneous		10% per D.O.197 s 2016			
H. Contractor's Profit(CP)		8% per D.O.197 s 2016			
I. Value Added Tax (VAT)		5% per D.O.197 s 2016			
Total Unit Cost					285.11

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:

Reinforcing Steel, (Grade 40)

Unit of Measurement: kg.

Output per hour: 180.00 kg./hr.

180.00

kg./hr.

Quantity:

9,278.00

Use 2 gangs of labor & equipment

[illegible]

icbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:	404(1)b	Reinforcing Steel, (Grade 60)

Unit of Measurement: kg.

Output per hour: 180.00 kg./hr.

Quantity:	8,088.00	Use 2 gangs of labor * equipment
-----------	----------	----------------------------------

[illegible]

icbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: 405(1)b3 Structural Concrete, fc' = 27.58 MPA

Unit of Measurement: cu.m.

Output per hour: 1.40

Quantity: 473.00 Use 3 gangs of equipment & labor

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor	a. Foreman	1	14.08	611.92	8,614.23
	b. Skilled	12	14.08	443.20	74,869.14
	c. Unskilled	24	14.08	342.24	115,628.23
Installation/Removal of Formworks					
b. Skilled		6	14.08	443.20	37,434.57
	c. Unskilled	12	14.08	342.24	57,814.11
					-
					-
Sub-total for A				P	294,360.29
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)	a. One bagger mixer	3	14.08	1,376.00	58,111.43
	b. Concrete vibrator	3	14.08	730.00	30,829.46
	c. Water truck	3	1.41	19,600.00	82,775.00
	Minor Tools (5% of Labor)				14,718.01
					-
					-
					-
					-
					-
					-
Sub-total for B				P	186,433.91
Total (A+B)					480,794.20
C. Output/day	33.60	In.m./day			
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials	a. Portland Cement	5,203.00	bag	283.00	1,472,449.00
	b. Fine Aggregates	236.50	cu.m.	956.50	226,212.25
	c. Coarse Aggregates	473.00	pc.	956.50	452,424.50
	d. Form lumber	8,278.00	pc.	42.00	347,676.00
	e. Plywood	190.00	pc.	423.00	80,370.00
	f. Assorted CWNails	83.00	pc.	56.00	4,648.00
					-
					-
					-
					-
					-
					-
Sub-total for E				P	2,583,779.75
Direct Cost (C + E)					3,064,573.95
G. Overhead, Contingencies and Miscellaneous			10% per D.O.197 s 2016		306,457.39
H. Contractor's Profit(CP)			8% per D.O.197 s 2016		245,165.92
I. Value Added Tax (VAT)			5% per D.O.197 s 2016		180,809.86
L. Total Unit Cost					8,027.50

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: 1716(6) Structural Steel Sheet Piles, Furnished

Unit of Measurement: In.m.

Output per hour: 48

In.m./hr.

Quantity: 11,392.00

Use 2 gangs of labor & equipment

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor					
	a. Const. Foreman	1	14.83	611.92	9,076.81
	b. Skilled Laborers	4	14.83	443.20	26,296.53
	c. Unskilled Laborers	4	14.83	342.24	20,306.24
Sub-total for A					55,679.59
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)					
	a. Truck Mounted Crane	2	14.83	20,848.00	618,490.67
					-
					-
Sub-total for B					618,490.67
Total (A+B)					674,170.25
Output/day		In.m./day			
768.00					
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials					
	a. Steel Sheet Pile FY50	546,816.00	kg.	66.89	36,575,162.49
					-
					-
Sub-total for E					36,575,162.49
Direct Cost (C + E)					37,249,332.74
Overhead, Contingencies and Miscellaneous		10% per D.O.197 s 2016			
Contractor's Profit(CP)		8% per D.O.197 s 2016			
Value Added Tax (VAT)		5% per D.O.197 s 2016			
Total Unit Cost					4,051.26

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:	1716 (12)	Structural Steel Sheet Piles, Driven

Unit of Measurement: In.m.

Output per hour: 10.00
ln.m./hr.

Quantity: 11,392.00

Use 2 gangs for labor & equipment

[illegible]

jcbor

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: 1716(16) Steel Sheet Test Piles, Furnished and Driven

Unit of Measurement: In.m.

Output per hour: 8.000 In.m./hr.

Quantity: 16.00

Designation		No. of Persons	No. of Days	Daily Rate	Amount
A. Labor	a. Const. Foreman	1	0.25	611.92	152.98
	b. Skilled	6	0.25	443.20	664.80
	c. Laborers, Unskilled	6	0.25	342.24	513.36
					-
Sub-total for A					1,331.14
Name and Capacity		No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)	a. Truck Mounted Crane	1	0.25	20,848.00	5,212.00
	b. Vibro Hammer	1	0.25	16,984.00	4,246.00
	c. Gen. Set	1	0.25	10,373.36	2,593.34
	d. Welding Machine	1	0.25	2,968.00	742.00
	e. Cutting Outfit	1	0.13	363.60	133.11
Sub-total for B					-
Total (A+B)				P	12,926.45
Output/day		64.00	In.m./day		14,257.59
Name and Specifications		Quantity	Unit	Unit Cost	Amount
E. Materials	a. Coco logs	13.60	m.	520.00	7,072.00
	b. Good Lumber	64.00	bd.ft.	42.00	2,688.00
	c. Nail/Spike	2.56	kg.	42.00	107.52
	d. Steel Sheet Pile	16.00	m.	4,051.26	64,820.16
	e. Welding Rod	0.38	kg.	145.00	55.68
	f. Oxy/Acetylene	0.15	set	3,750.00	576.00
Sub-total for E					-
Direct Cost (C + E)				P	75,319.36
Overhead, Contingencies and Miscellaneous			10% per D.O.197 s 2016		89,576.95
Contractor's Profit(CP)			8% per D.O.197 s 2016		8,957.70
Value Added Tax (VAT)			5% per D.O.197 s 2016		7,166.16
Total Unit Cost					5,285.04
					6,936.62

jcbr

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:	1710(5)	Grouted Riprap, Class "A"
-----------------------	---------	---------------------------

Unit of Measurement: cu.m.

Output per hour: 1.25 cu.m./hr.

Quantity:	1,568.00	Use 3 gangs for labor & equipment
-----------	----------	-----------------------------------

	Designation	No. of Persons	No. of Days	Daily Rate	Amount
A.	Labor				
a.	Const. Foreman	1	52.27	611.92	31,983.02
b.	Skilled laborer	6	52.27	443.20	138,987.52
c.	Unskilled Laborer	24	52.27	342.24	429,305.86
-					-
-					-
-					-
-					-
-					-
-					-
-					-
P					600,276.39
Sub-total for A					
B.	Name and Capacity	No. of Equipment	No. of Days	Daily Rate	Amount
a.	Equipment, (2014 ACEL Rates)				
b.	One bagger mixer	3	52.27	1,376.00	215,756.80
	Water truck	3	52.27	19,600.00	3,073,280.00
	Minor Tools(10% of Labor)				-
					60,027.64
					-
					-
					-
					-
					-
					-
					-
P					-
Sub-total for B					
C.	Total (A+B)				3,349,064.44
					3,949,340.83
D.	Output/day	30.00	cu.m./day		
E.	Name and Specifications	Quantity	Unit	Unit Cost	Amount
a.	Materials				
a.	Portland Cement	4,704.00	bag	283.00	1,331,232.00
b.	Fine Aggregates	392.00	cu.m.	956.50	374,948.00
c.	Gravel Fill	23.52	cu.m.	956.50	22,496.88
d.	Weep Holes	470.00	m.	204.00	95,880.00
e.	Filter Cloth	24.00	sq.m.	160.00	3,840.00
f.	Boulders	1,647.00	cu.m.	1,206.50	1,987,105.50
	Miscellaneous(1% Materials)				38,155.02
					-
					-
					-
					-
					-
P					-
Sub-total for E					
F.	Direct Cost [C + E]				3,853,657.40
G.	Overhead, Contingencies and Miscellaneous				7,802,998.24
H.	Contractor's Profit(CP)				780,299.82
I.	Value Added Tax (VAT)				624,239.86
L.	Total Unit Cost				460,376.90
					6,165.76

jcbor

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME: CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM), SIOCON, ZAMBOANGA DEL NORTE

Item No./Description: 1713(1) Rubble Concrete

Unit of Measurement: cu.m.

Output per hour: 1.40 cu.m./hr.

Quantity: 1,600.00

Designation	No. of Persons	No. of Days	Daily Rate	Amount
A. Labor				
a. Const. Foreman	1	47.62	611.92	29,139.05
b. Skilled laborer	6	47.62	443.20	126,628.57
c. Unskilled Laborer	24	47.62	342.24	391,131.43
				-
				-
				-
				-
				-
				-
Sub-total for A				P 546,899.05
Name and Capacity	No. of Equipment	No. of Days	Daily Rate	Amount
B. Equipment, (2014 ACEL Rates)				
a. One bagger mixer	3	47.62	1,376.00	196,571.43
b. Water truck	3	2.38	19,600.00	140,000.00
c. Backhoe	3	4.76	12,296.00	175,657.14
Minor Tools (10% of Labor)				54,689.90
				-
				-
				-
				-
				-
Sub-total for B				P 566,918.48
Total (A+B)				1,113,817.52
D. Output/day	33.60	cu.m./day		
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Portland Cement	6,720.00	bag	283.00	1,901,760.00
b. Fine Aggregates	420.00	cu.m.	956.50	401,730.00
c. Gravel Fill	32.00	cu.m.	956.50	30,608.00
d. Weep Holes	480.00	m.	204.00	97,920.00
e. Filter Cloth	24.00	sq.m.	160.00	3,840.00
f. Boulders	1,008.00	cu.m.	1,206.50	1,216,152.00
g. Coarse Aggregates	840.00	cu.m.	956.50	803,460.00
Miscellaneous(2% Materials)				89,109.40
				-
				-
				-
				-
Sub-total for E				P 4,544,579.40
Direct Cost (C + E)				5,658,396.92
G. Overhead, Contingencies and Miscellaneous	10% per D.O.197 s 2016			565,839.69
H. Contractor's Profit(CP)	8% per D.O.197 s 2016			452,671.75
I. Value Added Tax (VAT)	5% per D.O.197 s 2016			333,845.42
L. Total Unit Cost				4,381.72

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME:

CONSTRUCTION/MAINTENANCE OF FLOOD MITIGATION STRUCTURES AND DRAINAGE SYSTEMS - EXTENSION OF FLOOD CONTROL STRUCTURE ALONG SIOCON RIVER (DOWNSTREAM) , SIOCON, ZAMBOANGA DEL NORTE

Item No./Description:	508(1)	Handlaid Rock Embankment
-----------------------	--------	--------------------------

Unit of Measurement: cu.m.

Output per hour: 3.125 cu.m./hr.

Quantity:	13,471.00	Use 10 gangs for labor
-----------	-----------	------------------------

[illegible]

jcbbr

UNIT COST ANALYSIS FOR HAULING COST FOR ALL AGGREGATES

Hauling Cost from the District Office to Site

Item No. :	ALL AGGREGATES	Terrain	: Flat to Rolling
Quantity :	1,000.00	Unit	: cu.m.
		Hauling Distance	: 5.00 km.
		Effective Working Hours	: 8.00 hrs.

Hauling: Using 10.00 cu.m.capacity Dumptruck

Weight of Dumptruck (cap. 10.00 cu.m.)	:	16,000.00	kgs.
Unit weight of Fine Aggregates	:	1,640.00	kg/m3
Unit weight of Coarse Aggregates	:	1,534.00	kg/m3
Maximum Volume to be Carried per DT	:	11.57	cu.m.

*Dumptruck (10 Wheeler) days computation : TIME-MOTION ANALYSIS

Speed when loaded	:	30.00	kph
Speed when unloaded	:	40.00	kph
Loaded running	=	$\frac{5.00 \times 60}{30.00}$	= 10.00 mins.
Unloaded running	=	$\frac{5.00 \times 60}{40.00}$	= 7.50 mins.
Loading and Unloading	:	5.00	mins.
Capacity of Dumptruck	:	10.00	cu.m.
Total Cycle time	:	22.50	mins.
No. of trips for Dumptruck per day	=	$\frac{8 \times 60.00}{22.50}$	= 21.33 say 21.33 trips
Dumptruck daily output	=	10 x 21.33	= 213.33 cu.m.
Using (4) Dumptrucks	=	4 x 213.33	= 853.33 cu.m.

1. No. of days for Dumptrucks	=	$\frac{1,000.00}{853.33}$	= 1.17 say 1.17 days
-------------------------------	---	---------------------------	----------------------

EQUIPMENT USED : (2009 ACEL RATES)

4	- Unit Dumptruck	@ P	11,360.00 /day	x	1.17 days = P	53,250.00
					Sub - Total	P 53,250.00

Estimated Quantity		1,000.00 cu.m.
Unit Cost	P	10.65 / cu. m./km. (Unit Cost, Hauling per cu.m.per km.)
Grand Total	P	53,250.00
Equipment	P	53,250.00
Labor	P	
Materials	P	

ZAMBOANGA DEL NORTE 2nd DEO

	Ave. Hauling Distance	Unit Cost per cu.m./km.	Hauling Cost per cu.m.	Unit Pirce	Unit Cost per cu.m.
Cost of Fine Aggregates:	10.00 x	10.65 =	106.50 +	850.00 =	956.50
Cost of Coarse Aggregates:	10.00 x	10.65 =	106.50 +	850.00 =	956.50
Cost of Item 200 Materials:	10.00 x	10.65 =	106.50 +	618.00 =	724.50
Cost of Item 201 Materials:	10.00 x	10.65 =	106.50 +	663.00 =	769.50
Cost of Item 300 Materials:	10.00 x	10.65 =	106.50 +	755.00 =	861.50
Cost of Boulders:	10.00 x	10.65 =	106.50 +	1,100.00 =	1,206.50
Cost of Embankmen, Common Borrow:	10.00 x	10.65 =	106.50 +	270.00 =	376.50
Cost of Embankmen, Selected Borrow:	10.00 x	10.65 =	106.50 +	350.00 =	456.50

UNIT COST DERIVATION FOR PORTLAND CEMENT

TOTAL QUANTITY REQUIREMENTS FOR PORTLAND CEMENT

DESCRIPTION	QUANTITY (Bags)
Portland Cement Concrete Pavement, 0.28 m. thick	13.60
Reinforced Concrete Culvert Pipe, 910 mm. (36") diameter	0.00
Structural Concrete, f'c" = 27.58 MPA	5,203.00
Elastomeric Bearing Pad	0.00
Grouted Riprap, Class "A"	1,224.00
Construction of Field Office for the Engineer	220.00
RCCP, 610 mm dia.	14.00
Catch Basin	4.00
Concrete Cover	1.00
Concrete Curb & Gutter	157.38
Sidewalk	231.80
Informatory Signs	1.00
T O T A L	7,069.78

Quantity = 7,069.78 Bags

Delivery Charge = P 0.120 / bag / km.

S I T E	HAULING DISTANCE
Zamboanga DEL Norte 2nd DEO	90.00
PROJECT SITE	

*Average hauling distance from Source to assumed Stockpiling area :
say 90.00 km.

Delivery Charge = P 0.120 x 90.00
= P 10.80 / bag

*Delivery Truck : 7,069.78 bags., (hauling works)
20,000.00 kgs., (capacity per haul)
or 500.00 bags, (capacity per haul)

*Capacity of Laborers unloading bags of Cement from Delivery Truck :

Assume (10) laborers can unload 500.00 bags of Cement.

*Dumptruck (10 Wheeler) days computation : TIME-MOTION ANALYSIS

Speed when loaded : 30.00 kph
Speed when unloaded : 40.00 kph
Loaded running = $\frac{90.00 \times 60}{30.00}$ = 180.00 mins.

Unloaded running = $\frac{90.00 \times 60}{40.00} = 135.00$ mins.

Loading and Unloading : 45.00 mins.

Capacity of Dumptruck : 8.00 cu.m.

: 500.00 bags

Total Cycle time : 360.00 mins.

No. of trips for Dumptruck per day = $\frac{8.0 \times 60.00}{360.00} = 1.33$ say 1.33 trip

Dumptruck daily output = $500 \times 1.33 = 666.67$ cu.m.

Using (4) Dumptrucks = $4 \times 666.67 = 2,666.67$ cu.m.

1. No. of days for Delivery Truck = $\frac{7,069.78}{2,666.67} = 2.65$ say 0.00 days

2. No. of days for Labor, for unloading = complimentary to D. Truck days = 0.00 days

DELIVERY COST :

7,069.78	- Bags, Portland Cement	@ P	10.80	/ bag	= P	76,353.62
				Sub - Total	P	76,353.62

LABOR :

1	- Foreman	@ P	611.92 /day	x	0.00 days	= P	0.00
10	- Laborers. unloading	@ P	342.24 /day	x	0.00 days	= P	0.00
				Sub - Total	P		0.00

MATERIALS :

7,069.78	- Bags, Portland Cement	@ P	283.00	/ bag	= P	2,000,747.74
	(Pick-Up Price)			Sub - Total	P	2,000,747.74

Estimated Quantity		7,069.78 Bags
Unit Cost	P	293.80 / Bag, say P 283.00 / Bag
Grand Total	P	2,077,101.36
Delivery Cost	P	76,353.62
Labor	P	0.00
Materials	P	2,000,747.74

$$\text{Unloaded running} = \frac{90.00 \times 60}{50.00} = 108.00 \text{ mins.}$$

$$\text{Loading and Unloading} : 45.00 \text{ mins.}$$

$$\text{Capacity of Cargo truck} : 8.00 \text{ cu.m.}$$

$$: 12,000.00 \text{ bags kgs.}$$

$$\text{Total Cycle time} : 288.00 \text{ mins.}$$

$$\text{No. of trips for Cargo truck per day} = \frac{8.0 \times 60.00}{288.00} = 1.67 \text{ say } 1.67 \text{ trip}$$

$$\text{Cargo truck daily output} = 12,000 \times 1.67 = 20,000.00 \text{ kgs.}$$

$$\text{Using (2) Cargo trucks} = 2 \times 12,000.00 = 24,000.00 \text{ days}$$

$$1. \text{ No. of days for Cargo Truck} = \frac{546,816.00}{24,000.00} = 22.78 \text{ say } 22.78 \text{ days}$$

$$2. \text{ No. of days for Labor, for unloading} = \text{complimentary to C Truck days} = 22.78 \text{ days}$$

Equipment:

1	- Cargo Truck	@ P	611.92 /day	x	22.78 days = P	13,941.99
2	- Crawler Crane	@ P	9,696.00 /day	x	22.78 days = P	441,827.33
Sub - Total						P 455,769.31

LABOR :

1	- Foreman	@ P	611.92 /day	x	22.78 days = P	13,941.99
2	- Laborers, unloading	@ P	342.24 /day	x	22.78 days = P	15,595.19
Sub - Total						P 29,537.18

MATERIALS :

546,816.00	-kgs ,Steel Bars	@ P	66.00 / kg	= P	36,089,856.00
(Pick-Up Price)					
Sub - Total					P 36,089,856.00

Estimated Quantity	546,816.00 kgs.
Unit Cost	P 66.89 /kgs., say P 66.89 / kg
Grand Total	P 36,575,162.49
Equipment	P 455,769.31
Labor	P 29,537.18
Materials	P 36,089,856.00

$$\text{Unloaded running} = \frac{90.00 \times 60}{50.00} = 108.00 \text{ mins.}$$

$$\text{Loading and Unloading} : 45.00 \text{ mins.}$$

$$\text{Capacity of Cargotruck} : 8.00 \text{ cu.m.}$$

$$: 12,000.00 \text{ bags kgs.}$$

$$\text{Total Cycle time} : 288.00 \text{ mins.}$$

$$\text{No. of trips for Cargotruck per day} = \frac{8.0 \times 60.00}{288.00} = 1.67 \text{ say } 1.67 \text{ trip}$$

$$\text{Cargo truck daily output} = 12,000 \times 1.67 = 20,000.00 \text{ kgs.}$$

$$\text{Using (2) Cargo trucks} = 2 \times 12000.00 = 24,000.00 \text{ days}$$

$$1. \text{ No. of days for Cargo Truck} = \frac{9,742.00}{24,000.00} = 0.41 \text{ say } 0.41 \text{ days}$$

$$2. \text{ No. of days for Labor, for unloading} = \text{complimentary to C Truck days} = 0.41 \text{ days}$$

Equipment:

1 - Cargo Truck	@ P	611.92 /day	x	0.41 days = P	248.39
2 - Crawler Crane	@ P	9,696.00 /day	x	0.41 days = P	7,871.54
Sub - Total					8,119.92

LABOR :

1 - Foreman	@ P	611.92 /day	x	0.41 days = P	248.39
2 - Laborers, unloading	@ P	342.24 /day	x	0.41 days = P	277.84
Sub - Total					526.23

MATERIALS :

9,742.00 -kgs ,Steel Bars	@ P	40.00 / kg	= P	389,680.00
---------------------------	-----	------------	-----	------------

(Pick-Up Price)

$$\text{Sub - Total} = \text{P } 389,680.00$$

Estimated Quantity

Unit Cost	P	40.89 /kgs.,	say P	40.89 / kg
Grand Total	P	398,326.15		
Equipment	P	8,119.92		
Labor	P	526.23		
Materials	P	389,680.00		

TOTAL QUANTITY REQUIREMENTS FOR Grade 60

DESCRIPTION	QUANTITY (Bags)
Reinforcing Steel Bars Grade 60	8,493.00
TOTAL	8,493.00

Delivery Charge = P 0.120 / bag / km.

S I T E	HAULING DISTANCE
Zamboanga DEL Norte 2nd DEO	90.00
PROJECT SITE	

say 90.00 km.

*Crawler Crane (45T) or loading and unloading (Complimentary to Cargo truck

*Capacity of Laborers unloading bags of Cement from Delivery Truck :

Assume (10) laborers can unload
(Compli bags of Cement.

*Dumprtruck (10 Wheeler) days computation : **TIME-MOTION ANALYSIS**

Speed when loaded	:	40.00	kph
-------------------	---	-------	-----

Speed when unloaded : 50.00 kph

$$\text{Loaded running} = \frac{90.00 \times 60}{40.00} = 135.00 \text{ mins.}$$

$$\text{Unloaded running} = \frac{90.00 \times 60}{50.00} = 108.00 \text{ mins.}$$

$$\text{Loading and Unloading} : 45.00 \text{ mins.}$$

$$\text{Capacity of Cargo truck} : 8.00 \text{ cu.m.}$$

$$: 12,000.00 \text{ bags kgs.}$$

$$\text{Total Cycle time} : 288.00 \text{ mins.}$$

$$\text{No. of trips for Cargo truck per day} = \frac{8.0 \times 60.00}{288.00} = 1.67 \text{ say } 1.67 \text{ trip}$$

$$\text{Cargo truck daily output} = 12,000 \times 1.67 = 20,000.00 \text{ kgs.}$$

$$\text{Using (2) Cargo trucks} = 2 \times 12,000.00 = 24,000.00 \text{ days}$$

$$1. \text{ No. of days for Cargo Truck} = \frac{8,493.00}{24,000.00} = 0.35 \text{ say } 0.35 \text{ days}$$

$$2. \text{ No. of days for Labor, for unloading} = \text{complimentary to C Truck days} = 0.35 \text{ days}$$

Equipment:

1 - Cargo Truck	@ P	611.92 /day	x	0.35 days = P	216.54
2 - Crawler Crane	@ P	9,696.00 /day	x	0.35 days = P	6,862.34
Sub - Total					P 7,078.89

LABOR :

1 - Foreman	@ P	611.92 /day	x	0.35 days = P	216.54
2 - Laborers, unloading	@ P	342.24 /day	x	0.35 days = P	242.22
Sub - Total					P 458.76

MATERIALS :


8,493.00 -kgs .Steel Bars	@ P	42.00 / kg	= P	356,706.00
(Pick-Up Price)				
Sub - Total			P	356,706.00

Estimated Quantity 8,493.00 kgs.

Unit Cost	P	42.89 /kgs.,	say P	42.89 / kg
Grand Total	P	364,243.65		
Equipment	P	7,078.89		
Labor	P	458.76		
Materials	P	356,706.00		



CERTUSO Structural Specialists
303 Lee Business Corner, Juan Luna St., Davao City, Philippines
Fax: +6382-2210577, Phone: +6382-2275215
Email: info@certuso.com.ph



March 20 2018

FORMAL QUOTATION

RD JORGE U. SEBASTIAN JR.
Regional Director - DPWH Region 9 Office
Tetuan, Zamboanga City

CC: DPWH Design and Planning Division
DPWH Region 9 Office
Tetuan, Zamboanga City

Subject : Steel Sheet Pile Quotation

Dear Sir Jorge,

I am pleased to offer you my best price below items, subject to our standard terms and conditions of sale, as follows:

Description	Unit Price	Price per kg	Qty	Total Amount	REMARKS
HOT ROLLED Type 2 x 12m (U TYPE) 400mm x 100mm x 10.5mm x 48 kg/m x 12meters SECTION MODULUS: 874 CM3/M Steel Grade: SY 295	Php 38,016.00	Php 66.00	1000 pcs	Php 38,016,000.00	READILY AVAILABLE
HOT ROLLED Type 3 x 12m (U TYPE) 400mm x 125mm x 13mm x 60 kg/m x 12meters SECTION MODULUS: 1340 CM3/M Steel Grade: SY 295	Php 47,520.00	Php 66.00	1000 pcs	Php 47,520,000.00	READILY AVAILABLE
COLD FORMED MMU 9-4 x 12m 600mm x 355mm x 7mm x 53.4 kg/m x 12meters SECTION MODULUS: 947 CM3/M Steel Grade: Q235 B	Php 48,060.00	Php 75.00	667 pcs	Php 32,056,020.00	READILY AVAILABLE
COLD FORMED MMU 12-3 x 12m 600mm x 310mm x 9.5mm x 68.1 kg/m x 12meters SECTION MODULUS: 1240 CM3/M Steel Grade: Q235 B	Php 70,279.20	Php 75.00	667 pcs	Php 46,876,226.40	READILY AVAILABLE

PRODUCT SPECS AND STEEL GRADE:

- STEEL GRADES AVAILABLE: SY 295 / Q235B / S 355
- MILL CERTIFICATE INCLUDED

TERMS AND CONDITIONS FOR SHEET PILE:

Price above is Delivered ZAMBOANGA CITY PORT
Payment Terms – 50% DOWNPAYMENT 50% BALANCE BEFORE DELIVERY
Lead time is 14-21 days from date of confirmed order and SUBJECT TO AVAILABILITY OF VESSEL
All orders must be supported with a formal Purchase Order
Offer is valid within 15 days from date above
All other terms and conditions to be mutually agreed prior to confirmation of order.

Thank you and we look forward to receiving your valued order soon.

Very truly yours,

CERTUSO Structural Specialists

JAY LANCE KERWIN L. CINCO
Sales Manager



109.6/m-924
03.22.6557



Davao Golden Hardware, Inc.

Goldcrest Building, Km. 3, MacArthur Highway, Malina, 8000 Davao City
Phone: (+63 82) 298-5849 / 298-5850 / 296-0878
Fax: (+63 82) 297-7700 Email: davgol168@yahoo.com

SALES QUOTATION

March 20, 2018

RD JORGE U. SEBASTIAN JR.
Regional Director - DPWH Region 9 Office
Tetuan, Zamboanga City

CC: DPWH Design and Planning Division
DPWH Region 9 Office
Tetuan, Zamboanga City

Subject : Steel Sheet Pile Quotation

Dear RD Jorge,

Please see our offer for steel sheet piles:

Description	Unit Price
STEEL SHEET PILES 400mm x 100mm x 10.5mm x 48 kg/m x 12meters SECTION MODULUS: 874 CM3/M	Php 38,432.00
STEEL SHEET PILES 400mm x 125mm x 13mm x 60 kg/m x 12meters SECTION MODULUS: 1340 CM3/M	Php 47,860.00
STEEL SHEET PILES 600mm x 355mm x 7mm x 53.4 kg/m x 12meters SECTION MODULUS: 947 CM3/M	Php 48,164.40
STEEL SHEET PILES 600mm x 310mm x 9.5mm x 68.1 kg/m x 12meters SECTION MODULUS: 1240 CM3/M	Php 70,280.20

TERMS AND CONDITION:

- Vat inclusive and Cash before delivery
- Delivered Zamboanga City Port
- Subject to change without prior notice
- Subject to availability
- Price validity 7 days

Thank you.

Very truly yours,


ARTURCIA. YUTIG, JR.
Sales Manager