

Department of Public Works and Highways

Bureau : DPWH
Region : IX
District/City : Zamboanga City

PROGRAM OF WORK

(For all types of Project)

NAME/LOCATION OF PROJECT :		Appropriation : P 108,760,000.00
Paving of Unpaved Roads - Secondary Roads Rizal - Dakak - Dapitan Coastal Loop Road		Source of Funds : CY-2018
PROJECT CATEGORY :		Issued Obligated Authority :
NATIONAL ROAD		Released :
PROJECT DESCRIPTION :		Cal. Days to Complete : 207.00 Cal. Days
Scope of Work : Paving of Unpaved Road		Desirable Starting Date : Upon Approval
Road Width : 6.70 m.		Mode of Implementation :
Roadbed Width : 12.00 m.		
Subbase Course : 0.30 mtrs thick		
Surface Course : 0.15 mtrs thick		
NET LENGTH :		Net Length : 6.49 lane km
K1849+601.00 - K1852+010.19		Net Length : 3,243.00 In.m. / 3.243 km
K1854+026.00 - K1854+860.00		

MINIMUM EQUIPMENT REQUIREMENT :

DESCRIPTION	NO.	DESCRIPTION	NO.	DESCRIPTION	NO.
Dumptruck (10 Wheeler)	10	Water Pump	1	Project Engineer	1
Bulldozer	2	Portable Screed	1	Materials Engineer	1
Backhoe	3	Concrete Vibrator	2	Geometric Control	1
Road Grader	2	Concrete Cutter	2	Foreman	1
Road Roller	2	Bar Cutter	1	Materials Lab. Tech	1
Pay Loader	4	Bar Bender	1	Mason	10
Water Truck	2	Conc. Mixer (1-Bagger)	2	Carpenter	6
Water Tank	2	Plate Compactor	1	Laborers (Skilled)	10
Transit Mixer	4			Laborers (Unskilled)	20

TECHNICAL PERSONNEL REQUIRED :

ESTIMATED COST OF PROPOSED WORK

ITEM NO.	DESCRIPTION	% OF TOTAL	UNIT	QUANTITY	DIRECT COST	
					TOTAL	UNIT COST
100(3)a2	Individual Removal of Trees	0.001	each	1.00	957.66	957.66
100(3)a3	Individual Removal of Trees	0.002	each	2.00	1,915.31	957.66
100(4)	Individual Removal of Trees	0.001	each	1.00	957.66	957.66
101(3b2)	Removal of Existing PCCP	0.379	sq.m	2,644.00	320,720.51	121.30
101(4)a1	Removal of Existing RCPC	0.017	In.m	40.00	14,720.00	368.00
101(2)b	Removal of Existing Headwall	0.003	each	8.00	2,894.05	361.76
102(2)	Surplus Common Excavation	9.894	cu.m.	25,923.50	8,363,929.96	322.64
102(3)a	Surplus Rock Excavation	4.868	cu.m.	5,030.50	4,115,540.68	818.12
103 (1)a	Structure Excavation	0.194	cu.m.	711.50	163,727.28	230.12
103(3)	Foundation Fill	0.020	cu.m.	16.50	16,627.02	1,007.70
103(6)a	Pipe Culvert and Drain Excavation	0.030	cu.m.	111.50	25,657.89	230.12
104(1)a1	Embankment from Roadway Excavation	3.603	cu.m.	13,151.00	3,045,564.21	231.58
105 (1)a	Subgrade Preparation	0.429	sq.m.	23,648.00	362,567.19	15.33
200 (1)	Aggregate Subbase Course	22.006	cu.m.	12,837.00	18,602,302.09	1,449.12
300 (1)	Aggregate Surface Course	1.587	cu.m.	889.50	1,341,353.55	1,507.99
311(1)e1a	Portland Cement Concrete Pavement-Using Conventional Method, 0.28m thick	43.671	sq.m.	23,315.50	36,917,034.40	1,583.37
311(1)a	Portland Cement Concrete Pavement, 0.15m. Thick	4.726	sq.m	4,592.00	3,995,140.16	870.02
404 (1)a	Reinforcing Steel Bar, Grade 40	0.849	kg.	14,445.00	717,326.26	49.66
405 (1) a3	Structural Concrete, Class A	3.145	cu.m	357.00	2,658,412.24	7,446.53

500(1)b3	Pipe Culvert & Storm Drain	0.577	ln.m	123.00	487,994.21	3,967.43
505(2)a	Grouted Riprap, Class A	0.139	cu.m	28.50	117,772.14	4,132.36
506(1)	Stone Masonry	0.505	cu.m	101.00	427,154.22	4,229.25
612(1)	ReflectORIZED Thermoplastic Pavement Markings (White)	0.669	sq.m	775.50	565,195.49	728.81
612(2)	ReflectORIZED Thermoplastic Pavement Markings (Yellow)	0.202	sq.m	211.50	171,074.11	808.86
A.1.1(3)	Const. of Field Office for the Engineer	0.474	LS	1.00	401,083.78	401,083.78
A.1.1(11)	Prov. Of Furniture, Equipment and Appliances for Field Engineer	0.290	LS	1.00	244,863.32	244,863.32
A.1.2(5)	Operation & Maintenance of Gov't. Service Vehicle	0.385	L.S	1.00	325,128.00	325,128.00
B.5	Project Billboard	0.005	Unit	2.00	4,312.90	2,156.45
B.7	Occupational Safety & Health Program	0.198	L.S	1.00	167,436.12	167,436.12
B.9	Mobilization and Demobilization	0.985	L.S	1.00	832,248.00	832,248.00
B.4(1)	Construction Survey and Staking	0.145	Km.	3.24	122,623.11	37,811.63
TOTAL		100.000			P 84,534,233.51	

Name of Project


: Paving of Unpaved Roads - Secondary Roads Rizal - Dakak - Dapitan Coastal Loop Road

Station Limits


: K1849+601.00 - K1852+010.19
K1854+026.00 - K1854+860.00

BREAKDOWN OF ESTIMATED EXPENDITURES	% OF TOTAL	AMOUNT
I. ESTIMATED COST		
A. DIRECT COST		
A.1 Materials	55.25	60,085,287.25
A.2 Labor	1.60	1,744,003.89
A.3 Equipment Expenses	20.88	22,704,942.37
SUB-TOTAL (DIRECT COST)	77.73	84,534,233.51
B. INDIRECT COST (Per DO # 197 s. 2016)		
B.1 Overhead, Contingency & Misc. (10% Max. of D.C.)	7.63	8,296,455.81
B.2 Profit (8% Max. D.C.)	6.11	6,650,559.54
C. VAT (5% of D.C. and I.C. per D.O. # 197)	4.57	4,974,062.44
SUB-TOTAL (CONTRACT COST)	96.04	104,455,311.30
II. ESTIMATED GOVERNMENT EXPENDITURES		
1 Engineering and Administrative Overhead (3.5%)	3.50	3,806,600.00
2 Detailed Engineering (1%)	0.46	498,088.70
3 Reserved for the Payment of RROW)	0.00	
4 Physical Reserved		
TOTAL ESTIMATED PROJECT COST	100.00	108,760,000.00

Prepared by:


JERALD R. BARRERA
Engineer II


Submitted by:


LEONCIO B. SOLAMILLO
Chief, Construction Division

Recommending Approval:


CAYAMOMBAO D. DIA
Assistant Regional Director

APPROVED:


JORGE U. SEBASTIAN, JR., CESO III
Regional Director

APPROVED

ET FOR THE CONTRACT

Project Name and Location	Project Description	Project Status	Project Manager	Project Sponsor	Project Budget	Project Timeline	Project Risks	Project Deliverables	Project Metrics	Project Communication	Project Documentation	Project Reporting	Project Review	Project Closure
Project A: New Product Development	Develop a new product line for the company.	In Progress	John Doe	Jane Smith	\$1,000,000	12 months	High	Product A, Product B, Product C	Customer Satisfaction, Sales Volume	Weekly Meetings, Email Updates	Project Charter, Requirements Document	Monthly Reports, Quarterly Reviews	Post-Launch Review	Project Completion
Project B: Marketing Campaign	Launch a new marketing campaign for the company.	Completed	Jane Smith	John Doe	\$500,000	6 months	Medium	Campaign A, Campaign B, Campaign C	Brand Awareness, Lead Generation	Daily Meetings, Weekly Updates	Campaign Plan, Creative Brief	Weekly Reports, Monthly Reviews	Post-Campaign Review	Project Completion
Project C: IT System Upgrade	Upgrade the company's IT system.	On Hold	John Doe	Jane Smith	\$2,000,000	18 months	High	System A, System B, System C	System Uptime, User Satisfaction	Weekly Meetings, Monthly Updates	System Requirements, Implementation Plan	Monthly Reports, Quarterly Reviews	Post-Upgrade Review	Project Completion
Project D: Customer Service Improvement	Improve the company's customer service.	In Progress	Jane Smith	John Doe	\$750,000	9 months	Medium	Service A, Service B, Service C	Customer Satisfaction, Service Quality	Daily Meetings, Weekly Updates	Service Plan, Training Manual	Weekly Reports, Monthly Reviews	Post-Improvement Review	Project Completion
Project E: HR Policy Update	Update the company's HR policies.	Completed	John Doe	Jane Smith	\$250,000	3 months	Low	Policy A, Policy B, Policy C	Employee Satisfaction, Policy Compliance	Weekly Meetings, Monthly Updates	Policy Draft, Final Review	Monthly Reports, Quarterly Reviews	Post-Update Review	Project Completion

Station limits : K1849+601.00 - K1852+010.19
K1854+026.00 - K1854+860.00

Length	: 3,243.00	in.m.
--------	------------	-------

Item No.	Description	Quantity	Unit	Estimated Direct Cost	MARK-UP IN PERCENT	% PROFIT	VALUE	VAT	TOTAL INDIRECT COST	TOTAL COST	TOTAL COST	
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9) = ((5)+(7))*5%	(10) = ((5)+(9))*5%	(11) = (9) + (10)	(12) = (5) + (11)	(13) = (12) / (3)
PART A FACILITIES FOR THE ENGINEER												
A.1.(1)	Const. of Field Office for the Engineer	1.00	LS	401,083.78	10.00	8.00	18.00	72,195.08	23,663.94	95,859.02	496,942.80	
A.1.(1.1)	Prov. Of Furniture, Equipment and Appliances for Field Engineer	1.00	LS	244,863.32	0.00	0.00	0.00	-	12,243.17	257,106.49		
A.1.2(5)	Operation & Maintenance of Gov't Service Vehicle	1.00	L.S	325,128.00	0.00	0.00	0.00	-	16,256.40	341,384.40		
PART B OTHER GENERAL REQUIREMENTS												
B.5	Project Billboard	2.00	Unit	4,329.00	10.00	8.00	18.00	776.32	52,146.51	124,358.59		
B.7	Occupational Safety & Health Program	1.00	L.S	167,436.12	0.00	8.00	13,394.89	9,041.55	1,030.76	5,343.68		
B.9	Mobilization and Demobilization	1.00	L.S	832,248.00	0.00	0.00	0.00	-	41,612.40	873,860.40		
B.4(1)	Construction Survey and Staking	3.24	Km.	1,126,620.13	10.00	8.00	18.00	22,072.17	7,237.76	151,300.03	46,848.61	
PART C EARTHWORKS												
100(3)2	Individual Removal of Trees	1.00	each	957.66	10.00	8.00	18.00	172.38	56.50	1,186.54		
100(3)3	Individual Removal of Trees	2.00	each	1,915.31	10.00	8.00	18.00	344.76	113.00	2,373.07		
100(4)	Individual Removal of Trees	1.00	each	957.66	10.00	8.00	18.00	172.38	56.50	1,186.54		
101(3b2)	Removal of Existing PCFP	2,644.00	sq.m	320,720.51	10.00	8.00	18.00	57,729.69	18,922.51	76,652.20		
101(4)	Removal of Existing RCP	40.00	ln.m	14,720.00	10.00	8.00	18.00	2,649.40	868.48	18,238.08		
101(2)b	Removal of Existing Headwall	8.00	each	2,894.05	10.00	8.00	18.00	520.93	170.75	3,585.73		
102(2)	Surplus Common Excavation	25,923.50	cu.m.	8,363,929.96	10.00	8.00	18.00	1,505,507.39	493,471.87	1,998,979.26		
102(3)a	Surplus Rock Excavation	5,030.50	cu.m.	4,115,540.68	10.00	8.00	18.00	740,797.32	242,816.90	983,614.91		
103(1)a	Structure Excavation	711.50	cu.m.	163,727.28	10.00	8.00	18.00	29,470.91	9,659.91	39,130.82		
103(3)	Foundation Fill	16.50	cu.m.	16,627.02	10.00	8.00	18.00	2,992.66	980.99	3,973.86		
104(1)a	Pipe Culvert and Drain Excavation	111.50	cu.m.	25,657.89	10.00	8.00	18.00	4,618.42	6,132.24	31,790.13		
104(1)2	Subgrade Preparation	23,648.00	sq.m.	362,567.19	10.00	8.00	18.00	65,262.10	21,391.46	86,653.56		
TOTAL OF PART C												
200 (1)	Aggregate Subbase Course	12,837.00	cu.m.	18,602,302.09	10.00	8.00	18.00	3,348,414.38	1,097,535.82	4,445,950.20		
300 (1)	Aggregate Surface Course	889.50	cu.m.	1,341,353.55	10.00	8.00	18.00	241,443.64	79,139.86	320,583.50		
311(1)a1a	Portland Cement Concrete Pavement-using Conventional Method, 0.28m thick	23,315.50	sq.m.	36,917,034.40	10.00	8.00	18.00	6,645,064.19	2,178,105.03	8,823,171.22		
311(1)a	Portland Cement Concrete Pavement, 0.15m, Thick	4,592.00	sq.m.	3,995,140.16	10.00	8.00	18.00	719,125.23	235,713.27	954,838.50		
TOTAL OF PART E												
404 (1)a	Reinforcing Steel Bar, Grade 40	14,445.00	kg.	717,326.26	10.00	8.00	18.00	129,118.73	42,322.25	171,440.98		
405 (1) a3	Structural Concrete, Class A	357.00	cu.m.	2,658,412.24	10.00	8.00	18.00	478,514.20	156,846.32	635,360.53		
TOTAL OF PART F												
				3,376,5738.50			607,632.93	199,168.67	806,801.50			
				42,253,528.11			7,605,635.06	2,492,958.16	10,098,593.22			
										</		

Prepared by:

BELEN A. SAPALBA

CAYAMOMBAO D. DIA
Assistant Regional Director

APPROVED:

JOSEPH U. SEBASTIAN, JR., CEO III
Regional Director

Paving of Unpaved Roads - Secondary Roads Rizal - Dakak - Dapitan Coastal Loop Road

Project Name and Location

Station Limits : K1849+601.00 - K1852+010.19 K1854+026.00 - K1854+860.00
Length : 3,243.00 In.m.

Contract Duration : 207.00 Calendar Days

Item No.	Description	Quantity	Unit	Estimated Direct Cost	MARK-UP IN PERCENT		TOTAL MARK-UPS		VAT	TOTAL INDIRECT COST	TOTAL COST	TOTAL COST
					OCM	PROFIT	%	VALUE				
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)	(9) = (5)X(8)	(10) = [(5)+(9)]*5%	(11) = (9) + (10)	(12) = (5) + (11)	(13) = (12) / (3)
PART A	FACILITIES FOR THE ENGINEER				10.00	8.00	18.00					
A.1.1(3)	Const. of Field Office for the Engineer	1.00	LS	401,083.78	10.00	8.00	18.00	72,195.08	23,663.94	95,859.02	496,942.80	496,942.80
A.1.1(11)	Prov. Of Furniture, Equipment and Appliances for Field Engineer	1.00	LS	244,863.32	0.00	0.00	0.00	-	12,243.17	12,243.17	257,106.49	257,106.49
A.1.2(5)	Operation & Maintenance of Gov't. Service Vehicle	1.00	L.S	325,128.00	0.00	0.00	0.00	-	16,256.40	16,256.40	341,384.40	341,384.40
	TOTAL OF PART A			971,075.10				72,195.08	52,163.61	124,358.59	1,095,433.69	
PART B	OTHER GENERAL REQUIREMENTS											
B.5	Project Billboard	2.00	Unit	4,312.90	10.00	8.00	18.00	776.32	254.46	1,030.78	5,343.68	2,671.84
B.7	Occupational Safety & Health Program	1.00	LS	167,436.12	0.00	8.00	8.00	13,394.89	9,041.55	22,436.44	189,872.56	189,872.56
B.9	Mobilization and Demobilization	1.00	L.S	832,248.00	0.00	0.00	0.00	-	41,612.40	41,612.40	873,860.40	873,860.40
B.4(1)	Construction Survey and Staking	3.24	Km.	122,623.11	10.00	8.00	18.00	22,072.16	7,234.76	29,306.92	151,930.03	46,848.61
	TOTAL OF PART B			1,126,620.13				36,243.37	58,143.17	94,386.55	1,221,006.67	
PART C	EARTHWORKS											
100(3)a2	Individual Removal of Trees	1.00	each	957.66	10.00	8.00	18.00	172.38	56.50	228.88	1,186.54	1,186.54
100(3)a3	Individual Removal of Trees	2.00	each	1,915.31	10.00	8.00	18.00	344.76	113.00	457.76	2,373.07	1,186.54
100(4)	Individual Removal of Trees	1.00	each	957.66	10.00	8.00	18.00	172.38	56.50	228.88	1,186.54	1,186.54
101(3b2)	Removal of Existing PCCP	2,644.00	sq.m	320,720.51	10.00	8.00	18.00	57,729.69	18,922.51	76,652.20	397,372.71	150.29
101(4)a1	Removal of Existing RCPC	40.00	In.m	14,720.00	10.00	8.00	18.00	2,649.60	868.48	3,518.08	18,238.08	455.95
101(2)b	Removal of Existing Headwall	8.00	each	2,894.05	10.00	8.00	18.00	520.93	170.75	691.68	3,585.73	448.22
102(2)	Surplus Common Excavation	25,923.50	cu.m.	8,363,929.96	10.00	8.00	18.00	1,505,507.39	493,471.87	1,998,979.26	10,362,909.22	399.75
102(3)a	Surplus Rock Excavation	5,030.50	cu.m.	4,115,540.68	10.00	8.00	18.00	740,797.32	242,816.90	983,614.22	5,099,154.91	1,013.65
103(1)a	Structure Excavation	711.50	cu.m.	163,727.28	10.00	8.00	18.00	29,470.91	9,659.91	39,130.82	202,858.11	285.11
103(3)	Foundation Fill	16.50	cu.m.	16,627.02	10.00	8.00	18.00	2,992.86	980.99	3,973.86	20,600.87	1,248.54
103(6)a	Pipe Culvert and Drain Excavation	111.50	cu.m.	25,657.89	10.00	8.00	18.00	4,618.42	1,513.82	6,132.24	31,790.13	285.11
104(1)a1	Embankment from Roadway Excavation	13,151.00	cu.m.	3,045,564.21	10.00	8.00	18.00	548,201.56	179,688.29	727,889.85	3,773,454.05	286.93
105(1)a	Subgrade Preparation	23,648.00	sq.m.	362,567.19	10.00	8.00	18.00	65,262.10	21,391.46	86,653.56	449,220.75	19.00
	TOTAL OF PART C			16,435,779.42				2,958,440.30	969,710.99	3,928,151.28	20,363,930.71	
PART D	SUBBASE AND BASE COURSE											
200(1)	Aggregate Subbase Course	12,837.00	cu.m.	18,602,302.09	10.00	8.00	18.00	3,348,414.38	1,097,535.82	4,445,950.20	23,048,252.29	1,795.45
	TOTAL OF PART D			18,602,302.09				3,348,414.38	1,097,535.82	4,445,950.20	23,048,252.29	
PART E	SURFACE COURSES											
300(1)	Aggregate Surface Course	889.50	cu.m.	1,341,353.55	10.00	8.00	18.00	241,443.64	79,139.86	320,583.50	1,661,937.04	1,868.39
311(1)e1a	Portland Cement Concrete Pavement-using Conventional Method, 0.28m Thick	23,315.50	sq.m.	36,917,034.40	10.00	8.00	18.00	6,645,066.19	2,178,105.03	8,823,171.22	45,740,205.62	1,961.79
311(1)a	Portland Cement Concrete Pavement, 0.15m. Thick	4,592.00	sq.m	3,995,140.16	10.00	8.00	18.00	719,125.23	235,713.27	954,838.50	4,949,978.66	1,077.96
	TOTAL OF PART E			42,253,528.11				7,405,635.06	2,492,958.16	10,098,593.22	52,352,121.33	
PART F	BRIDGE CONSTRUCTION											
404(1)a	Reinforcing Steel Bar, Grade 40	14,445.00	kg.	717,326.26	10.00	8.00	18.00	129,118.73	42,322.25	171,440.98	888,767.24	61.53
405(1) a3	Structural Concrete, Class A	357.00	cu.m	2,658,412.24	10.00	8.00	18.00	478,514.20	156,846.32	635,360.53	3,293,772.77	9,226.25
	TOTAL OF PART F			3,375,738.50				607,632.93	199,168.57	806,801.50	4,182,540.01	
PART G	DRAINAGE AND SLOPE PROTECTION STRUCTURES											
500(1)b3	Pipe Culvert & Storm Drain	123.00	In.m	487,994.21	10.00	8.00	18.00	87,838.96	28,791.66	116,630.62	604,624.83	4,915.65
505(2)a	Grouted Riprap, Class A	28.50	cu.m	117,772.14	10.00	8.00	18.00	21,198.98	6,948.56	28,147.54	145,919.68	5,119.99
506(1)	Stone Masonry	101.00	cu.m	427,154.22	10.00	8.00	18.00	76,887.76	25,202.10	102,089.86	529,244.07	5,240.04
	TOTAL OF PART G			1,032,920.56				185,925.70	60,942.31	246,868.01	1,279,788.57	
PART H	MISCELLANEOUS STRUCTURES											
612(1)	Reflectorized Thermoplastic Pavement Markings (White)	775.50	sq.m	565,195.49	10.00	8.00	18.00	101,735.19	33,346.53	135,081.72	700,277.21	903.00
612(2)	Reflectorized Thermoplastic Pavement Markings (Yellow)	211.50	sq.m	171,074.11	10.00	8.00	18.00	30,793.34	10,093.37	40,886.71	211,960.82	1,002.18
	TOTAL OF PART H			736,269.60				132,528.53	43,439.91	175,968.43	912,238.04	
	TOTAL			84,534,233.51				14,947,015.34	3,876,526.62	19,921,077.79	104,455,311.30	

Prepared by:

BELEN A. SAPALLIDA
Head TWG BAC

Recommending Approval:

CAYAMOMBAO D. DIA
Assistant Regional Director

APPROVED:

JORGE U. SEBASTIAN, JR., CESO III
Regional Director

SUMMARY

Project : Paving of Unpaved Roads - Secondary Roads Rizal - Dalkak - Dapitan Coastal Loop Road

	Description	Quantity	Unit	Labor	Equipment	Materials	OCM	Profit	VAT	TOTAL
?	Individual Removal of Trees	1.00	each	217.45	660.21	80.00	95.77	76.61	56.50	1,186.54
1	Individual Removal of Trees	2.00	each	434.90	1,320.41	160.00	191.53	153.22	113.00	2,373.07
	Individual Removal of Trees	1.00	each	217.45	660.21	80.00	95.77	76.61	56.50	1,186.54
	Removal of Existing FCCP	2,644.00	sq.m	10,711.51	310,009.00	-	32,072.05	25,657.64	18,922.51	397,372.71
	Removal of Existing RCP	40.00	ln.m	1,080.33	13,639.67	-	1,472.00	1,177.60	868.48	18,238.08
	Removal of Existing Headwall	8.00	each	140.01	2,754.04	-	289.41	231.52	170.75	3,585.73
	Surplus Common Excavation	25,923.50	cu.m	71,974.44	8,291,955.52	-	836,393.00	669,114.40	493,471.87	10,362,909.22
	Surplus Rock Excavation	5,030.50	cu.m	301,439.54	2,199,310.65	1,614,790.50	411,554.07	329,243.25	242,816.90	5,099,154.91
	Structure Excavation	711.50	cu.m	7,286.83	156,440.46	-	16,372.73	13,098.18	9,659.91	202,858.11
	Foundation Fill	16.50	cu.m	3,268.45	1,947.00	11,411.57	1,662.70	1,330.16	980.99	20,600.87
	Pipe Culvert and Drain Excavation	111.50	cu.m	1,141.93	24,515.97	-	2,565.79	2,052.63	1,513.82	31,790.13
	Embankment from Roadway Excavation	13,151.00	cu.m	77,998.98	2,967,565.23	-	304,556.42	243,645.14	179,688.29	3,773,454.05
	Subgrade Preparation	23,648.00	sq.m	12,773.86	349,793.33	-	36,256.72	29,005.38	21,391.46	449,220.75
	Aggregate Subbase Course	12,837.00	cu.m	41,604.72	1,611,043.50	16,949,653.88	1,860,230.21	1,488,184.17	1,097,535.82	23,048,252.29
	Aggregate Surface Course	889.50	cu.m	2,882.87	78,943.13	1,259,527.55	134,135.35	107,308.28	79,139.86	1,661,937.04
3	Portland Cement Concrete Pavement-using Conventional Method, 0.28m thick	23,315.50	sq.m	327,891.90	4,864,000.21	31,725,142.29	3,691,703.44	2,953,362.75	2,178,105.03	45,740,205.62
	Portland Cement Concrete Pavement, 0.15m. thick	4,592.00	sq.m	34,717.03	538,925.10	3,421,498.04	399,514.02	319,611.21	235,713.27	4,949,978.66
	Reinforcing Steel Bar, Grade 40	14,445.00	kg.	42,494.78	32,346.77	642,484.71	71,732.63	57,386.10	42,322.25	888,767.24
	Structural Concrete, Class A	357.00	cu.m	307,063.35	152,670.67	2,198,678.23	265,841.22	212,672.98	156,846.32	3,293,772.77
1	Pipe Culvert & Storm Drain	123.00	ln.m	44,084.43	106,498.44	337,411.34	48,799.42	39,039.54	28,791.66	604,624.83
	Grouted Riprap, Class A	28.50	cu.m	12,073.28	26,869.26	78,829.59	11,777.21	9,421.77	6,948.56	145,919.68
	Stone Masonry	101.00	cu.m	34,228.82	32,394.53	360,530.87	42,715.42	34,172.34	25,202.10	529,244.07
	Reflectorized Thermoplastic Pavement Markings (White)	775.50	sq.m	13,771.95	46,320.62	505,102.93	56,519.55	45,215.64	33,346.53	700,277.21
	Reflectorized Thermoplastic Pavement Markings (Yellow)	211.50	sq.m	3,755.99	12,632.90	154,685.23	17,107.41	13,685.93	10,093.37	211,960.82
	Const. of Field Office for the Engineer	1.00	LS	53,245.60	31,804.56	316,033.62	40,108.38	32,086.70	23,663.94	496,942.80
	Prov. Of Furniture, Equipment and Appliances for Field Engineer	1.00	LS	-	-	244,863.32	-	-	12,243.17	257,106.49
	Operation & Maintenance of Gov't. Service Vehicle	1.00	LS	91,742.40	-	233,385.60	-	-	16,256.40	341,384.40
	Project Billboard	2.00	Unit	434.90	-	3,878.00	431.29	345.03	254.46	5,343.68
	Occupational Safety & Health Program	1.00	L.S	155,076.12	-	12,360.00	-	13,394.89	9,041.55	189,872.56
	Mobilization and Demobilization	1.00	L.S	-	832,248.00	-	-	-	41,612.40	873,860.40
	Construction Survey and Staking	3.24	Km.	90,250.10	17,673.01	14,700.00	12,262.31	9,809.85	7,234.76	151,930.03
	TOTAL			1,744,003.89	22,704,942.37	60,085,287.25	8,296,455.81	6,650,559.54	4,974,062.44	104,455,311.30

: 3,243.00 In.m.

138	:	TOTAL NO. OF WORKING DAYS
46	:	INCLEMENT WEATHER & CURING TIME
23	:	NUMBER OF SUNDAYS
207	:	TOTAL NO. CALENDAR DAYS

GERALD R. BARRERA

TEONCIO B. SOLAMILLO
Chief, Construction Division

JOSEPH H. SEASHAN, JR., CEO III

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 100(3)a2 Individual Removal of Trees

Unit of Measurement : each

Output per hour : 1.00

Quantity : 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.13	611.92	76.49
b. Skilled Laborer	1	0.13	443.20	55.40
c. Laborer	2	0.13	342.24	85.56
Sub-total for A				P 217.45
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	0.03	12,296.00	384.25
b. Dumptruck	1	0.02	11,360.00	241.40
c. Chain Saw	1	0.02	602.88	12.81
Minor Tools (5% of Labor Cost)				21.75
Sub-total for B				P 660.21
Total (A+B)				P 877.66
D. Output/day 8.00 each /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Rope, 1" dia.	4.00	m	20.00	80.00
Sub-total for E				P 80.00
F. Direct Cost (C+E)				957.66
G. Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016 95.77
H. Contractor's Profit (CP)				8% per D.O 197 s 2016 76.61
I. Value Added Tax (VAT)				5% 56.50
J. Total Unit Cost				1,186.54

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description

: 100(3)a3 Individual Removal of Trees

Unit of Measurement

: each

Output per hour

: 1.00

Quantity

: 2.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.25	611.92	152.98
b. Skilled Laborer	1	0.25	443.20	110.80
c. Laborer	2	0.25	342.24	171.12
Sub-total for A				P 434.90
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	0.06	12,296.00	768.50
b. Dumptruck	1	0.04	11,360.00	482.80
c. Chain Saw	1	0.04	602.88	25.62
Minor Tools (5% of Labor Cost)				43.49
Sub-total for B				P 1,320.41
Total (A+B)				P 1,755.31
D. Output/day 8.00 each /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Rope, 1" dia.	8.00	m	20.00	160.00
Sub-total for E				P 160.00
Direct Cost (C+E)				1,915.31
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				1,186.54

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description

: 100(4) Individual Removal of Trees

Unit of Measurement

: each

Output per hour

: 1.00

Quantity

: 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.13	611.92	76.49
b. Skilled Laborer	1	0.13	443.20	55.40
c. Laborer	2	0.13	342.24	85.56
Sub-total for A				P 217.45
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	0.03	12,296.00	384.25
b. Dumptruck	1	0.02	11,360.00	241.40
c. Chain Saw	1	0.02	602.88	12.81
Minor Tools (5% of Labor Cost)				21.75
Sub-total for B				P 660.21
Total (A+B)				P 877.66
D. Output/day	8.00 each/day			
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Rope, 1" dia.	4.00	m	20.00	80.00
Sub-total for E				P 80.00
Direct Cost (C+E)				957.66
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				1,186.54

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description

: 101(3b2) Removal of Existing PCCP

Unit of Measurement

: sq.m

Output per hour

: 40.00

Quantity

: 2,644.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	8.26	611.92	5,055.99
b. Laborer	2	8.26	342.24	5,655.52
Sub-total for A				P 10,711.51
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	8.26	12,296.00	101,595.70
b. Payloader	1	8.26	13,864.00	114,551.30
c. Dumptruck	1	8.26	11,360.00	93,862.00
Sub-total for B				P 310,009.00
Total (A+B)				P 320,720.51
D. Output/day	320.00	sq.m /day		
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Sub-total for E				P 0.00
F. Direct Cost (C+E)				320,720.51
G. Overhead, Contingencies and Miscellaneous	10%	per D.O 197 s 2016		32,072.05
H. Contractor's Profit (CP)	8%	per D.O 197 s 2016		25,657.64
I. Value Added Tax (VAT)	5%			18,922.51
J. Total Unit Cost				150.29

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 101(4)a1 Removal of Existing RCPC

Unit of Measurement : In.m

Output per hour : 6.00

Quantity : 40.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.83	611.92	509.93
b. Laborer	2	0.83	342.24	570.40
Sub-total for A				P 1,080.33
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	0.83	12,296.00	10,246.67
b. Boom Truck	1	0.42	8,143.20	3,393.00
Sub-total for B				P 13,639.67
Total (A+B)				P 14,720.00
D. Output/day 48.00 In.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Sub-total for E				P 0.00
F. Direct Cost (C+E)				14,720.00
G. Overhead, Contingencies and Miscellaneous			10% per D.O 197 s 2016	1,472.00
H. Contractor's Profit (CP)			8% per D.O 197 s 2016	1,177.60
I. Value Added Tax (VAT)			5%	868.48
J. Total Unit Cost				455.95

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 101(2)b Removal of Existing Headwall

Unit of Measurement : cu.m

Output per hour : 10.00

Quantity : 8.00 each
8.64

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.11	611.92	66.09
b. Laborer	2	0.11	342.24	73.92
Sub-total for A				P 140.01
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe w/ breaker	1	0.05	15,984.80	863.18
b. Backhoe	1	0.05	12,296.00	663.98
c. Dumptruck	1	0.11	11,360.00	1,226.88
Sub-total for B				P 2,754.04
Total (A+B)				P 2,894.05
D. Output/day 80.00 cu.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Sub-total for E				P 0.00
Direct Cost (C+E)				2,894.05
G. Overhead, Contingencies and Miscellaneous	10% per D.O 197 s 2016			289.41
H. Contractor's Profit (CP)	8% per D.O 197 s 2016			231.52
I. Value Added Tax (VAT)	5% per D.O 197 s 2016			170.75
J. Total Unit Cost				448.22

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 102(2) Surplus Common Excavation

Unit of Measurement : cu.m.

Output per hour : 60.00

Quantity : 25,923.5

Use Two (2) gangs					
Designation	No. of Person	No. of Days	Daily Rate	Amount	
A. Labor					
a. Construction Foreman	1	27.00	611.92	16,524.07	
b. Laborer	6	27.00	342.24	55,450.37	
Sub-total for A				P	71,974.44
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount	
B Equipment, (2014 ACEL Rates)					
a. Bulldozer	2	27.00	27,032.00	1,459,925.11	
b. Payloader	2	27.00	13,864.00	748,757.09	
c. Payloader	2	20.25	13,864.00	561,567.82	
d. Dumptruck	18	27.00	11,360.00	5,521,705.50	
Sub-total for B				P	8,291,955.52
Total (A+B)				P	8,363,929.96
D. Output/day	960.00 cu.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount	
E. Materials					
Sub-total for E				P	0.00
Sub-total for F					
Direct Cost (C+E)					8,363,929.96
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016	836,393.00
Contractor's Profit (CP)				8% per D.O 197 s 2016	669,114.40
Value Added Tax (VAT)				5%	493,471.87
Total Unit Cost					399.75

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 102(3)a Surplus Rock Excavation

Unit of Measurement : cu.m.

Output per hour : 4.20

Quantity : 5,030.5

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
<i>Drilling</i>				
a. Construction Foreman	1	59.89	611.92	36,645.99
b. Skilled Laborer	2	59.89	443.20	53,083.75
c. Laborer	4	59.89	342.24	81,982.78
<i>Blasting</i>				
a. Construction Foreman	1	29.94	611.92	18,323.00
b. Skilled Laborer	1	29.94	443.20	13,270.94
c. Laborer	2	29.94	342.24	20,495.69
<i>Disposal</i>				
a. Construction Foreman	1	59.89	611.92	36,645.99
b. Laborer	2	59.89	342.24	40,991.39
Sub-total for A				P 301,439.54
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	29.94	15,984.80	478,640.10
b. Payloader	1	22.46	13,864.00	311,352.02
c. Payloader	1	7.49	13,864.00	103,784.01
d. Dumptruck	1	59.89	11,360.00	680,315.24
e. Pneumatic Drilling Machine	2	59.89	1,360.00	162,892.38
f. Air Compressor	1	59.89	7,720.00	462,326.90
Sub-total for B				P 2,199,310.65
Total (A+B)				P 2,500,750.18
Output/day 33.60 cu.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Dynamite	2,012.20	kg	250.00	503,050.00
b. Detonation Cord	10,061.00	m	75.00	754,575.00
c. Detonator	754.58	pc	250.00	188,643.75
d. Ammonium Sulfate	1,006.10	kg	70.00	70,427.00
e. Blasting Cap	2,012.20	pc	40.00	80,488.00
f. Safety Fuse	503.05	m	35.00	17,606.75
Sub-total for E				P 1,614,790.50
Direct Cost (C+E)				4,115,540.68
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				1,013.65

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 103 (1)a Structure Excavation

Unit of Measurement : cu.m.

Output per hour : 20.00

Quantity : 711.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	4.45	611.92	2,721.13
b. Laborers	3	4.45	342.24	4,565.70
Sub-total for A				P 7,286.83
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Dumptruck	2	4.45	11,360.00	101,033.00
b. Backhoe	1	4.45	12,296.00	54,678.78
Minor Tools (10% of Labor)				728.68
Sub-total for B				P 156,440.46
Total (A+B)				P 163,727.28
D. Output/day	160.00 cu.m /day			
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Sub-total for E				P 0.00
Sub-total for E				163,727.28
Direct Cost (C+E)				
G. Overhead, Contingencies and Miscellaneous	10% per D.O 197 s 2016			16,372.73
H. Contractor's Profit (CP)	8% per D.O 197 s 2016			13,098.18
I. Value Added Tax (VAT)	5%			9,659.91
Total Unit Cost				285.11

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 103(3) Foundation Fill

Unit of Measurement : cu.m.

Output per hour : 1.25

Quantity : 16.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	1.65	611.92	1,009.67
b. Laborer	4	1.65	342.24	2,258.78
Sub-total for A				P 3,268.45
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Plate Compactor	1	1.65	984.00	1,623.60
b. Water Truck	1	0.02	19,600.00	323.40
c. Minor Tools (10% of Labor)				
Sub-total for B				P 1,947.00
Total (A+B)				P 5,215.45
D. Output/day 10.00 cu.m. /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Filling Materials	18.98	cu.m.	601.40	11,411.57
Sub-total for E				P 11,411.57
Direct Cost (C+E)				16,627.02
G. Overhead, Contingencies and Miscellaneous	10% per D.O 197 s 2016			1,662.70
H. Contractor's Profit (CP)	8% per D.O 197 s 2016			1,330.16
I. Value Added Tax (VAT)	5%			980.99
J. Total Unit Cost				1,248.54

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 103(6)a Pipe Culvert and Drain Excavation

Unit of Measurement : cu.m.

Output per hour : 20.00

Quantity : 111.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.70	611.92	426.43
b. Laborer	3	0.70	342.24	715.50
Sub-total for A				P 1,141.93
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Dumptruck	2	0.70	11,360.00	15,833.00
b. Backhoe	1	0.70	12,296.00	8,568.78
Minor Tools (10% of Labor)				114.19
Sub-total for B				P 24,515.97
Total (A+B)				P 25,657.89
D. Output/day 160.00 cu.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a.				
Sub-total for E				P 0.00
Direct Cost (C+E)				25,657.89
Overhead, Contingencies and Miscellaneous			10% per D.O 197 s 2016	2,565.79
Contractor's Profit (CP)			8% per D.O 197 s 2016	2,052.63
Value Added Tax (VAT)			5%	1,513.82
Total Unit Cost				285.11

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 104(1)a1 Embankment from Roadway Excavation

Unit of Measurement : cu.m.

Output per hour : 50.00

Quantity : 13,151.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
For Excavation Work				
a. Construction Foreman	1	27.29	611.92	16,698.27
b. Laborer	2	27.29	342.24	18,678.31
Spreading & Compaction				
a. Construction Foreman	1	32.88	611.92	20,118.40
b. Laborer	2	32.88	342.24	22,503.99
Sub-total for A				P 77,998.98
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
For Excavation Work				
a. Bulldozer	1	27.29	27,032.00	737,658.00
b. Payloader	1	27.29	13,864.00	378,325.34
c. Dumptruck	2	27.29	11,360.00	619,990.74
Spreading and Compaction				
a. Road Grader	1	32.88	17,384.00	571,542.46
b. Road Roller	1	32.88	13,216.00	434,509.04
c. Water Truck	1	11.51	19,600.00	225,539.65
Sub-total for B				P 2,967,565.23
Total (A+B)				P 3,045,564.21
D. Output/day 400.00 cu.m. /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Sub-total for E				P 0.00
F. Direct Cost (C+E)				3,045,564.21
G. Overhead, Contingencies and Miscellaneous			10% per D.O 197 s 2016	304,556.42
H. Contractor's Profit (CP)			8% per D.O 197 s 2016	243,645.14
I. Value Added Tax (VAT)			5%	179,688.29
J. Total Unit Cost				286.93

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 105 (1)a Subgrade Preparation

Unit of Measurement : sq.m.

Output per hour : 300.00

Quantity : 23,648.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	9.85	611.92	6,029.45
b. Laborer	2	9.85	342.24	6,744.41
Sub-total for A				P 12,773.86
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Road Grader	1	9.85	17,384.00	171,290.35
b. Road Roller	1	9.85	13,216.00	130,221.65
c. Water Truck	1	2.46	19,600.00	48,281.33
Sub-total for B				P 349,793.33
Total (A+B)				P 362,567.19
D. Output/day	2,400.00 sq.m./day			
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a.				
Sub-total for E				P 0.00
Direct Cost (C+E)				362,567.19
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016 36,256.72
Contractor's Profit (CP)				8% per D.O 197 s 2016 29,005.38
Value Added Tax (VAT)				5% 21,391.46
Total Unit Cost				19.00

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 200 (1) Aggregate Subbase Course

Unit of Measurement : cu.m.

Output per hour : 50.00

Quantity : 12.837.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	32.09	611.92	19,638.04
b. Laborer	2	32.09	342.24	21,966.67
Sub-total for A				P 41,604.72
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Road Grader	1	32.09	17,384.00	557,896.02
b. Road Roller	1	32.09	13,216.00	424,134.48
c. Water Truck	1	32.09	19,600.00	629,013.00
Sub-total for B				P 1,611,043.50
Total (A+B)				P 1,652,648.22
D. Output/day	400.00	cu.m.	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Aggregate Subbase Course (w/ Shrinkage of 15%)	16,046.25	cu.m.	1,056.30	16,949,653.88
Sub-total for E				P 16,949,653.88
Direct Cost (C+E)				18,602,302.09
G. Overhead, Contingencies and Miscellaneous	10% per D.O 197 s 2016			1,860,230.21
H. Contractor's Profit (CP)	8% per D.O 197 s 2016			1,488,184.17
I. Value Added Tax (VAT)	5%			1,097,535.82
J. Total Unit Cost				1,795.45

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 300 (1) Aggregate Surface Course

Unit of Measurement : cu.m.

Output per hour : 50.00

Quantity : 889.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	2.22	611.92	1,360.76
b. Laborer	2	2.22	342.24	1,522.11
Sub-total for A				P 2,882.87
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Road Grader	1	2.22	17,384.00	38,657.67
b. Road Roller	1	2.22	13,216.00	29,389.08
c. Water Truck	1	0.56	19,600.00	10,896.38
Sub-total for B				P 78,943.13
Total (A+B)				P 81,825.99
D. Output/day	400.00	cu.m.	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Aggregate Surface Course (w/ shrinkage of 15%)	1,022.93	cu.m.	1,231.30	1,259,527.55
Sub-total for E				P 1,259,527.55
Direct Cost (C+E)				1,341,353.55
G. Overhead, Contingencies and Miscellaneous	10% per D.O 197 s 2016			134,135.35
H. Contractor's Profit (CP)	8% per D.O 197 s 2016			107,308.28
I. Value Added Tax (VAT)	5%			79,139.86
J. Total Unit Cost				1,868.39

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 311(1)ela Portland Cement Concrete Pavement-using Conventional Method, 0.28m thick

Unit of Measurement : sq.m.

Output per hour : 57.70

Quantity : 23,315.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	50.51	611.92	30,908.19
b. Skilled	4	50.51	443.20	89,544.45
c. Laborer	12	50.51	342.24	207,439.26
Sub-total for A				P 327,891.90
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Transit Mixer	4	50.51	10,544.00	2,130,317.44
b. Concrete Vibrator	2	50.51	730.00	73,744.87
c. Batching Plant	1	50.51	14,076.00	710,981.32
d. Pay Loader	1	50.51	13,864.00	700,273.16
e. Concrete Screeder	1	50.51	4,360.00	220,224.39
f. Water Truck	1	50.51	19,600.00	989,999.57
g. Concrete Saw	1	50.51	261.04	13,185.18
h. Bar Cutter	1	5.05	1,758.00	8,879.69
Minor Tools (5% of labor)				16,394.59
Sub-total for B				P 4,864,000.21
Total (A+B)				P 5,191,892.11
C. Output/day	461.60	sq.m.	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Reinforcing Steel Bar	11,657.75	kg	41.00	477,967.75
b. Curing Compound	6,761.50	lit	40.00	270,459.80
c. Asphalt Sealant	3,963.64	lit	75.00	297,272.63
d. Sand	3,590.59	cu.m	1,206.30	4,331,325.10
e. Gravel	6,528.34	cu.m	1,156.30	7,548,719.54
f. Cement	62,019.23	bag	291.84	18,099,904.50
g. Concrete Saw	3.50	pc	8,000.00	27,978.60
h. Pipe Sleeve, 2" dia.	181.86	l.m	133.00	24,187.50
i. Grease/Tar	181.86	lit	21.00	3,819.08
j. Steel Forms	10,725.13	lit	60.00	643,507.80
Sub-total for E				P 31,725,142.29
Direct Cost (C+E)				36,917,034.40
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016 3,691,703.44
Contractor's Profit (CP)				8% per D.O 197 s 2016 2,953,362.75
Value Added Tax (VAT)				5% 2,178,105.03
Total Unit Cost				1,961.79

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 311(1)a Portland Cement Concrete Pavement, 0.15m. Thick

Unit of Measurement : sq.m

Output per hour : 107.33

Quantity : 4,592.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	5.35	611.92	3,272.54
b. Skilled	4	5.35	443.20	9,480.92
c. Laborer	12	5.35	342.24	21,963.56
Sub-total for A				P 34,717.03
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Transit Mixer	4	5.35	10,544.00	225,556.92
b. Concrete Vibrator	2	5.35	730.00	7,808.07
c. Batching Plant	1	5.35	14,076.00	75,278.34
d. Pay Loader	1	5.35	13,864.00	74,144.56
e. Concrete Screeder	1	5.35	4,360.00	23,317.25
f. Water Truck	1	5.35	19,600.00	104,820.65
g. Concrete Saw	1	5.35	261.04	1,396.04
h. Bar Cutter	1	0.53	1,758.00	940.18
Minor Tools (5% of Labor)				25,663.10
Sub-total for B				P 538,925.10
Total (A+B)				P 573,642.12
C. Output/day	858.64 sq.m /day			
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Reinforcing Steel Bar	1,515.36	kg	41.00	62,129.76
b. Curing Compound	1,331.68	lit	40.00	53,267.20
c. Asphalt Sealant	551.04	lit	75.00	41,328.00
d. Steel Form	2,112.32	l.m	40.00	84,492.80
e. Sand	378.84	cu.m	1,206.30	456,994.69
f. Gravel	688.80	cu.m	1,156.30	796,459.44
g. Cement	6,566.56	bag	291.84	1,916,407.36
h. Concrete Saw	0.69	pc	8,000.00	5,510.40
i. Pipe Sleeve, 1" dia.	35.82	l.m	133.00	4,763.74
j. Grease/Tar	6.89	lit	21.00	144.65
Sub-total for E				P 3,421,498.04
Direct Cost (C+E)				3,995,140.16
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016 399,514.02
Contractor's Profit (CP)				8% per D.O 197 s 2016 319,611.21
Value Added Tax (VAT)				5% 235,713.27
Total Unit Cost				1,077.96

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 404 (1)a Reinforcing Steel Bar, Grade 40

Unit of Measurement : kg.

Output per hour : 180.00

Quantity : 14,445.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	10.03	611.92	6,138.32
b. Skilled Laborer	2	10.03	443.20	8,891.70
c. Laborer	8	10.03	342.24	27,464.76
Sub-total for A				P 42,494.78
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2009 ACEL Rates)				
a. Bar Cutter	1	5.02	1,758.00	8,817.47
b. Bar Bender	1	5.02	2,812.00	14,103.94
c. Cargo Truck	1	1.50	6,264.00	9,425.36
Sub-total for B				P 32,346.77
Total (A+B)				P 74,841.55
D. Output/day	1,440.00 kg. /day			
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Tie Wire	303.35	kg	68.00	20,627.46
b. Reinforcing Steel Bar, Grade 40	15,167.25	kg	41.00	621,857.25
Sub-total for E				P 642,484.71
Direct Cost (C+E)				717,326.26
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				61.53

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 405 (1) a3 Structural Concrete, Class A

Unit of Measurement : cu.m

Output per hour : 1.40

Quantity : 357.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	31.88	611.92	19,504.95
b. Skilled Laborer	4	31.88	443.20	56,508.00
c. Laborer	8	31.88	342.24	87,271.20
<i>Installation/Removal of Form Works</i>				
a. Skilled Laborer	4	31.88	443.20	56,508.00
b. Laborer	8	31.88	342.24	87,271.20
Sub-total for A				P 307,063.35
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. One Bagger Mixer	1	31.88	1,376.00	43,860.00
b. Concrete Vibrator	1	31.88	972.00	30,982.50
c. Water Truck	1	3.19	19,600.00	62,475.00
Minor Tools (5% of Labor)				15,353.17
Sub-total for B				P 152,670.67
Total (A+B)				P 459,734.02
D. Output/day	11.20	cu.m /day		
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Form Lumber	8,330.00	bd.ft	40.00	333,200.00
b. Plywood	190.40	pc	1,211.00	230,574.40
c. Assorted CW Nails	249.90	kg.	68.00	16,993.20
d. Portland Cement	3,391.50	bag	291.84	989,786.98
e. Sand	178.50	cu.m	1,206.30	215,324.55
f. Gravel	357.00	cu.m	1,156.30	412,799.10
Sub-total for E				P 2,198,678.23
Direct Cost (C+E)				2,658,412.24
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				9,226.25

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 500(1)b3 Pipe Culvert & Storm Drain

Unit of Measurement : ln.m

Output per hour : 1.00

Quantity : 123.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	15.38	611.92	9,408.27
b. Skilled Laborer	2	15.38	443.20	13,628.40
c. Laborer	4	15.38	342.24	21,047.76
Sub-total for A				P 44,084.43
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Backhoe	1	7.69	12,296.00	94,525.50
b. Plate Compactor	1	7.69	984.00	7,564.50
Minor Tools (10% of Labor)				4,408.44
Sub-total for B				P 106,498.44
Total (A+B)				P 150,582.87
D. Output/day	8.00	ln.m	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Portland Cement	132.84	bag	291.84	38,768.48
b. Sand	7.50	cu.m	1,206.30	9,050.87
c. RC Pipes (910 mm dia.)	123.00	pc	2,200.00	270,600.00
d. Sand Bedding	15.74	cu.m	1,206.30	18,991.99
Sub-total for E				P 337,411.34
Direct Cost (C+E)				487,994.21
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				4,915.65

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 505(2)a Grouted Riprap, Class A

Unit of Measurement : cu.m

Output per hour : 1.25

Quantity : 28.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	2.85	611.92	1,743.97
b. Skilled Laborer	2	2.85	443.20	2,526.24
c. Laborer	8	2.85	342.24	7,803.07
Sub-total for A				P 12,073.28
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. One Bagger Mixer	1	2.85	1,376.00	3,921.60
b. Water Truck	1	1.14	19,600.00	22,344.00
Minor Tools (5% of Labor)				603.66
Sub-total for B				P 26,869.26
Total (A+B)				P 38,942.55
D. Output/day 10.00 cu.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Cement	85.50	bag	291.84	24,952.61
b. Sand	7.13	cu.m	1,206.30	8,594.89
c. Gravel Fill	0.43	cu.m	1,156.30	494.32
d. Weep Holes (PVC), 2" dia.	8.55	ln.m	133.00	1,137.15
e. Filter Cloth	0.43	sq.m	160.00	68.40
f. Boulders	29.93	cu.m	1,430.30	42,801.73
Miscellaneous (1% of Materials)				780.49
Sub-total for E				P 78,829.59
Direct Cost (C+E)				117,772.14
G. Overhead, Contingencies and Miscellaneous		10% per D.O 197 s 2016		11,777.21
H. Contractor's Profit (CP)		8% per D.O 197 s 2016		9,421.77
I. Value Added Tax (VAT)		5%		6,948.56
J. Total Unit Cost				5,119.99

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 506(1) Stone Masonry
Unit of Measurement : cu.m
Output per hour : 1.56
Quantity : 101.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	8.08	611.92	4,944.31
b. Skilled Laborer	2	8.08	443.20	7,162.11
c. Laborer	8	8.08	342.24	22,122.39
Sub-total for A				P 34,228.82
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. One Bagger Mixer	1	8.08	1,376.00	11,118.08
b. Water Truck	1	0.40	19,600.00	7,918.40
c. Backhoe	1	0.81	12,296.00	9,935.17
Minor Tools (10% of Labor)				3,422.88
Sub-total for B				P 32,394.53
Total (A+B)				P 66,623.35
Output/day 12.50 cu.m /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Cement	555.50	bag	291.84	162,119.02
b. Sand	30.30	cu.m	1,206.30	36,550.89
c. Gravel Fill	2.02	cu.m	1,156.30	2,335.73
d. Weep Holes (PVC)	30.30	ln.m	133.00	4,029.90
e. Filter Cloth	1.52	sq.m	160.00	242.40
f. Boulders	106.05	cu.m	1,430.30	151,683.32
Miscellaneous (1% of Materials)				3,569.61
Sub-total for E				P 360,530.87
Direct Cost (C+E)				427,154.22
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				5,240.04

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : 612(1) ReflectORIZED Thermoplastic Pavement Markings (White)

Unit of Measurement : sq.m

Output per hour : 25.00

Quantity : 775.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	3.88	611.92	2,372.72
b. Skilled Laborer	2	3.88	443.20	3,437.02
c. Laborer	6	3.88	342.24	7,962.21
Sub-total for A				P 13,771.95
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACCEL Rates)				
a. Cargo Truck/Delivery Truck	1	3.88	9,696.00	37,596.24
b. Applicator Machine	1	3.88	750.00	2,908.13
c. Kneading Machine	1	3.88	1,500.00	5,816.25
Minor Tools (10% of labor)				
Sub-total for B				P 46,320.62
Total (A+B)				P 60,092.56
D. Output/day	200.00	sq.m	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Thermoplastic Paint (white)	252.04	bag	1,585.00	399,479.44
b. Glass Beads	25.59	bag	2,500.00	63,978.75
c. Primer	93.06	liter	180.00	16,750.80
d. LPG (50 kg.)	3.10	cyl	90.00	279.18
e. LPG (12 kg.)	1.55	cyl	50.00	77.55
f. Calsumine	96.94	kg	5.00	484.69
Miscellaneous (5% of Materials)				24,052.52
Sub-total for E				P 505,102.93
Direct Cost (C+E)				565,195.49
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				903.00

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description

: 612(2) ReflectORIZED Thermoplastic Pavement Markings (Yellow)

Unit of Measurement

: sq.m

Output per hour

: 25.00

Quantity

: 211.50

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	1.06	611.92	647.11
b. Skilled Laborer	2	1.06	443.20	937.37
c. Laborer	6	1.06	342.24	2,171.51
Sub-total for A				P 3,755.99
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Cargo Truck/Delivery Truck	1	1.06	9,696.00	10,253.52
b. Applicator Machine	1	1.06	750.00	793.13
c. Kneading Machine	1	1.06	1,500.00	1,586.25
Minor Tools (10% of labor)				
Sub-total for B				P 12,632.90
Total (A+B)				P 16,388.88
D. Output/day	200.00	sq.m	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Thermoplastic Paint (yellow)	68.74	bag	1,800.00	123,727.50
b. Glass Beads	6.98	bag	2,500.00	17,448.75
c. Primer	25.38	liter	233.00	5,913.54
d. LPG (50 kg.)	0.85	cyl	90.00	76.14
e. LPG (12 kg.)	0.42	cyl	50.00	21.15
f. Calsumine	26.44	kg	5.00	132.19
Miscellaneous (5% of Materials)				7,365.96
Sub-total for E				P 154,685.23
Direct Cost (C+E)				171,074.11
Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
Contractor's Profit (CP)				8% per D.O 197 s 2016
Value Added Tax (VAT)				5%
Total Unit Cost				1,002.18

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte 3rd DEO

Item No./Description : A.1.1(3) Const. of Field Office for the Engineer

Unit of Measurement : LS

Output per hour :

Quantity : 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	10.00	611.92	6,119.20
b. Masons	3	10.00	443.20	13,296.00
c. Carpenters	3	10.00	443.20	13,296.00
d. Laborers	6	10.00	342.24	20,534.40
Sub-total for A				
			P	53,245.60
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACCEL Rates)				
a. Bagger Mixer	1	5.00	1,376.00	6,880.00
b. Water Truck	1	1.00	19,600.00	19,600.00
Minor Tools (10% of Labor)				5,324.56
Sub-total for B				
			P	31,804.56
Total (A+B)				
			P	85,050.16
C. Output/day	0.00 LS /day			
D. Output/day	0.00 LS /day			
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
I. Earthworks (Excavation, Embankment, Bedding)				
a. Gravel Bedding	3.50	cu.m	1,156.30	4,047.05
b. Selected Fill	10.00	cu.m	601.40	6,014.00
c. Soil Poisoning	2.50	lit	1,900.00	4,750.00
II. Concrete Works (Footing, Columns, Beams & Slab on Grade)				
a. Portland Cement	90.00	bag	291.84	26,265.91
b. Crushed Gravel	20.00	cu.m	1,156.30	23,126.00
c. Washed Sand	17.00	cu.m	1,206.30	20,507.10
III. Reinforcing Bars (Footing Columns, Beams, & Slabs on Grade)				
a. Deformed Round Bar, Grade 40	500.00	kg	40.00	20,000.00
b. No. 16 GI Tie Wire	20.00	kg	68.00	1,360.00
IV. Formworks (Columns & Beams)				
a. Coco Lumber	400.00	bd.ft	15.00	6,000.00
b. Ordinary Plywood, 1/4"x4'x8'	18.00	pc	520.00	9,360.00
c. CWN, Assorted	5.00	kg	44.00	220.00
V. Masonry Works (masonry walls & plastering)				
a. CHB 6" thk	650.00	pc	18.00	11,700.00
b. Portland Cement	50.00	bag	291.84	14,592.17
c. Washed Sand	10.00	cu.m	1,206.30	12,063.00
d. 10mm dia. X 6m RSB	75.00	kg	43.00	3,225.00
e. No. 16 GI Tie Wire	2.50	kg	81.00	202.50
VI. Doors and Windows				
a. D-1, Hollow Core Flush Type swing door, complete w/ accessories, 0.90mx2.1m	2.00	set	1,765.27	3,530.54
b. W-1, Jalousie window, 1.4m x 1.2m	2.00	set	924.00	1,848.00
c. W-2, Jalousie window, 2.8m x 1.2m	2.00	set	1,848.00	3,696.00
Sub-Total for E				
			P	172,507.27
Sub-total for E				
			P	316,033.62
Sub-total for E				
			P	401,083.78
F. Direct Cost (C+E)				
G. Overhead, Contingencies and Miscellaneous	10% per D.O 197 s 2016			
				40,108.38
H. Contractor's Profit (CP)	8% per D.O 197 s 2016			
				32,086.70
I. Value Added Tax (VAT)	5%			
				23,663.94
J. Total Unit Cost				496,942.80

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte 3rd DEO

Item No./Description : A.1.1(3) Const. of Field Office for the Engineer

Unit of Measurement : LS

Output per hour :

Quantity : 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	16.00	611.92	
b. Masons	3	16.00	443.20	
c. Carpenters	3	16.00	443.20	
d. Laborers	6	16.00	342.24	
Sub-total for A				P 0.00
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Bagger Mixer	1	5.00	1,376.00	
b. Water Truck	1	1.00	19,600.00	
Minor Tools (10% of Labor)				
Sub-total for B				P 0.00
Total (A+B)				P 0.00
C. Output/day	0.00	LS	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
VII Steel Works				
a. 65 x 65 x 6mm. L	300.00	kg	48.00	14,400.00
b. 50 x 50 x 6mm. L	200.00	kg	48.00	9,600.00
c. 50 x 50 x 4mm. L	100.00	kg	48.00	4,800.00
d. Purlins C- 150 x 50 x 3mm.	19.00	kg	45.00	855.00
e. 16mm dia. Cross bracing	32.00	kg	50.00	1,600.00
f. 16mm dia. Turn buckle	15.00	pc	123.00	1,845.00
g. 12mm thk base plate	22.00	kg	45.00	990.00
h. 10mm thk batten plate	15.00	kg	45.00	675.00
i. 10mm dia. Sag rod	7.50	kg	50.00	375.00
j. 20mm dia. X 350 mm anchor bolts	7.00	pc	60.00	420.00
k. Welding Rod	12.50	kg	125.00	1,562.50
l. Primer, Zinc Chromate	5.00	gal	531.00	2,655.00
VII Roofing Works				
a. Pre-painted GI Roofing Sheet long span	55.00	sq.m	420.00	23,100.00
b. Pre-painted ridge roll ga 24, 0.60m width	10.00	ln.m	189.00	1,890.00
c. Pre-painted flashing, ga. 24	2.00	ln.m	189.00	378.00
d. Teckscrew 1 1/2"	500.00	pc	1.25	625.00
e. Roof Sealant	2.00	lit	242.84	485.68
IX. Carpentry Works				
a. Rough Lumber, sun dried tangle	350.00	bd.ft	37.00	12,950.00
b. Plywood, ordinary 1/4" x 4' x 8'	30.00	pc	350.00	10,500.00
c. Finishing Nails	5.00	kg	74.00	370.00
d. Common Wire Nails	10.00	kg	74.00	740.00
e. Wood Preservative Brown	5.00	lit	900.00	4,500.00
Sub-Total for E				95,316.18
Sub-total for E				P 95,316.18
Direct Cost (C+E)				
G. Overhead, Contingencies and Miscellaneous				10% per D.O 197 s 2016
H. Contractor's Profit (CP)				8% per D.O 197 s 2016
I. Value Added Tax (VAT)				5%
J. Total Unit Cost				

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte 3rd DEO

Item No./Description : A.1.1(3) Const. of Field Office for the Engineer

Unit of Measurement : LS

Output per hour :

Quantity : 1.00

Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
X. Electrical Works				
a. 2 x 40w Fluorescent lighting fixtures	5.00	set	1,500.00	7,500.00
b. Porcelain Ceiling Outlet w/ female	2.00	pc	50.00	100.00
c. duplex Convenience outlet	3.00	pc	170.00	510.00
d. two gang switch	3.00	pc	132.00	396.00
e. 3.5mm2 thw	3.00	roll	3,600.00	10,800.00
f. 8.00mm2 thw	25.00	m	69.33	1,733.25
g. 15mm dia. PVC pipe	20.00	pc	76.00	1,520.00
h. 15mm dia. PVC Coupling	25.00	pc	27.00	675.00
i. 15mm dia. PVC Elbow	25.00	pc	26.00	650.00
j. 15mm dia. PVC Clamp	55.00	pc	8.00	440.00
k. 20mm dia. RSC Pipe	4.00	pc	240.00	960.00
l. 20mm dia. RSC Coupling	3.00	pc	36.00	108.00
m. 20mm dia. RSC elbow	3.00	pc	30.00	90.00
n. 20mm dia. RSC Clamp	10.00	pc	18.00	180.00
o. 20mm dia. Service entrance cap	2.00	pc	101.49	202.98
p. wire holder	2.00	pc	50.00	100.00
q. utility box	7.00	pc	32.00	224.00
r. octagonal box	8.00	pc	34.00	272.00
s. electrical tape (big)	7.00	pc	28.00	196.00
t. panel board (side main w/ braches)	2.00	set	3,000.00	6,000.00
XI. Plumbing Works				
a. Water Closet (include. Fitting & Accessories)	1.00	set	7,631.94	7,631.94
b. Lavatory (include fitting & Accessories)	1.00	set	5,000.00	5,000.00
c. 1/2" GI Pipe S-40	2.00	pc	292.00	584.00
d. 1/2" Water Faucet	2.00	pc	165.00	330.00
e. 1/2" Assorted Connector	8.00	pc	19.00	152.00
f. 4" PVC series 1000	1.00	pc	640.00	640.00
g. 2" PVC series 1000	1.00	pc	305.00	305.00
h. 4" PVC assorted Connector	6.00	pc	77.00	462.00
i. 2" PVC assorted Connector	8.00	pc	56.00	448.00
Sub-Total for E				48,210.17
Sub-total for E			P	48,210.17
F. Direct Cost (C+E)				
G. Overhead, Contingencies and Miscellaneous			10% per D.O 197 s 2016	
H. Contractor's Profit (CP)			8% per D.O 197 s 2016	
I. Value Added Tax (VAT)			5%	
J. Total Unit Cost				

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte 3rd DEO

DETAILED UNIT PRICE ANALYSIS

Item No./Description

: A.1.1(11) Prov. Of Furniture, Equipment and Appliances for Field Engineer

Unit of Measurement

: LS

Output per hour

:

Quantity : 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A.				
Sub-total for A				
			P	0.00
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B.				
Sub-total for B				
			P	0.00
Total (A+B)				
			P	0.00
D. Output/day	0.00	LS	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Office Equipment/Facilities & Supplies				
a. Office Table, Executive type w/ chair	2.00	unit	7,000.00	14,000.00
b. 1/2" wooden office table	2.00	each	2,830.00	5,660.00
c. Drawing Table	2.00	unit	5,000.00	10,000.00
d. Electric Desk Fan	3.00	unit	1,370.00	4,110.00
e. Folding Beds, Good Quality	3.00	each	2,700.00	8,100.00
f. 6" sleeping beds w/ pillows and blanket	3.00	each	5,000.00	15,000.00
g. Double burner gas stove (Gasul)	1.00	unit	3,700.00	3,700.00
h. 10 cups Rice Cooker	1.00	unit	2,500.00	2,500.00
i. Aluminum Cookware	1.00	set	3,500.00	3,500.00
j. Plate, Glass, Spoon and fork	1.00	dozen	2,000.00	2,000.00
k. 6 seater dining table	1.00	each	2,800.00	2,800.00
l. Monoblock Backrest chair	2.00	dozen	2,500.00	5,000.00
m. Plastic Pail & Basin	2.00	pc	500.00	1,000.00
n. White Board	3.00	Unit	7,000.00	21,000.00
o. Bond Paper (Long)	20.00	ream	300.00	6,000.00
p. Bond Paper (Short)	20.00	ream	270.00	5,400.00
q. Yellow Pad	6.00	pad	35.00	210.00
r. White Board Marker	10.00	pc	75.00	750.00
s. Sign Pen (assorted color)	2.00	dozen	650.00	1,300.00
t. Ballpen (assorted color)	4.00	box	180.00	720.00
u. Mechanical Pencil	6.00	unit	350.00	2,100.00
v. Pencil Lead, No. 5	4.00	box	145.00	580.00
w. Puncher	1.00	Unit	253.32	253.32
x. Staple Pad w/ wire	2.00	Unit	275.00	550.00
y. Cutter Blade	2.00	box	240.00	480.00
z. Scotch Tape	10.00	roll	45.00	450.00
aa Brown Envelop	7.00	dozen	125.00	875.00
bb Folder, Long	7.00	dozen	85.00	595.00
cc Folder, Short	7.00	dozen	70.00	490.00
dd Data File Folder	12.00	pc	85.00	1,020.00
ee Desktop w/ complete accessories	1.00	unit	60,000.00	60,000.00
ff Printer (3in1)	1.00	unit	20,000.00	20,000.00
gg Camera	2.00	unit	15,000.00	30,000.00
Lighting/Water Fixtures				
a. Electric Bill	4.60	mons	1,200.00	5,520.00
b. Water Bill	4.60	mons	1,000.00	4,600.00
c. LPG Gasul (11 kg)	4.60	mons	1,000.00	4,600.00
Sub-Total for E				
			P	244,863.32
Sub-total for E				
			P	244,863.32
F. Direct Cost (C+E)				
G. Overhead, Contingencies and Miscellaneous				
			per D.O 197 s 2016	
H. Contractor's Profit (CP)			per D.O 197 s 2016	
I. Value Added Tax (VAT)		5%		12,243.17
J. Total Unit Cost				257,106.49

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description

: A.1.2(5) Operation & Maintenance of Gov't. Service Vehicle

Unit of Measurement

: L.S

Output per hour

:

Quantity

: 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Service Driver	1	207.00	443.20	91,742.40
Sub-total for A				
		P		91,742.40
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
Sub-total for B				
		P		0.00
Total (A+B)				
		P		91,742.40
D. Output/day	0.00	L.S	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Liters, Diesel Fuel	2,070.00	liters	35.00	72,450.00
b. Engine Oil & Lubricants	1.00	ls	22,935.60	22,935.60
c. Tires	4.00	pcs	9,500.00	38,000.00
d. Spare parts etc.	1.00	ls	100,000.00	100,000.00
Sub-total for E				
		P		233,385.60
Direct Cost (C+E)				
				325,128.00
G. Overhead, Contingencies and Miscellaneous		0% per D.O 197 s 2016		0.00
H. Contractor's Profit (CP)		0% per D.O 197 s 2016		0.00
I. Value Added Tax (VAT)		5%		16,256.40
J. Total Unit Cost				341,384.40

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : B.5 Project Billboard

Unit of Measurement : Unit

Output per hour :

Quantity : 2.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Construction Foreman	1	0.25	611.92	152.98
b. Carpenters	1	0.25	443.20	110.80
c. Laborer	2	0.25	342.24	171.12
Sub-total for A				P 434.90
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
Sub-total for B				P 0.00
Total (A+B)				P 434.90
D. Output/day	0.00	Unit /day		
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Marine Plywood 3/16" thk. X 4' x 8'	2.00	pc	345.00	690.00
b. Tarpaulin (4' x 8')	2.00	pc	800.00	1,600.00
c. Assorted Sizes Lumber	100.00	bd. Ft	15.00	1,500.00
d. Assorted Sizes CW Nails	2.00	kg	44.00	88.00
Sub-total for E				P 3,878.00
Direct Cost (C+E)				4,312.90
G. Overhead, Contingencies and Miscellaneous	10%	per D.O 197 s 2016		431.29
H. Contractor's Profit (CP)	8%	per D.O 197 s 2016		345.03
I. Value Added Tax (VAT)	5%			254.46
J. Total Unit Cost				2,671.84

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : B.7 Occupational Safety & Health Program

Unit of Measurement : L.S

Output per hour :

Quantity : 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
a. Safety Practitioner	1	103.50	611.92	63,333.72
b. First Aider	1	207.00	443.20	91,742.40
Sub-total for A				P 155,076.12
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
Sub-total for B				P 0.00
Total (A+B)				P 155,076.12
D. Output/day	0.00	L.S /day		
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Pairs, Rubber Boots Men, Long with Steel Toe, Black	24.00	pair	400.00	9,600.00
b. Pairs, Working Gloves (Maong Materials)	24.00	pair	15.00	360.00
c. Pcs. Rain Coats (Rain Forced, Hip Length Small, Medium & Large)	24.00	pcs	100.00	2,400.00
Sub-total for E				P 12,360.00
Direct Cost (C+E)				167,436.12
Overhead, Contingencies and Miscellaneous				per D.O 197 s 2016 0.00
Contractor's Profit (CP)				8% per D.O 197 s 2016 13,394.89
Value Added Tax (VAT)				5% 9,041.55
Total Unit Cost				189,872.56

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME : Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description : B.9 Mobilization and Demobilization

Unit of Measurement : L.S

Output per hour :

Quantity : 1.00

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor				
Sub-total for A				P 0.00
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment, (2014 ACEL Rates)				
a. Low Bed Trailer	2	4.00	34,043.00	272,344.00
b. Water Truck	1	4.00	19,600.00	78,400.00
c. Backhoe	1	4.00	12,296.00	49,184.00
d. Payloader	2	4.00	13,864.00	110,912.00
e. Dumptruck	2	4.00	11,360.00	90,880.00
f. Bullduzer	1	4.00	27,032.00	108,128.00
g. Road Roller	1	4.00	13,216.00	52,864.00
h. Road Grader	1	4.00	17,384.00	69,536.00
Sub-total for B				P 832,248.00
Total (A+B)				P 832,248.00
D. Output/day 0.00 L.S /day				
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
Sub-total for E				P 0.00
Direct Cost (C+E)				832,248.00
G. Overhead, Contingencies and Miscellaneous		per D.O 197 s 2016		0.00
H. Contractor's Profit (CP)		per D.O 197 s 2016		0.00
I. Value Added Tax (VAT)	5%			41,612.40
J. Total Unit Cost				873,860.40

DETAILED UNIT PRICE ANALYSIS

PROJECT NAME

: Paving of Unpaved Road Rizal - Dakak - Dapitan Coastal Loop Road, Zamboanga del Norte
3rd DEO

Item No./Description

: B.4(1) Construction Survey and Staking

Unit of Measurement

: Km.

Output per hour

: 0.04

Quantity

: 3.24

Designation	No. of Person	No. of Days	Daily Rate	Amount
A. Labor (For Field Works)				
a. Geodetic Engineer	1	10.81	833.31	9,008.08
b. Skilled Laborer	3	10.81	443.20	14,372.98
c. Laborer	3	10.81	342.24	11,098.84
(For Office Works)				
a. Geodetic Engineer	1	32.43	833.31	27,024.24
b. Skilled Laborer	2	32.43	443.20	28,745.95
Sub-total for A			P	90,250.10
Name and Capacity	No. of Equip.	No. of Days	Daily Rate	Amount
B Equipment. (2014 ACEL Rates)				
a. Total Station w/ complete accessories Minor Tools (10% of labor)	1	10.81	800.00	8,648.00
				9,025.01
Sub-total for B			P	17,673.01
Total (A+B)			P	107,923.11
Output/day	0.30	Km.	/day	
Name and Specifications	Quantity	Unit	Unit Cost	Amount
E. Materials				
a. Standard Stake Plan (800 mm x 910 mm)	35.00	pcs	200.00	7,000.00
b. Blue Printing	175.00	pcs	40.00	7,000.00
Miscellaneous (5% of Materials)				700.00
Sub-total for E			P	14,700.00
Direct Cost (C+E)				122,623.11
Overhead, Contingencies and Miscellaneous		10% per D.O 197 s 2016		12,262.31
Contractor's Profit (CP)		8% per D.O 197 s 2016		9,809.85
Value Added Tax (VAT)		5%		7,234.76
Total Unit Cost				46,848.61

UNIT COST ANALYSIS FOR HAULING COST FOR ALL AGGREGATES

Hauling Cost from the District Office to Site

Item No	: ALL AGGREGATES	Terrain	: Flat to Rolling
Quantity	: 1,000.00	Unit	: cu.m.
		Hauling Distance	: 5.00 km.
		Effective Working Hours	: 8.00 hrs.

Hauling	: Using 10.00 cu.m. capacity Dumptruck		
	Weight of Dumptruck (cap. 10.00 cu.m.)	: 16,000.00	kgs
	Unit Weight of Fine Aggrgates	: 1,640.00	kg/cu.m.
	Unit Weight of Course Aggrgates	: 1,534.00	kg/cu.m.

Maximum Volumeto be Carried per DT : 11.57 cu.m.

* Dumptruck (10 Wheeler) days computation : **TIME-MOTION ANALYSIS**

Speed when loaded	: 30.00	kph
Speed when unloaded	: 40.00	kph

$$\text{Loaded Running} = \frac{5.00 \times 60.00}{30.00} = 10 \text{ mins.}$$

$$\text{Unloaded Running} = \frac{5.00 \times 60.00}{40.00} = 7.5 \text{ mins.}$$

Loading & Unloading	= 5.00	mins.
Capacity of Dumptruck	= 10.00	cu.m.
Total Cycle Time	= 22.50	mins.

$$\text{No. of trips for Dumptruck per day} = \frac{8.00 \times 60.00}{22.50} = 21.33 \text{ trips}$$

$$\begin{aligned} \text{Dumptruck Daily Outpout} &= 10.00 \times 21.33 = 213.33 \text{ cu.m.} \\ \text{Using 4 Dumptruck} &= 213.33 \times 4.00 = 853.33 \text{ cu.m.} \end{aligned}$$

$$\text{No. of Days for Dumptruck} = \frac{1,000.00}{853.33} = 1.17 \text{ days}$$

EQUIPMENT USED: (2009 ACEL RATES)

$$4.00 - \text{Unit Dumptruck} @ \text{P } 10,816.00 / \text{day} \times 1.17 \text{ days} = \text{P } 50,700.00$$

$$\text{Sub-Total} \quad \text{P } 50,700.00$$

Estimated Quantity	= 1,000.00	cu.m.
Unit Cost	P 10.14	/cu.m/km. (unit cost hauling per cu.m. per km.)
Grand Total	P 50,700.00	
Equipment	P 50,700.00	
Labor	P	
Equipment	P	

ZAMBOANGA DEL NORTE 3RD DEO (using 2nd Quarter 2017)

	Hauling Distance	Unit Cost per cu.m/km	Hauling Cost per km.	Unit Price	Unit cost per cu.m.
Cost of Fine Aggregates	45.00	X 10.14	= 456.30	+ 750.00	= 1,206.30
Cost of Coarse Aggregates	45.00	X 10.14	= 456.30	+ 700.00	= 1,156.30
Cost of Item 200 Materials	45.00	X 10.14	= 456.30	+ 600.00	= 1,056.30
Cost of Item 201 Materials	45.00	X 10.14	= 456.30	+ 650.00	= 1,106.30
Cost of Item 300 Materials	45.00	X 10.14	= 456.30	+ 775.00	= 1,231.30
Cost of Boulders	45.00	X 10.14	= 456.30	+ 974.00	= 1,430.30
Cost of Embankment, Common Borrow	10.00	X 10.14	= 101.40	+ 400.00	= 501.40
Cost of Embankment, Selected Borrow	10.00	X 10.14	= 101.40	+ 500.00	= 601.40

UNIT COST DERIVATION FOR PORTLAND CEMENT

TOTAL QUANTITY REQUIREMENTS FOR PORTLAND CEMENT

Description	Quantity (Bags)
Portland Cement Concrete Pavement-using Conventional Method, 0.28m thick	62,019.23
Portland Cement Concrete Pavement, 0.15m. Thick	6,566.56
Structural Concrete, Class A	3,391.50
Grouted Riprap, Class A	85.50
Stone Masonry	555.50
Const. of Field Office for the Engineer	90.00
	50.00
Concrete Structure (Lean Concrete)	-
TOTAL	72,758.29

Quantity = 72,758.29 Bags

Delivery Charge = P 0.12 /bag/km

SITE	HAULING DISTANCE
Zamboanga del Norte 3rd DEO	
PROJECT SITE	50.00

* Average Hauling Distance from source to assumed stockpiling area:
say 50.00 km.

Delivery Charge = P 0.12 X 50.00
Delivery Charge = P 6.00 /bag

* Delivery Truck : 72,758.29 bags (hauling works)
20,000.00 kgs., (capacity per haul)
500.00 bags, (capacity per haul)

* Capacity of Laborers unloading bags of Cement from Delivery Truck:

Assume 10 laborers can unload 500.00 bags of Cement

*Dumptruck (10 Wheeler) days computation : **TIME - MOTION ANALYSIS**

Speed when loaded : 30.00 kph

Speed when unloaded : 40.00 kph

Loaded Running = $\frac{50.00 \times 60.00}{30.00}$ = 100 mins.

Unloading Running = $\frac{50.00 \times 60.00}{40.00}$ = 75 mins.

Loading & Unloading = 45.00 mins.

Capacity of Dumptruck = 8.00 cu.m.

500.00 bags

Total Cycle Time = 220.00 mins.

No. of trips for Dumptruck per day = $\frac{8.00}{220.00} \times 60.00 = 2.18$ trips

Dumptruck Daily Output = $500.00 \times 2.18 = 1,090.91$ cu.m.
 Using 4 Dumptruck = $1,090.91 \times 4.00 = 4,363.64$ cu.m.

No. of Days for Dumptruck = $\frac{72,758.29}{4,363.64} = 16.67$ days

No. of Days for Labor for unloading = complimentary to D.Truck days = 16.67 days

DELIVERY COST:

72,758.29 Bags, Portland Cement @ P 6.00 /bag = P 436,549.74
Sub-total

LABOR:

1 Foreman @ P 558.00 /day X 16.67 days = P 9,303.97
 10 Laborers @ P 312.24 /day X 16.67 days = P 52,062.19
Sub-total 61,366.16

MATERIALS:

72,758.29 Bags, Portland Cement @ P 285.00 /bag = P 20,736,112.65
Sub-total

Estimated Quantity : 72,758.29 Bags

Unit Cost P 291.84
 Grand Total P 21,234,028.55
 Delivery Cost P 436,549.74
 Labor P 61,366.16
 Materials P 20,736,112.65