Republic of the Philippines
DEPARTMENT OF PUBLIC WORKS AND HIGHWAYS
OFFICE OF THE SECRETARY
Manila

04 JUN 2018

MEMORANDUM

FOR : **MARK A. VILLAR**
Secretary
This Department

Respectfully submitted is the Memorandum dated May 11, 2018 of **Assistant Regional Director CAYAMOMBAO D. DIA** of DPWH-IX, favorably endorsing the request for Modification of **District Engineer NAJIB D. DILANGALEN, CEO VI**, Zamboanga Sibugay 2nd DEO to be implemented by the said District under FY2018 GAA, to wit:

As per GAA/Original			***As Modified***		
Project Description					
UACS No. 300116201170000 **Project ID: P00258450MN** Local Program Local Roads and Bridges - Local Roads - Construction / Repair / Rehabilitation / Improvement of Various Infrastructure including Local Projects Upgrading/Concrete Paving of Access Road to IBT Circumferential Road going to Taway, Ipil,Zamboanga Sibugay			Local Program Local Roads and Bridges - Local Roads - Construction / Repair / Rehabilitation / Improvement of Various Infrastructure including Local Projects Upgrading/Concrete Paving of Access Road to IBT Circumferential Road going to Taway, Ipil,Zamboanga Sibugay		
Physical Target	**Unit Cost**	**Allocation**	**Physical Target**	**Unit Cost**	**Estimated Cost**
CW-1 – Construction of Concrete Road: **6.0** Lane Km	₱ 4,900,000.00 / Lane Km	₱ 29.40 M	CW-1 – Construction of Concrete Road: **2.90726** Lane Km	₱ 10,112,614.63 / Lane Km	₱ 29.40 M
EAO	-	₱ 0.6 M	EAO	-	₱ 0.60 M
Total		**₱ 30 M**	**Total**		**₱ 30 M**

Justification:

- The physical target decreased from 6.0 lane kilometers to 2.90726 lane kilometers by adopting the 0.23-meter-thick, 6.10-meter-wide PCC Pavement instead of the standard for barangay roads which is 0.15-meter-thick and 5.0-meter-wide, since the project will serve as the access road for the Integrated Bus Terminal for the Municipality of Ipil.
- Inclusion of items 404, 405, 500, 505 & 506 for the Construction of Reinforced Concrete Line Canal, RCCP Cross drains and Grouted Riprap Slope Protection which constitutes 13.01% of the total project cost amounting P 3,767,829.07 to provide proper drainage and slope protection ensuring the preservation of the road.

Based on our evaluation, the submitted request for modification of the said project is in order; hence, approval hereof is recommended.

RAFAEL C. YABUT
Senior Undersecretary
Undersecretary for Mindanao Regional Operations

APPROVED/~~DISAPPROVED~~:

MARK A. VILLAR
Secretary

RAFAEL C. YABUT
Senior Undersecretary
Officer-In-Charge

2.1 NDJC/ACF/RCY

Department of Public Works and Highways
Office of the Secretary
WIN8C03111